



**Draft NEPA Environmental
Assessment
Westover Metropolitan Airport –
Modifications to Civil Aviation
Operations**

An environmental assessment prepared according to the National Environmental Policy Act and the U.S Air Force NEPA analysis process (EIAP)

July 5, 2018

Prepared for:

Westover Metropolitan Development
Corporation (WMDC)

Prepared by:

Stantec Consulting Services Inc.

Revision	Description	Author		Quality Check		Independent Review	



Project Cover Sheet

Draft NEPA Environmental Assessment Modification to Civil Air Operations at Westover Metropolitan Airport (CEF)

1. Applicant: Westover Metropolitan Development Corporation (WMDC)
2. Consultant Team: Stantec Consulting Services, Inc. and HNTB Corporation
3. Federal Agency: United States Air Force (USAF)
4. Federal Agency: Federal Aviation Administration (New England Division)
5. Report Title: **Draft** Environmental Assessment (Draft EA)
6. Additional Information: Further information on this document may be obtained from:

Stantec Consulting Services, Inc.

Attn: Randall P. Christensen – Senior Environmental Scientist


136 West Street, Suite 203

Northampton, MA 01060-3711

email: randy.christensen@stantec.com

phone: (413)584-4776

7. Proposed Action Summary: The Westover Metropolitan Development Corporation proposes the modification of civil aviation operations from the current 16 hours per day operation to 24 hours per day operation through the installation of additional communications equipment that will facilitate pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Furthermore, pilot interaction during non-towered operations will utilize a Common Traffic Advisory Frequency, a well-established Federal Aviation Administration communications procedure, thus assuring a continued level of safety during these non-towered civil aviation operations between the hours of 11:00PM and 7:00AM. The proposed action includes an average of 4 departures and 4 arrivals of civil aircraft during each non-towered operating period.
8. Project Alternatives: The Existing Condition (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low General Aviation (GA) Operations (2023) fleet mixes were developed based on information provided by the ATCT, and included potential new civil aircraft that would be introduced if the airport hours were extended from 16-hour to 24-hour. The following list provides a description of the project alternatives and associated assumptions for each alternative/scenario:
Existing Conditions represented the current state at WARB/CEF in 2018. The fleet mixes and operations represented the current aircraft types and associated operations for both military and civil operations. This baseline analysis reflects the reduced C-5 Galaxy fleet and the modified engines of the “M” model.
Short Term represented the first year (2019) when the airport operating hours would be extended from 16 hours per day to 24 hours per day. The fleet mixes and operations included potential new civil aircraft types and additional civil nighttime operations.
Future No Action (2023) assumed the airport would remain open for 16 hours per day in 2023. The fleet mix and operations included projected operations but no changes to the fleet mix or civil aviation operating hours.




Project Cover Sheet

Future Proposed Action (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023 for civil aviation operations. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 4 arrivals and 4 departures each night; a total of 8 civil operations.

Future Low GA Operations (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 2 arrivals and 2 departures each night, or half of the operations contained in the Future Proposed Action (2023). This scenario shows the resultant impacts if the full projected use of the extended operating hours was not realized.

9. Abstract: This EA was prepared by the Westover Metropolitan Development Corporation (WMDC) in accordance with the National Environmental Policy Act (NEPA) of 1969 (42 United States Code [USC] 4321 et seq.), as implemented by the Council on Environmental Quality (CEQ) regulations (40 Code of Federal Regulations [CFR] 1500–1508), and Air Force Instruction (AFI) 32-7061 and 32 CFR Part 989, “*The Environmental Impact Analysis Process*” (EIAP). WMDC has prepared this EA to determine potential environmental consequences of a modification to civil aviation operations at CEF, with an emphasis on changes in the extent of critical noise contours surrounding the airport relative to existing land uses and known sensitive receptors. WMDC assessed two alternatives to the proposed action; a “no action” alternative and a “low operations” alternative to properly evaluate the impacts of the proposed action. Critical environmental resources evaluated for the action focused on noise, land use and air quality. Since the project proposed no construction, soil disturbance, vegetation clearing or building demolition, several environmental resource categories were eliminated from detailed investigation for this EA.



July 5, 2018

Table of Contents

FINDING OF NO SIGNIFICANT IMPACT (DRAFT).....	I
ABBREVIATIONS	I
1.0 PURPOSE OF AND NEED FOR ACTION.....	1.1
1.1 PROJECT BACKGROUND AND RELEVANT DOCUMENTS	1.4
1.1.1 1987 USAF Environmental Impact Statement.....	1.4
1.1.2 1995 USAF Environmental Impact Statement.....	1.4
1.1.3 2003 and 2014 FAR Part 150 Noise Compatibility Planning Updates.....	1.6
1.1.4 Westover Metropolitan Airport 2008 Master Plan Update	1.7
1.1.5 KC-46A Third Main Operating Base (MOB 3) Beddown Environmental Impact Statement (EIS) - April 2017.....	1.7
1.1.6 Westover Air Reserve Base/Metropolitan Airport Noise Exposure Map (NEM) & Noise Compatibility Plan (NCP) Update (DRAFT June 2018)	1.8
2.0 PROPOSED ACTION AND ALTERNATIVES.....	2.11
3.0 AFFECTED ENVIRONMENT	3.12
3.1 SCOPE OF THE ENVIRONMENTAL ASSESSMENT	3.12
3.2 NOISE (ACOUSTIC ENVIRONMENT).....	3.15
3.3 AIR QUALITY	3.19
3.4 LAND USE	3.20
3.5 CULTURAL RESOURCES	3.20
4.0 ENVIRONMENTAL CONSEQUENCES	4.22
4.1 INTRODUCTION.....	4.22
4.2 NOISE	4.22
4.2.1 Existing Conditions (2018).....	4.22
4.2.2 Short Term Proposed Action (2019).....	4.23
4.2.3 Future No Action (2023)	4.23
4.2.4 Future Proposed Action (2023)	4.23
4.2.5 Future Low Civil Air Operations (2023)	4.23
4.2.6 Noise Contour Summary	4.23
4.2.7 Supplemental Noise Metrics.....	4.24
4.3 AIR QUALITY	4.25
4.4 LAND USE	4.26
4.5 CULTURAL RESOURCES	4.28
5.0 REFERENCES.....	5.29

LIST OF TABLES

Table 3-1: Generalized Land Uses within the Existing (2018) "No Action" Conditions - 65 DNL Noise Exposure Contour at WARB/CEF.....	3.15
Table 3-2: Generalized Land Uses within the Future (2023) "No Action" Conditions - 65 DNL Noise Exposure Contour at WARB/CEF	3.16



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

July 5, 2018


Table 3-3: Comparison of Land Area Within Critical Noise Contours Between the 2015 and 2018 Baseline Years for WARB/CEF	3.19
Table 4-1: Summary Table of Land Area Within the Critical Noise Contours for the Project Alternatives	4.24
Table 4-2: Clean Air Act Conformity Rule Emission Rate Thresholds for Maintenance Areas	4.25
Table 4-4: Air Pollutant Emission Comparison Between the No Action and Proposed Action Alternatives.....	4.26

LIST OF FIGURES

Figure 1-1 Vicinity Map	1.2
Figure 1-2 Airport Map	1.3
Figure 1-3 2014 NEM Update vs. 2018 NEM Update Noise Contours	1.10
Figure 3-1 Existing Conditions (2018) Noise Contours.....	3.17
Figure 3-2 Future Conditions (2023) Noise Contours	3.18
Figure 3-3 Land Use Plan	3.21
Figure 4-1 Proposed Action Noise Contours and Land Use Plan.....	4.27

LIST OF APPENDICES

APPENDIX A	2018 NEM/NCP UPDATE (DRAFT).....	A.1
APPENDIX B	CORRESPONDENCE.....	B.1
APPENDIX C	NOISE ANALYSIS – TECHNICAL MEMO	C.1



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

July 5, 2018

Finding of No Significant Impact (Draft)

Finding of No Significant Impact – Proposed Modification to Civil Aviation Operations at the Westover Air Reserve Base and Westover Metropolitan Airport. Chicopee, Massachusetts.

This Finding of No Significant Impact (FONSI) was prepared in accordance with the National Environmental Policy Act of 1969, the Council on Environmental Quality (CEQ) regulations (40 Code of Federal Regulations (CFR) 1500-1508), and the Air Force Environmental Impact Analysis Process (32 CFR 989). The decisions included in this FONSI are based upon information contained in the Environmental Assessment (EA), Modification to Civil Aviation Operations, Westover Metropolitan Airport (CEF) located in Chicopee, Massachusetts. The EA analyzed potential environmental consequences that could result from implementation of the Proposed Action (including two action Alternatives) or the No Action Alternative.

Purpose and Need - This Civil Aviation Action will extend the hours of civil aviation operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with the WMDC mission as established and defined in the 1974 WMDC enacting legislation (Massachusetts) which reads, in part, *“it is the purpose of the Westover Metropolitan Development Corporation created by this Act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment.”* Furthermore, this extension of operating hours will provide for flexibility in scheduling and capability to accommodate maintenance and weather delays considered necessary to facilitate development of civil aviation operations at CEF to levels sufficient to sustain an economically viable civil aviation program. This purpose is supported by the goals and objectives of the 2008 CEF Master Plan Update which includes improvement of civil air operations to assist the WMDC and CEF in becoming a self-sustaining entity.

Project Alternatives - The Existing Condition (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low General Aviation (GA) Operations (2023) fleet mixes were developed based on information provided by the ATCT, and included potential new civil aircraft that would be introduced if the airport hours were extended from 16-hour to 24-hour. The following list provides a description of the project alternatives and associated assumptions for each alternative/scenario:

Existing Conditions represented the current state at WARB/CEF in 2018. The fleet mixes and operations represented the current aircraft types and associated operations for both military and civil operations. This baseline analysis reflects the reduced C-5 Galaxy fleet and the modified engines of the “M” model.

Short Term represented the first year (2019) when the airport operating hours would be extended from 16 hours per day to 24 hours per day. The fleet mixes and operations included potential new civil aircraft types and additional civil nighttime operations.

Future No Action (2023) assumed the airport would remain open for 16 hours per day in 2023. The fleet mix and operations included projected operations but no changes to the fleet mix or civil aviation operating hours.

Future Proposed Action (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023 for civil aviation operations. The civil fleet mixes and operations included potential new civil



DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

July 5, 2018

aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 4 arrivals and 4 departures each night; a total of 8 civil operations.


Future Low GA Operations (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 2 arrivals and 2 departures each night, or half of the operations contained in the Future Proposed Action (2023). This scenario shows the resultant impacts if the full projected use of the extended operating hours was not realized.

EA Determination – The proposed modification to civil aviation operations at WARB/CEF was assessed relative to potential direct and indirect impacts to various sensitive environmental resources for a proposed action in the short term (2019) and long term (2023), and for “no action” alternative in the long term (2023). Furthermore, a reduced proposed action was also assessed. Based on the outcome of the impact assessment relative to the WMDC purpose and need, the Future (2023) Proposed Action of an average daily increase in non-towered nighttime operations of 4 arrivals and 4 departures (8 operations) was selected as the preferred alternative.

The proposed action involved no construction, demolition, soil or vegetation disturbance resulting in a narrowly focused scope for the EA. Noise, air quality, land use and cultural resources were determined to have potential impacts from the proposed action and thus were analyzed further in the EA. The following categories were found to be unlikely to be impacted by the proposed action and thus were eliminated from detailed investigation; topography, geology, soils (including protected farmland), water resources (including Wild and Scenic rivers), wetlands, floodplain, water quality, biological resources (including rare species), infrastructure, traffic congestion and transportation, solid waste generation, hazardous waste, safety and occupational health, socioeconomics, environmental justice, and children’s health and safety risks.

No significant impacts to the assessed resource categories were identified from the selected alternative. Detailed noise modeling was completed for all alternatives and no incompatible uses were identified within the proposed critical noise contours. The change in the noise contours due to the proposed action are minimal and do not encompass any residential areas or other sensitive receptors. Air quality conformity analysis resulted in compliance with the General Conformity rule should the area become a non-attainment area in the future. Currently the area is in attainment for the NAAQS and not subject to the General Conformity Rule.


Coordination and Public Involvement – Preparation of this EA involved consultation and coordination with several entities critical to the assessment of the scoped natural resource categories. Coordination with tribal and Massachusetts SHPOs on cultural resources and the Massachusetts Department of Environmental Protection and USEPA sources on air quality were completed. Noise contour generation included extensive local coordination with planning/zoning departments, as well as other officials and local planners through the Joint Land Use Study steering committee. The JLUS also represents a direct conduit to the concerned public through the Pioneer Valley Planning Commission; the PVPC conducts the JLUS steering committee meetings and provides information on the WARB through their website. The draft EA was distributed to the PVPC and JLUS and was placed in several public locations (libraries) within adjacent communities. A 30-day public comment period was advertised in a local (daily) newspaper, announced at a FAR Part 150 public meeting on July 5th, and advertised on various websites. Comments received were assessed and addressed in the Final version of the EA.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

July 5, 2018

Conclusion - In accordance with Council of Environmental Quality regulations implementing the National Environmental Policy Act of 1969 (as amended) and the USAF Environmental Impact Analysis Process, 32 CFR 989, the USAF concludes that the Proposed Action will have no significant impact on the quality of the natural or human environment and a FONSI is the appropriate level of NEPA determination; thus preparation of an Environmental Impact Statement (EIS) is not necessary.




**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

July 5, 2018

Abbreviations


ATCT	Air Traffic Control Tower
AICUZ	Air Installation Compatible Use Zone
AIM	Aeronautical Information Manual
CAA	Federal Clean Air Act
CEF	Westover Metropolitan Airport
CTAF	Common Traffic Advisory Frequency
DNL	Day-Night Noise Level
EA	Environmental Assessment (pursuant to NEPA)
EIS	Environmental Impact Statement (pursuant to NEPA)
FAA	Federal Aviation Administration
FONSI	Finding of No Significant Impact
EIAP	(USAF) Environmental Impact Analysis Process
JLUS	Joint Land Use Study
NAAQS	National Ambient Air Quality Standards
NEM	Noise Exposure Map
NEPA	National Environmental Policy Act 1969 (42 United States Code 4321 et seq.)
NCP	Noise Compatibility Program (pursuant to FAR Part 150)
Part 150	FAA Regulations 14 CFR Part 150, <u><i>Airport Noise Compatibility Planning</i></u>
PVPC	Pioneer Valley Planning Commission



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

July 5, 2018

ROD	Record of Decision (on an EIS)
USAF	United States Air Force
WARB	Westover Air Reserve Base
WMDC	Westover Metropolitan Development Corporation



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Purpose of and Need for Action
July 5, 2018

1.0 PURPOSE OF AND NEED FOR ACTION

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF) at the Westover Air Reserve Base (WARB), to modify civil aviation operations at CEF. Figure 1-1 provides the regional setting for WARB/CEF while Figure 1-2 provides a more detailed view of the airport layout.


This Civil Aviation Action will extend the hours of civil aviation operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with the WMDC mission as established and defined in the 1974 WMDC enacting legislation (Massachusetts) which reads, in part, *“it is the purpose of the Westover Metropolitan Development Corporation created by this Act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment.”* Furthermore, this extension of operating hours will provide for flexibility in scheduling and capability to accommodate maintenance and weather delays considered necessary to facilitate development of civil aviation operations at CEF to levels sufficient to sustain an economically viable civil aviation program. This purpose is supported by the goals and objectives of the 2008 CEF Master Plan Update which includes improvement of civil air operations to assist the WMDC and CEF in becoming a self-sustaining entity.

The extended hours of civil aviation operations are projected to result in an average daily increase of 4 arrivals and 4 departures of civil aircraft per each non-towered operating period. This total of 8 operations per each period of extended operations is the quantity used to calculate the potential for environmental impact in the various resource categories assessed in this EA.

This extension of civil aviation operation hours will be facilitated by installation of certain communications equipment that will provide for pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Radio communications for the nighttime operations will shift from ATCT-controlled communications to a Common Traffic Advisory Frequency (CTAF) per the procedures outlined in the Aeronautical Information Manual (AIM) Chapter 4 Section 1-9 Traffic Advisory Practices at Airports Without Operating Control Towers developed by the Federal Aviation Administration (FAA). This form of communication is utilized by operating aircraft throughout the country at non-towered airports. Regionally, Orange Municipal Airport (30 miles north), Southbridge Municipal Airport (26 miles east) and Northampton Airport (10 miles northwest) are examples of existing, active, non-towered airports supporting civil aviation that employ this communications method. Westfield-Barnes Regional Airport (10 miles west), a towered joint-use airport provides for nighttime civil aviation operations using the exact form of communications and pilot-activated lighting proposed for CEF.




Westover Air Reserve Base / Metropolitan Airport **NEPA EA**



LEGEND

- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

Vicinity Map
Figure 1-1







Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI

Westover Air Reserve Base / Metropolitan Airport NEPA EA



LEGEND

-  Westover Air Reserve Base Installation Area
-  Westover Metropolitan Development Corporation Aviation Property
-  County Boundary
-  Town Boundary

**Airfield Layout
Figure 1-2**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

Purpose of and Need for Action
July 5, 2018

The project as proposed would not result in disturbance to soils or vegetation, require any building demolition or modification, or require the installation of new structures or facilities. No physical construction activities are associated with the proposed action. No change in workforce would result from the proposed action. The physical action associated with the project is limited to the installation of the pilot communications equipment, thus allowing for the non-ATCT operations to commence. The equipment is installed in existing electrical vaults, navigational aids and the ATCT; no new trenching, ground disturbance or structures are necessary to accommodate the new equipment.

Procedural updates and changes to the airport data as maintained by the FAA would be necessary prior to the initiation of non-towered civil operations. Modification and update of the Joint-Use Agreement between the WMDC and the U.S. Air Force (USAF) would also be necessary; the current Joint-Use Agreement is dated April 1994 and does not provide for the scope of non-towered nighttime civil aviation operations defined in this EA.

1.1 PROJECT BACKGROUND AND RELEVANT DOCUMENTS

Several past planning and permitting processes and associated documents provide important background information for the proposed action of modifying civil aviation operations at CEF to include non-towered operations between the hours of 11:00PM and 6:00AM. A brief summary is provided of the more significant actions that have guided the current proposal and this investigation of environmental impact. The documents referenced in this section are generally available through the WARB and WMDC and the Pioneer Valley Planning Commission (PVPC). They are incorporated herein by reference only, as they are too voluminous to attach to the EA and much of the information is not pertinent to the proposed action.


1.1.1 1987 USAF Environmental Impact Statement

The WMDC has previously proposed changes to civil air operational hours at CEF to include 24-hour operations. An Environmental Impact Statement (EIS) in 1987 for the USAF/WARB mission change from C-130 to C-5A aircraft addressed a request by the WMDC to expand tower operations to 24 hours per day to permit development of civil aviation operations with emphasis, at that time, on cargo operations. The civil aviation project Purpose and Need in that EIS is substantially similar to that contained in this EA. The Record of Decision (ROD) for the 1987 EIS did not include an environmental determination for the civil air proposed action, thus the changes were not approved pursuant to NEPA. Of significance in the 1987 EIS was the modeling of the change in civil aviation operations concurrently with the proposed military change from the C-130 to the C-5A cargo aircraft. The impact on the critical noise contours resulting from the change in the military fleet mix resulted in locally significant expansion of noise contours, thus any additional operational increase (even civil operations) would only contribute to the already-significant environmental impacts of the proposed action. In particular, the critical noise contours extended well off the airport property for the proposed action and into noise-sensitive land uses.

The 1987 EIS is significant to this current EA due to the similarities in the Civil Aviation proposed action.

1.1.2 1995 USAF Environmental Impact Statement

In 1995 the USAF developed a Supplemental EIS providing for a re-assessment of air operations and procedures at the WARB in the wake of Operations Desert Shield and Desert Storm and associated changes in training operations. The two proposed actions in the 1995 SEIS included two proposed actions:



DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

Purpose of and Need for Action
July 5, 2018

Military Action - Evaluation of the impacts of current, projected, and potential military aircraft operations to permit optimum utilization of available resources while reducing associated impacts to the lowest practicable level consistent with maintenance of unit readiness and accomplishment of mission requirements in both peacetime and contingency operations.

Civil Aviation Action - Response to a revised request from the Westover Metropolitan Development Corporation (WMDC) to extend the hours of tower operations from the current 16 hours per day (hr/day) (7 a.m. to 11 p.m.) to 24 hr/day to facilitate development of civil aviation operations.

The Civil Aviation Action described in the 1995 EIS relied upon the control tower to be staffed and open 24 hours per day to facilitate the nighttime civil operations. In that proposal, the tower would not be staffed unless an aircraft were known to need the airport during the expanded hours. When needed, WMDC would request that the USAF schedule personnel to remain on duty or report early to accommodate the aircraft arrival or departure.


In 1995, WMDC believed that the immediate result would be to create a more flexible operating environment for the existing airport users. The long-term expectation was that the added flexibility would result in an increase in activity to the levels projected in a (then) new five-year aviation forecast through expansion of existing aviation services and possibly the attraction of new aviation services. At that time, the WMDC projected that civil aviation operations would increase to approximately 18,600 operations per year. 1995 civil aviation activity at CEF was reported to be less than 3,900 operations per year.

The Record of Decision (ROD) on the 1995 EIS signed on August 8, 1995 provided for the following relative to a change in civil aviation operations:

Expansion of hours for civil aviation flights is granted as detailed below, subject to the following conditions. This expansion of hours will not take place until after the Joint Use Agreement between WMDC and the US Air Force is revised or modified as necessary to incorporate the change in civil operations, including but not limited to, assumption of liability for any claims arising out of said expansion of hours of civil operations.

Currently, civil aircraft operations are authorized use during normal airfield operating hours (6:00 a.m. and midnight). Civil aircraft will be authorized to operate between midnight and 6:00 a.m. local time when required because of either, mechanical problems, air traffic delays, time constraints, etc. Flights will not be regularly scheduled for operation between midnight and 6:00 a.m. local time. When use is required between midnight and 6:00 a.m. local time, WMDC will request that the Air Force schedule personnel to remain on duty or report early to accommodate the civil aircraft arrival or departure. All civil aircraft operations are to be conducted consistent with the Joint Use Agreement then in force, FAA requirements, and mitigation measures adopted via the completed Massachusetts Environmental Policy Act (MEPA) and FAA FAR Part 150 processes.

The 1995 SEIS and the ROD discuss mitigation measures that were attached to this decision meant to reduce environmental impacts to acceptable levels and/or to minimize these impacts. Several of these measures were incorporated into later studies and documents to address aircraft noise on sensitive receptors surrounding the WARB. While the ROD provided for some civil aviation operations, the special conditions of the ROD limited the benefits of the decision relative to the WMDC objectives.



DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

Purpose of and Need for Action
July 5, 2018

The 1995 EIS is significant to this current EA due to the similarities in the proposed Civil Aviation action, and the EIS ROD that provided for some extension of the civil aviation operating hours. The impact assessment is dissimilar to the current EA in that the critical noise contours extended well off the WARB property into incompatible land uses at the time the EIS was prepared.

1.1.3 2003 and 2014 FAR Part 150 Noise Compatibility Planning Updates

14 CFR Part 150, *Airport Noise Compatibility Planning*, established the airport noise compatibility planning program and its guiding criteria was promulgated by the FAA in 1981. The regulation sets forth the requirements that program sponsors must develop a facility Noise Exposure Map (NEM) through identification of the current and anticipated noise exposure patterns at the airport, based on annual average conditions, using tools and methodologies prescribed by the regulation. Secondly, the sponsor may prepare a Noise Compatibility Program (NCP) for review and approval by the FAA to make noise mitigation projects eligible for federal funding. These mitigation projects may include property acquisition in areas of significant noise exposure, modification of flight patterns, structures, and facilities to mitigate noise, and sound insulation programs.


The Westover Metropolitan Development Corporation (WMDC) first completed an NEM and NCP under 14 CFR Part 150 for the Airport in 1994. An NEM/NCP was prepared in 1996, with updates conducted in 2003 and again in 2014. These provided important operational data for both military and civilian uses and updated the critical noise contours for the airport relative to sensitive environmental receptors. Significant changes in military operations typically prompted the updates such as the change in the critical aircraft, changes in operation numbers and/or a fleet size reduction. A Part 150 Study is the FAA's directed way to evaluate aircraft noise and land use compatibility. It is a voluntary aircraft noise and land use compatibility study that identifies existing and future aircraft noise levels, land use compatibility and develops alternatives to abate or mitigate aircraft noise over noise sensitive uses. WMDC has conducted several mitigation projects under their Part 150 program.

Of significance in these documents are the raw data and resultant NEMs for the WARB and CEF. The data includes aircraft identification, flight tracks, flight stage length, number of operations, time-of-day information and runway usage to develop the critical noise contours and determine the extent of incompatible land uses within the critical contours for the present day and the near-term future (5 years out from the base year of the NEM). These documents provide information regarding the extent of land use incompatibility for past operational years at WARB. Comparison of present day operations (2018) and proposed actions to these past NEMs is a critical measurement of relative environmental impact for the airport. In the past, the critical noise contours extended well off the WARB property and into incompatible land use areas. This is not the case for present day operations at WARB.

Additionally, the update of the NCP in these documents demonstrates progress on noise mitigation strategies. The NCP updates reflect completed mitigation tasks and identifies new mitigation approaches and targets to match changes in airport operations.

1.1.3.1 Joint Land Use Studies

Preceding the NEM/NCP updates and providing critical information for them are Joint Land Use Studies (JLUS). Managed by the Department of Defense (DoD) Office of Economic Adjustment (OEA), JLUS is a "cooperative land-use planning effort between affected local government and the military installation". The recommendations developed



DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

Purpose of and Need for Action
July 5, 2018

from the JLUS provide the policy framework to support adoption and implementation of compatible development near the WARB; often contributing greatly to the NCP language. JLUS operates under the premise that local land-use planning and zoning is one of the most effective tools available to resolve incompatible development issues. JLUS updates were prepared in 1990, 1995, 2004 and 2018, and were used extensively as information for the above-referenced NEM/NCP Updates. The JLUS Steering Committee (comprised of WARB, WMDC and municipal officials) working with the Pioneer Valley Planning Commission (PVPC) develop the JLUS updates. The individual updates are available at the PVPC website http://www.pvpc.org/westover_jlus.

The JLUS are significant reference documents for this EA, particularly for the update and maintenance of the existing land uses surrounding the WARB and forecasts of land use changes. Furthermore, the influence of the JLUS on the NCP updates is critical in unifying interested parties in the analysis of WARB activities relative to potential local and regional environmental impacts. The JLUS/PVPC land use plan, recently updated, is the base map for figures in the 2018 WARB/CEF NEM/NCP Update that provides the foundation for this EA.

1.1.3.2 2013 Air Installation Compatible Use Zone (AICUZ) Study Westover Air Reserve Base, Massachusetts


As with the JLUS discussed above, the 2013 AICUZ study was a significant contributor to the 2014 NEM/NCP Update and provided an additional review and modeling of critical noise contours for the 2013 WARB/CEF operations relative to the surrounding land use. As with the 2014 NEM/NCP update, the results of the 2013 AICUZ study reflect a different aviation environment at the WARB, since the 16-aircraft fleet of C-5B Galaxy aircraft continued to operate at that time. The 439th Airlift Wing currently operates 8 C-5M Super-Galaxy aircraft; a significant change from the conditions analyzed in the 2013 AICUZ study with a resultant change in noise contour geometry.

1.1.4 Westover Metropolitan Airport 2008 Master Plan Update

The most current version of the CEF master plan contains the goals and objectives of the WMDC in their operation of the airport and further development of civil aviation operations. Of importance to this EA is the documented focus of the WMDC on improving the civil aviation environment as a means of making CEF a self-sustaining civil aviation operation. This reoccurring theme further supports the Purpose and Need for the proposed action in this EA.

1.1.5 KC-46A Third Main Operating Base (MOB 3) Beddown Environmental Impact Statement (EIS) - April 2017

WARB was a considered alternative location for the basing of 12 KC-46A refueling aircraft, with associated facilities and infrastructure, and workforce. The proposed action in the EIS was to provide a *fully capable, combat operational KC-46A aerial refueling squadron to accomplish aerial refueling and related missions*. Basing this squadron at WARB was investigated in the NEPA EIS, complete with an assessment of environmental impacts. Current and forecasted WARB aircraft operations were subjected to noise and air quality analysis for existing conditions (2017 “no action” alternative) and for a future condition with the entire operational KC-46A squadron present at the airport. This would have been a complete new squadron in addition to the C-5 Galaxy aircraft already present at WARB. Noise and air quality analyses were conducted on a recent (2017) operational climate at WARB, which proved useful information for this (2018) EA.



DRAFT NEPA ENVIRONMENTAL ASSESSMENT WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS

Purpose of and Need for Action

July 5, 2018

Data in this EIS reflected operations at WARB when the 439th Airlift Wing operated 16 C-5B Galaxy aircraft. The 439th Airlift Wing currently operates 8 C-5M Super-Galaxy aircraft; a significant change from the conditions analyzed in the EIS. The reduction in the C-5 fleet and the engine upgrade from the “B” to the “M” model was significant from a noise and air quality perspective, and thus a major factor prompting the development of the 2018 NEM/NCP Update and the 2018 JLUS. This information contained in this 2017 EIS is significant for this EA in that it provides a look at total airport operations just preceding the major change in the C-5 Galaxy fleet. Furthermore, it contains recent agency correspondence and natural resource information for the WARB environment. The agency responses are helpful in identifying the presence of sensitive environmental resources, and in providing recent agency reaction to projects at WARB. The EIS historical/archeological and tribal coordination documentation was of particular interest relative to the proposed action of this EA.


WARB was not the selected alternative in this EIS to base the KC-46A refueling squadron. A ROD was issued on April 14, 2017.

1.1.6 Westover Air Reserve Base/Metropolitan Airport Noise Exposure Map (NEM) & Noise Compatibility Plan (NCP) Update (DRAFT June 2018)

A current, draft NEM/NCP Update has been prepared by the WMDC; it is attached as Appendix A to this EA. It contains updated noise exposure map contours for the present (2018) military/civil operations at WARB and forecasted operations out to 2023. It is the first noise exposure map update since the significant change in the C-5 Galaxy fleet at the WARB and contains significant differences in the critical noise contours from the 2014 NEM Update and the 2013 AICUZ study. It also contains the most up-to-date land use plan for the area, as developed by the JLUS/PVPC. The land use plan forms the base map for most of the figures contained in the document. The information in the Draft 2018 NEM/NCP Update provides the baseline noise contours for the “no action” alternatives assessed in this EA. Figure 1-3 provides a comparison of the noise contours between the 2014 NEM Update and the 2018 conditions.

The Draft 2018 NEM/NCP Update provides details on the noise model prescribed by the FAA and USAF for developing noise contours at WARB. Analysis of the existing and short-term noise contours are provided along with an analysis of incompatible land uses within the critical noise contours. The area (in acres) of each contour is presented, along with a differentiation between on-airport and off-airport areas. These baseline contours form the “no action” alternative for this EA, representing existing and future noise conditions at WARB in the absence of the proposed change in civil aviation operations.

This EA includes substantial information from, and reference to, the Draft 2018 NEM/NCP Update, and thus the document is included in its entirety in Appendix A. The document includes the following sections: Chapter 1 provides an introduction to the NEM/NCP process, Section 1.1 of the chapter provides an overview of the Part 150 process. Section 1.2 reviews the requirements of Noise Exposure Map (NEM) submittals, Section 1.3 discusses Noise Compatibility Program(NCP) measures, Section 1.4 discusses the project roles and responsibilities, and Section 1.5 explains the study goals. Chapter Two presents the existing and forecast operations data used in determining the noise environment around WARB. Chapter Three discusses land use and compatibility criteria. Chapter Four includes the updated NEMs for 2018 and 2023; Figures 4-1 and 4-2 provide the critical noise contours superimposed over the current land use plan. Chapter Five details the impact to the existing NCP based on the NEMs, and Chapter




**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**


Purpose of and Need for Action
July 5, 2018

Six provides a summary of consultation completed throughout the 2018 NEM/NCP Update process. Appendices A through E of the Draft 2018 NEM/NCP Update provides supporting material relevant to the study.

In general, the Draft 2018 NEM/NCP Update concludes that for both the 2018 and (future) 2023 conditions at WARB/CEF, *“the 65+ DNL noise exposure contour does not include any residential or recreational land uses. No population counts were needed as no residences appear to exist within the 65+ DNL noise exposure contour. According to the Regional Land Use Plan Map associated with the most recent PVPC comprehensive plan (Valley Vision 4), future land uses within the 65-70 DNL noise exposure contour off Airport property include Existing Protected Land and Open Water only; uses that are not considered incompatible with the FAA’s Part 150 land use guidelines.”* The document conclusion is based on the acoustical environment without the change in civil air operations to 24-hour operations. However; as is stated later in this EA, the proposed action results in a similar conclusion relative to the critical noise contours.




**Westover Air Reserve Base / Metropolitan Airport NEPA EA
DRAFT Generalized Existing Land Use**



LEGEND

- | | | |
|--|--|---|
| ■ Commercial/Industrial | ■ Transportation | Local Historic District |
| ■ Open/Agricultural/Recreational | ■ Water | ■ Place of Worship |
| ■ Public/Quasi-Public | WARB Installation Area | ■ School |
| ■ Residential | WMDC Aviation Property | |
| ■ Previously Acquired Property under the Voluntary Acquisition Program | County Boundary | |
| ■ Cemetery | Town Boundary | |
| ■ Institutional | National Register of Historic Places | |
| | National Register Historic District | |

**Figure 1-3
2014 NEM Existing Condition
vs. 2018 NEM Existing Condition**



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis

**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**


proposed action and alternatives
July 5, 2018

2.0 PROPOSED ACTION AND ALTERNATIVES

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF) at the Westover Air Reserve Base (WARB), to modify civil aviation operations at CEF. This Civil Aviation Action will extend the hours of civil aviation operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of the civil aviation program. The extended hours of civil aviation operations are projected to result in an average of 4 arrivals and 4 departures (8 operations) of civil aircraft per non-towered operating period. Based on this proposed action, a number of alternative scenarios were investigated for this EA, including Existing Conditions, Short Term Proposed Action, Future “No Action, Future Proposed Action and a Future Low GA Operations. Each is described below. The alternatives were developed in concert with WMDC, the USAF WARB and the consultant teams. The list is consistent with the USAF EIAP section for alternatives development at 32 CFR Part 989 section 989.8.

The Existing Condition (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low General Aviation (GA) Operations (2023) fleet mixes were developed based on information provided by the ATCT, and included potential new civil aircraft that would be introduced if the airport hours were extended from 16-hour to 24-hour. The civil fleet mixes were developed by Stantec and WMDC for use by HNTB. The following list provides a description of the project alternatives and associated assumptions for each alternative/scenario:

1. Existing Conditions represented the current state at WARB/CEF in 2018. The fleet mixes and operations represented the current aircraft types and associated operations for both military and civil operations. This baseline analysis reflects the reduced C-5 Galaxy fleet and the modified engines of the “M” model.
2. Short Term represented the first year (2019) when the airport operating hours would be extended from 16 hours per day to 24 hours per day. The fleet mixes and operations included potential new civil aircraft types and additional civil nighttime operations.
3. Future No Action (2023) assumed the airport would remain open for 16 hours per day in 2023. The fleet mix and operations included projected operations but no changes to the fleet mix or civil aviation operating hours.
4. Future Proposed Action (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023 for civil aviation operations. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 4 arrivals and 4 departures each night; a total of 8 civil operations.
5. Future Low GA Operations (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 2 arrivals and 2 departures each night, or half of the operations contained in the Future Proposed Action (2023). This scenario shows the resultant impacts if the full projected use of the extended operating hours was not realized.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018


3.0 AFFECTED ENVIRONMENT

Typical airport projects involve a variety of environmentally impactful elements from the construction stage through the operating stage, thus requiring study and analysis of the full range of protected environmental resources prescribed by NEPA. Typical construction-phase project elements, including demolition, construction, soil disturbance, vegetation clearing, and modification of elevations, ground slope and soil coverage, result in short-term impacts to the project environment. Typical operation-phase project elements, including changes in noise, workforce, surface traffic, staffing, waste material generation and site stormwater characteristics result in longer-term changes to the project environment. Clearly, the project scope and magnitude dictate the extent and range of these environmental impacts. It is not practical to apply the same range of impact analysis to each project, and this is recognized by the USAF NEPA regulations at 32 CFR Part 989, “The Environmental Impact Analysis Process” (EIAP). For EAs, the EIAP recognizes this in section 989.14 where it is specified “*The length of an EA should be as short and concise as possible, while matching the magnitude of the proposal. An EA briefly discusses the need for the proposed action, reasonable alternatives to the proposed action, the affected environment, the environmental impacts of the proposed action and alternatives (including the “no action” alternative), and a listing of agencies and persons consulted during preparation.*” Considering this direction, the following narrative provides the scope of this EA.

3.1 SCOPE OF THE ENVIRONMENTAL ASSESSMENT

The proposed action of this EA involves no construction or demolition activities and is restricted to operation-phase elements only. The installation of the necessary communications equipment and the administrative updated of agreements and airport data are the necessary pre-operation steps to the proposed modification to the civil aviation operations. Following a cursory evaluation of potential impacts to the prescribed environmental resource categories, including the definition of the “Area of Potential Effect” as the limits of the critical noise contours, the following list of resources will be assessed in detail for the project alternatives in this EA:

1. Noise (Acoustic Environment): This is the principle impact category assessed in this EA. The proposed action will generate a minimal additional number of aircraft operations during nighttime hours thus having the potential to modify the critical noise contours and impact sensitive receptors.
2. Air Quality: Additional aircraft operations, complete with the ground-associated equipment and transportation, will result in air emissions over the “no action” alternative. Assessment of these additional emissions relative to the Conformity Rule is necessary.
3. Land Use: Changes in the critical noise contours off the airport property can impact existing incompatible land uses and interfere with future land use planning.
4. Historical, Architectural, Archaeological and Cultural Resources: The presence of these resources within an expanded critical noise contour could lead to impacts. A review of the known resources relative to the Area of Potential Effect is necessary for the proposed action and the alternatives to determine the potential for impact.




**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

The preliminary assessment determined an unlikely impact to the following resources thus they were eliminated from further discussion in this EA. A list of the eliminated resources, and a brief explanation for each is provided below:

1. Topography, Geology and Soils including Protected Farmland: No physical alteration of soils or vegetation is proposed with this project. Existing topographical and geological features will remain in their present condition for all the project alternatives.
2. Water Resources, including Wild and Scenic Rivers, Wetlands and Floodplain: No physical alteration of any wetland or waterway will result from this project, including both wetland soils and vegetation. Existing wetlands and streams on and adjacent to WARB will continue to function in their present capacity and no impacts as defined by Section 404 of the Federal Clean Water Act or the Massachusetts Wetlands Protection Act Regulations (310 CMR 10.00) are proposed. There are no waterways designated as “Wild and Scenic” within the existing or proposed limits of the critical noise contours. While 100-year floodplain is located within the critical noise contours at the Runway 23 end (associated with Stony Brook and Muddy Brook within the Westover Golf Course and Westover Conservation Area), no physical changes to the floodplain will result from the project.
3. Water Quality: Impacts to water quality can occur with changes in stormwater runoff characteristics within the watershed, the release of pollutants that can reach area waterways and/or changes to groundwater quantity or quality resulting from water withdrawals or new discharges to the aquifer. The proposed project contains no plans for modification of the watershed (topography or cover types) or is expected to cause the need for new construction. Furthermore, the project does not require new water withdrawals or changes to the stormwater management system. No water quality impacts as defined by Sections 401 or 402 of the Federal Clean Water Act, or by the Massachusetts Surface Water Quality Standards at 301 CMR 4.00 are proposed.
4. Biological Resources including Rare Species: Federal Endangered Species Act (ESA) consultation under section 7(c) of the Endangered Species Act (Act) of 1973, as amended (16 U.S.C. 1531 et seq.) identifies the regional presence of Northern Long-eared Bat *Myotis septentrionalis* in Hampden County. Correspondence generated through the U.S. Fish & Wildlife Service IPaC program is contained in Appendix B of this EA. Further research with the Massachusetts Natural Heritage and Endangered Species Program suggests the presence of winter hibernacula for this species in Hampden County. Projects that would alter habitat, particularly the winter hibernacula, would impact this species. Furthermore, State-listed species per the Massachusetts Endangered Species Act (MGL c. 131A and its implementing regulations (321 CMR 10.00)), are present at WARB, and have been well documented in various studies. State-listed grassland bird species including grasshopper sparrow (*Ammodramus savannarum*) and upland sandpiper (*Bartramia longicauda*) are known to occur in the turf areas at WARB.

The proposed action will have no impacts to the habitat of any of the Federally- or State-listed protected species since no soil or vegetation alteration will occur. The minimal addition of nighttime civil operations to the primary runway at WARB is a continuation of the existing airport use with aircraft types common to the airport and the region. The critical noise contours associated with the proposed action remain well within the limits of recent contours and do not result in higher decibel readings than existing aircraft at WARB. Furthermore, the proposed operations will utilize existing flight tracks and procedures typical of WARB




**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

operations. Since baseline noise conditions are not significantly altered by the project, no impacts to wildlife are anticipated.

5. Infrastructure: The existing infrastructure is suitable to address the proposed civil operation changes and additions proposed with this project. The addition of additional communications equipment will rely on the existing electrical layout and will not require new construction or increased electrical use.
6. Traffic Congestion and Transportation: The existing infrastructure relative to ground transportation at CEF is suitable to accommodate this minor addition of civil aviation operations. No impacts to local traffic patterns will result from the limited nighttime operations.
7. Solid Waste and Hazardous Wastes: No demolition is proposed with this project. Only minimal solid waste would be generated by the additional civil aviation flights at CEF. The anticipated flights are primarily low-passenger business jets that generate little solid waste. The existing waste management schedule and structure would not require modification for this project. No hazardous material storage or waste generation would result from the proposed addition of civil aviation operations above existing conditions.
8. Safety and Occupational Health: The project is a continuation of existing flight procedures at WARB/CEF. The non-towered civil aviation operations will utilize an established pilot-to-pilot communications procedure that is frequently used throughout the region and the Country. Similarly, ground safety procedures with respect to loading and unloading aircraft, fueling and secure area compliance are well established at WARB/CEF requiring little, if any modification to accommodate the nighttime civil aviation activity. The established procedures for these various airport-related activities have been developed with current safety regulations and policies and will continue to promote the safety of airport users.
9. Socioeconomics: The project will allow WMDC to be more competitive in attracting civil aviation to CEF by providing for the 24-hour operational capacity. Improved service to the civil aviation industry will improve the capacity of WMDC to be a self-sustaining entity by collecting additional landing fees and increased hangar leases. Civil aviation operations will increase passenger and crew activity in the local area. Positive impacts to the CEF and local region can result from the project. Negative impacts to surrounding properties are not anticipated due the minor changes in the critical noise contours. The difference between the existing and proposed contours are restricted to open space land uses and do not include residential areas. No negative effect on off-airport property values are anticipated.
10. Environmental Justice, and Children's Health and Safety Risks: A review of census data for the proposed critical noise contours suggests that no minority populations or low-income populations are present within the area of potential effect; see Chapter 4 of the Draft 2018 NEM/NCP Update in Appendix A. There are no residential populations within the critical noise contours for the proposed action. Therefore, the project is consistent with Executive Orders 12898 *Federal Actions to Address Environmental Justice in Minority Populations and Low-Income* and 13045 *Protection of Children from Environmental Health Risks and Safety Risks*.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

3.2 NOISE (ACOUSTIC ENVIRONMENT)

Quantification of existing (2018) aircraft noise exposure at the WARB was the subject of the 2018 NEM/NCP Update contained in Appendix A of this EA. The document provides details on aircraft types, flight tracks, operations, runway use, and weather considerations used to generate the critical noise contours surrounding the airport based on current airport use. These critical contours are then compared to the airport property line and regional land use to determine the extent of various uses within the critical noise contours and ultimately presenting the status of incompatible land uses within the critical contours. Reviewers of this EA are directed to Chapter 2 of the 2018 NEM/NCP Update for the input to the acoustical models used to generate the critical noise contours, Figure 4-1 for the depiction of the critical noise contours over the airport property and adjacent land uses, and Figure 4-2 for a forecasted view of the critical contours for the future (2023) “no action” condition. For convenience, these two noise contour figures from the Draft 2018 NEM/NCP are provided in this EA as Figures 3-1 and 3-2.

Tables 3-1 and 3-2 (reproduced from the Draft 2018 NEM/NCP Update) provide acreage of various land use within the critical 65 DNL contour for the 2018 and future 2023 condition. Note the extent of the critical contours that remain on airport property and lack of any coverage within residential areas. The lack of incompatible land uses within the critical contours for existing operations at WARB/CEF is significant relative to Part 150 and this NEPA analysis.

Table 3-1: Generalized Land Uses within the Existing (2018) "No Action" Conditions - 65 DNL Noise Exposure Contour at WARB/CEF

Generalized Land Use	Land within Contour (acres)			
	65-70 DNL	70-75 DNL	75+ DNL	Total (65+ DNL)
Airport Property	368.4	171.3	57.2	596.9
Commercial/Industrial	1.7	0	0	1.7
Open/Agricultural	13.8	0	0	13.8
Recreational	0	0	0	0
Residential	0	0	0	0
Transportation/Utility	0	0	0	0
Voluntary Acquisition Property	0	0	0	0
Water	0.6	0	0	0.6
Wetland	0	0	0	0
Total	384.5	171.3	57.2	613.0

Source: MassGIS, Draft 2018 NEM/NCP Update.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

Table 3-2: Generalized Land Uses within the Future (2023) "No Action" Conditions - 65 DNL Noise Exposure Contour at WARB/CEF

Generalized Land Use	Land within Contour (acres)			
	65-70 DNL	70-75 DNL	75+ DNL	Total (65+ DNL)
Airport Property	386.8	163.7	76.2	626.7
Commercial/Industrial	1.8	0	0	1.8
Open/Agricultural	20.9	0	0	20.9
Recreational	0	0	0	0
Residential	0	0	0	0
Transportation/Utility	0	0	0	0
Voluntary Acquisition Property	0	0	0	0
Water	3.3	0	0	3.3
Wetland	0	0	0	0
Total	412.8	163.7	76.2	652.7


Source: MassGIS, Draft 2018 NEM/NCP Update.

As summarized from Chapter 4.0 of the 2018 NEM/NCP Update, the 65+ DNL noise exposure contours encompass approximately 613 acres (almost one square mile) in total under existing conditions. Of this acreage approximately 597 acres are within Airport property. There are no residential land uses within the 65+ DNL noise exposure contour, nor are there any properties previously acquired by the Airport for noise abatement under their existing NCP. As no houses appear to be present population counts were not needed. There are also no recreational uses or noise sensitive locations within the 65+ DNL noise exposure contour. Thus, there are no incompatible land uses when considering the FAA's Part 150 land use guidelines. The entire 70+ DNL noise contour (approximately 229 acres/0.36 square miles) remains within the boundaries of the Airport. There are no incompatible land uses within the 70+ DNL noise contour. There are no known non-residential noise sensitive land uses, such as hospitals, places of worship, schools, historic sites, or nursing homes, within the 65+ DNL noise contour.

For comparison, the 2015 noise exposure data from the KC-46A *THIRD MAIN OPERATING BASE (MOB 3) BEDDOWN ENVIRONMENTAL IMPACT STATEMENT* (see Section 1.1.5 of this EA) calculated a total area within the 65-70 DNL contour of 739 acres with 410 acres of that total occurring off the airport. The 2018 NEM data represents an approximate 48% reduction in the extent of the critical contour, and a 96% reduction of off-airport area. The differences in the WARB/CEF acoustic environment since 2015 are reflected in Table 3-3 which summarize the acreage of land within the critical noise contours for the 2015 versus 2018 baseline conditions. The difference between the 2015 and 2018 acreages within the critical noise contours is quite evident and resulted in the elimination of incompatible land uses within the critical contours for sent day aircraft operations.




Westover Air Reserve Base / Metropolitan Airport NEPA EA



LEGEND

- | | |
|--|---|
| Existing Conditions DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |


Existing Conditions Noise Contour Figure 3-1



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO


Westover Air Reserve Base / Metropolitan Airport **NEPA EA**



LEGEND

- | | |
|--|---|
| No Action Alternative DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

No Action (2023) Alternative Noise Contour Figure 3-2



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

Table 3-3: Comparison of Land Area Within Critical Noise Contours Between the 2015 and 2018 Baseline Years for WARB/CEF

Noise Level (DNL)	Land Within Contours (Acres)					
	On Airport		Off Airport		Total	
	2015	2018	2015	2018	2015	2018
65 - 69	320	368.4	419	26	739	613
70 - 74	369	171.3	44	0	413	171.3
75 +	450	57.2	1	0	451	57.2

Source: KC-46A *Third Main Operating Base Beddown EIS (April 2017), 2018 Draft NEM/NCP Update*


The change in the C-5 Galaxy fleet was principally responsible for this significant change in the acoustic environment at WARB/CEF since the 2015 noise exposure analysis. The fleet change prompted the preparation of the 2018 NEM/NCP Update that is the basis for the “existing conditions” noise calculations for the proposed action.

3.3 AIR QUALITY

The proposed action would result in an increase of up to 8 average daily civil aircraft operations at WARB/CEF, which would generate additional air emissions. Air quality assessments for proposed Federal actions are required for compliance with the Federal Clean Air Act (CAA) and the State-level Massachusetts Clean Air Act and associated regulations relative to the National Ambient Air Quality Standards (NAAQS). The EIAP requires that documents address the CAA Conformity Rules requirements. The EIAP conformity process is addressed in the guide “*Air Force Air Quality Environmental Impact Analysis Process (EIAP) Guide*” developed by the Air Force Civil Engineer Compliance Technical Support Branch (October 2014). Per that documented, the General Conformity rule applies to non-federal highway and non-transit Federal actions and thus applies to this project.

The WARB section of Hampden County, Massachusetts is presently in attainment for all NAAQS; due in part to the revocation of the 1997 Ozone NAAQS in April 2015. Prior to the revocation, WARB was within a moderate nonattainment area for the 1997 Ozone NAAQS. Current legal nation-wide challenges to the revocation may alter the attainment status of the region for the NAAQS, but the project site in June 2018 is in attainment and is not listed as a maintenance area. The requirement to prepare an air quality conformity determination (40 CFR 93 Subpart B section 93.153(b)) only applies to areas that are nonattainment or maintenance for one or more NAAQSs.

However; given the relatively recent non-attainment status of the region for ozone, the presence of an ozone “maintenance area” southwest of the WARB, and the legal challenges to the revocation of the 1997 Ozone NAAQS, the proposed action was subjected to air quality modeling to test potential compliance with the General Conformity rule specific to ozone. See Chapter 4 of this EA for the results of this analysis.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Affected Environment
July 5, 2018

3.4 LAND USE


The current and potential land uses within the project area have been documented in the Draft 2018 NEM/NCP Update located in Appendix A of this EA; review of Section 3.3 of that document is necessary to comprehend the noise impact analysis conducted in this EA and the conclusions of that analysis. Figure 3-3 depicts the existing land uses in the project area. The Draft 2018 NEM/NCP Update provides a land use discussion relative to FAR Part 150, discussing the current status of incompatible land uses within the current critical noise contours at WARB/CEF. The document concludes that, *“The 65+ DNL noise exposure contour does not include any residential or recreational land uses. No population counts were needed as no residences appear to exist within the 65+ DNL noise exposure contour. According to the Regional Land Use Plan Map associated with the most recent PVPC comprehensive plan (Valley Vision 4), future land uses within the 65-70 DNL noise exposure contour off Airport property include Existing Protected Land and Open Water only; uses that are not considered incompatible with the FAA’s Part 150 land use guidelines.”*

3.5 CULTURAL RESOURCES


As the project does not propose any construction, demolition, excavation, soil disturbance or vegetation impacts, the potential for cultural resource impacts are minimal. They are investigated in this EA due to the slight increase in the noise contours with the proposed action, which have some potential to disrupt enjoyment of historic sites on public property. The area of potential effect is considered to be that area of potential noise increase off the airport property at the ends of Runway 5 and 23 where slight increases of the critical noise contours are possible. The discussion of cultural resources is thus commensurate with the potential area of effect. This section contains a general discussion of the project area while Section 4.5 provides an analysis of potential impacts.

The Massachusetts Cultural Resource Information System (MCRIS) developed by the Massachusetts Historical Commission (the State Historic Preservation Officer for Massachusetts) was consulted for the presence of various cultural resources within the critical noise contours associated with the project. Several buildings and land areas within WARB are eligible for inclusion on the National Register of Historic Places and thus subject to protection under the National Historic Preservation Act. There is a recognized Historic District within the WARB surrounding many of the listed structures and areas on the MCRIS list. These sites are generally west of the runway environment.

Tribal consultation was conducted to determine the presence of sensitive traditional resources within the APE. Four tribal contacts were initiated and two responses were received; see Appendix B. Based on the responses, and review of a similar consultation completed with the same tribes for the KC-46A *Third Main Operating Base Beddown EIS* (April 2017), there are no known tribal sacred sites or properties within the APE.



Westover Air Reserve Base / Metropolitan Airport NEPA EA




USDA-FSA-APFO

LEGEND

- | | |
|---|---|
| ■ Commercial/Industrial | ■ Transportation |
| ■ Open/Agricultural/Recreational | ■ Water |
| ■ Public/Quasi-Public | ■ WARB Installation Area |
| ■ Residential | ■ WMDC Aviation Property |
| ■ Previously Acquired Property under the Voluntary Acquisition Program | ■ County Boundary |
| ■ Cemetery | ■ Town Boundary |
| ■ Institutional | ⚪ Place of Worship |
| | ⚪ School |
| | ○ National Register of Historic Places |
| | △ Local Historic District |

Generalized Existing Land Use Figure 3-3



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

Environmental Consequences
July 5, 2018

4.0 ENVIRONMENTAL CONSEQUENCES

4.1 INTRODUCTION

Environmental consequences resulting from the proposed modification of civil aviation operations at WARB/CEF are assessed in this chapter. The scope of the analysis is commensurate with the magnitude of the action and is limited to those resource categories where the noise and air emissions from the increase in non-towered nighttime flights might be impacted. Each pertinent environmental resource is assessed for the project alternatives, including the “no action” alternative. The “no action” alternative establishes a baseline set of conditions for which to compare impacts associated with the various project alternatives.

Of significance and reference to this section is the Noise Analysis Technical Memorandum (HNTB, 2018) contained in Appendix C of this EA. This document contains the entire discussion of the noise-related consequences of the project alternatives. Important figures and tables associated with the noise-related consequences are copied in this that EA chapter for convenience, but the entire technical memorandum should be thoroughly reviewed for a full comprehension of the changes in the critical noise contours associated with the project.

4.2 NOISE


The Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF), home to the Massachusetts Air Force Reserve 439th Airlift Wing, previously operated Lockheed C-5A Galaxy aircraft and has upgraded to the C-5M Super Galaxy. A Title 14 Code of Federal Register (CFR) Part 150 Update (Part 150 Update) is being prepared to disclose the impacts of the C-5M Super Galaxy fleet upgrade. The Westover Metropolitan Development Corporation (WMDC) proposes to extend CEF operating hours to 24 hours per day. Noise exposure contours were prepared representative of existing conditions in 2018 and forecast conditions in 2019 and 2023 using the Aviation Environmental Design Tool (AEDT) Version 2d and NOISEMAP Version 7.363. The technical memorandum in Appendix C presents the data sources, methodologies, and assumptions applied to develop the noise contours, as well as the presentation of noise contours and their comparisons.

The following list provides a description of the project alternatives and associated assumptions for each alternative/scenario, followed by an analysis of the noise conditions for each alternative relative to potential incompatible land uses.

4.2.1 Existing Conditions (2018)

The Existing Conditions represents the current noise conditions at WARB/CEF in 2018. The fleet mixes and aircraft operations represent the current aircraft types and associated operations for both military and civil operations. This baseline analysis reflects the reduced C-5 Galaxy fleet and the modified engines of the “M” model.

Baseline critical noise contours for the existing conditions are presented in Figure 1 of the technical memorandum with the resultant acreage within the critical noise contours presented in Table 7 of the memorandum. Table 3-4 provides a summary of the land area contained within the critical noise contours for this alternative relative to the other project alternatives.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Environmental Consequences
July 5, 2018

4.2.2 Short Term Proposed Action (2019)

This alternative represented the first year (2019) when the airport operating hours would be extended from 16 hours per day to 24 hours per day. The fleet mixes and operations included potential new civil aircraft types and additional civil nighttime operations. This alternative provides an immediate view of the changes in the critical noise contours.

Critical noise contours for the existing conditions are presented in Figure 2 of the technical memorandum with the resultant acreage within the critical noise contours presented in Table 8 of the memorandum.

4.2.3 Future No Action (2023)

This alternative assumed the airport would remain open for 16 hours per day into 2023. The fleet mix and operations included projected operations but no changes to the fleet mix or civil aviation operating hours.

Baseline critical noise contours for the existing conditions are presented in Figure 3 of the technical memorandum with the resultant acreage within the critical noise contours presented in Table 9 of the memorandum.

4.2.4 Future Proposed Action (2023)

This “proposed action” alternative assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023 for civil aviation operations. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 4 arrivals and 4 departures each night; a total of 8 civil operations.

Baseline critical noise contours for the existing conditions are presented in Figure 4 of the technical memorandum with the resultant acreage within the critical noise contours presented in Table 10 of the memorandum.


4.2.5 Future Low Civil Air Operations (2023)

This alternative assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The civil fleet mixes and operations included potential new civil aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 2 arrivals and 2 departures each night, or half of the operations contained in the Future Proposed Action (2023). This scenario shows the resultant impacts if the full projected use of the extended operating hours was not realized.

Baseline critical noise contours for the existing conditions are presented in Figure 5 of the technical memorandum with the resultant acreage within the critical noise contours presented in Table 11 of the memorandum.

4.2.6 Noise Contour Summary

The total area within the 65+ DNL noise contour of the Proposed Future Action (2023) alternative is 715.3 acres, which is 16.7% larger than the Existing Conditions (2018), and 9.6% larger than the No Action (2023) alternative. The larger contour is due to an increase in operations, especially nighttime operations under the Proposed Action. The total area within the 65+ DNL noise contour of the Low GA Operations (2023) alternative is 682.1 acres, which is 11.3% larger than the Existing Conditions (2018) and 4.5% larger than the No Action (2023) alternative. The total



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Environmental Consequences
July 5, 2018

area within the 65+ DNL noise contour of the Short Term (2019) alternative is 626.1 acres, which is slightly larger (2.1%) than the Existing Conditions (2018) alternative. These data are summarized in Table 3-4.


Table 4-1: Summary Table of Land Area Within the Critical Noise Contours for the Project Alternatives

Project Alternative	Land within Contour (acres)			
	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
“No Action” Existing Conditions (2018)	384.5	171.3	57.2	613.0
Short Term Proposed Action (2019)	393.2	166.9	66.0	626.1
“No Action” Future Conditions (2023)	412.8	163.7	76.2	652.7
Proposed Action Future Conditions (2023)	452.9	162.8	99.9	715.3
Low Civil Aviation Operations Future Conditions (2023)	430.2	161.8	90.1	682.1

Comparison of the contours to the land use plan shows no residential areas or noise sensitive sites are included in the 65+ DNL noise contour of any of the five alternatives. The 70+ DNL noise contour falls entirely within the airport boundary for all alternatives. Compared with the No Action (2023) alternative, the Proposed Action (2023) alternative 65+ DNL noise contour extends slightly further to the northeast beyond the north bank of Wade Pond and Stony Brook. For other areas, the Proposed Action (2023) and No Action (2023) noise contours are very similar. This is because the noise contours are dominated by the military noise signature in the future alternatives. Therefore, the increase of civil aviation nighttime operations under the Proposed Future Action is expected to be a minor contributor to the overall noise exposure. The military noise signature is by far the largest contributor to the overall noise exposure for CEF and is present in all future alternatives. Figure 6 in the technical memorandum provides all of the critical contours for the project alternatives superimposed on the land use plan for comparison purposes. The figure clearly shows the minimal differences between the contours between the “no action” alternatives and the “proposed action” alternatives.

4.2.7 Supplemental Noise Metrics

The USAF directed the preparation of two supplemental noise metrics for this project. The Percent Highly Annoyed and the Probability of Awakening metrics are described and analyzed in the technical memorandum. The methodologies followed the two technical bulletins published by the U.S. Department of Defense Noise Working Group (DNWG). The results of the Percent Highly Annoyed analyses are presented in Figures 8-12 of the technical memorandum. For the Percent Highly Annoyed metric, the following summary of potential impact is provided. *“The analysis shows the majority (approximately 85% - 90%) of the 10% contour falls within the airport boundary. The total area within 10% contour of the Proposed Action (2023) alternative is 1,012.5 acres, which is 19.8% larger than the Existing Conditions (2018), and 10.7% larger than the No Action (2023) alternative. The larger contour is due to an increase in operations, especially nighttime operations under the Proposed Action. The total area within the 10%*



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Environmental Consequences
July 5, 2018

contour of the Low GA Operations (2023) alternative is 964.5 acres, which is 14.1% larger than the Existing Conditions (2018) and 5.5% larger than the No Action (2023) alternative. The total area within the 10% contour of the Short Term (2019) alternative is 626.1 acres, which is slightly larger (2.1%) than the Existing Conditions (2018) alternative.” No existing incompatible land uses are located within the critical contours of this metric.

The results of the Probability of Awakening metric are presented in Figure 13 of the technical memorandum; it was conducted on the Proposed Future Action alternative only. The critical contour for this metric remains completely on airport property for the proposed action, thus analysis of the reduced and no action alternatives is not necessary.

4.3 AIR QUALITY

The proposed action was evaluated relative to the existing attainment status of the region and the General Conformity Rule. Conformity Rules (40 CFR Subpart B section 93.153) apply only to areas that are designated by the USEPA as non-attainment and maintenance areas. Conformity is intended to ensure that a Federal action is consistent with a state implementation plan to control a priority pollutant and address violations to the NAAQS.

The project is within USEPA designated attainment area for the NAAQS and is not currently listed as a maintenance area. It is designated as an ozone transfer region, and the site was within a non-attainment area for ozone prior to the revocation of the 1997 NAAQS. Consultation with the USAF suggested that an evaluation of the proposed action relative to the emission thresholds for maintenance areas be completed to evaluate conformity should the region be changed to non-attainment for ozone in the near future. These thresholds for maintenance areas are reproduced from 40 CFR Subpart B section 93.153(b)(2) in Table 4-1.

Table 4-2: Clean Air Act Conformity Rule Emission Rate Thresholds for Maintenance Areas

Pollutant	Tons/year
Ozone (NOX), SO2 or NO2:	
All maintenance areas	100
Ozone (VOC's)	
Maintenance areas inside an ozone transport region	50
Maintenance areas outside an ozone transport region	100
Carbon monoxide: All maintenance areas	100
PM10: All maintenance areas	100
PM2.5 (direct emissions, SO2, NOX, VOC, and Ammonia)	100
All maintenance areas	100
Pb: All maintenance areas	25

Source: 40 CFR Subpart B section 93.153(b)(2)



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Environmental Consequences
July 5, 2018

The latest version of AEDT (version 2d) was used to model the direct and indirect emission sources associated with the additional civil aviation operations in the proposed future (2023) action. Table 4-2 provides the emission rates for the existing conditions (2018) for civil aviation operations at WARB/CEF and for the proposed future (2023) action, revealing the additional amount of air quality pollutants resulting from the increase in operations.

Table 4-3: Air Pollutant Emission Comparison Between the No Action and Proposed Action Alternatives


Alternative	Air Pollutant Emissions (tons/year)													
	CO (ST)	HC (ST)	TOG (ST)	VOC (ST)	NMHC (ST)	NOx (ST)	nvPM Mass (ST)	PMSO (ST)	PMFO (ST)	CO2 (ST)	H2O (ST)	SOx (ST)	PM 2-5 (ST)	PM 10 (ST)
Proposed Action	24.3	4.9	5.7	5.6	5.6	10.0	0.1	0.0	0.1	3,356.8	1,316.1	1.2	0.2	0.2
No Action	16.8	2.6	3.0	3.0	3.0	5.8	0.0	0.0	0.0	2,010.6	788.3	0.7	0.1	0.1
Net Increase	7.5	2.3	2.6	2.6	2.6	4.2	0.0	0.0	0.0	1,346.2	527.8	0.5	0.1	0.1

Source: HNTB analysis


Comparison of the net increase in pollutant emissions from civil aviation operations at WARB/CEF presented in Table 4-2 to the emission rate thresholds of Table 4-1 reveal that the project will not violate the emission thresholds for designated ozone maintenance areas; all increases remain below *de minimus* standards. The proposed action would generate an insignificant increase in air emissions relative to the CAA, the NAAQS and the General Conformity Rule.

4.4 LAND USE

DNL noise exposure contours prepared for the Future (2023) Proposed Action NEM are shown in Figure 4-1 superimposed on the existing land use plan. The overall size of the 65 DNL noise exposure contour increases by approximately 62 acres to nearly 715 acres (slightly more than one square mile), due to a proposed increase in civil aviation operations. The 65+ DNL noise exposure contour does not include any residential or recreational land uses. No population counts were needed as no residences appear to exist within the 65+ DNL noise exposure contour. According to the Regional Land Use Plan Map associated with the most recent PVPC comprehensive plan (Valley Vision 4), future land uses within the 65-70 DNL noise exposure contour off Airport property include Existing Protected Land and Open Water only; uses that are not considered incompatible with the FAA's Part 150 land use guidelines. The proposed action does not appear to impact future land use decisions. The Noise Compatibility Plan contained in the Draft 2018 NEM/NCP Update includes recommendations for land use planning to promote smart growth in the WARB vicinity and to ensure the separation of critical noise contours and incompatible land uses.




Westover Air Reserve Base / Metropolitan Airport **NEPA EA**



LEGEND

- | | |
|--|---|
| Proposed Action Alternative DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

Proposed Action Alternative Noise Contour Figure 4-1




Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Environmental Consequences
July 5, 2018

4.5 CULTURAL RESOURCES

No off-airport cultural resources were identified within the limits of the critical noise contour for the proposed action. Since the project does not include demolition, construction, soil disturbance or vegetation clearing, impacts to cultural resources are avoided. Increased noise over historic sites can impact the cultural setting of such sites. Review of the slight expansion of the critical noise contours for the Future (2023) Proposed Action reveals no historic sites within the area of potential effect. Furthermore, tribal consultation for the subject did not reveal any concerns for sensitive tribal resources.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

References
July 5, 2018

5.0 REFERENCES

Code of Federal Regulations, 32 CFR 989 – Environmental Impact Analysis Process

HNTB 2008. Westover Metropolitan Airport Master Plan Update. June 2008.

HNTB 2014. Westover Air Reserve Base/Metropolitan Airport Noise Exposure Map (NEM) & Noise Compatibility Plan (NCP) Update. Prepared for the Westover Metropolitan Development Corp. By; HNTB Corporation 2014.

HNTB 2018. Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF) Title 14 C.F.R. Part 150 and EA Studies – Noise Contour Development – Technical Memorandum. By; Yue Xu, Ph.D., P.E. Aviation/Environmental Planner. May 25, 2018.

HNTB 2018. Westover Air Reserve Base/Metropolitan Airport Noise Exposure Map (NEM) & Noise Compatibility Plan (NCP) Update (Draft Final). Prepared for the Westover Metropolitan Development Corp. June 2018.

MADEP 2018. Massachusetts Air Quality Attainment Designations and Attainment. Retrieved from <https://www.mass.gov/service-details/designations-attainment> . June 2018.

MADFW 2018. Massachusetts Division of Fisheries and Wildlife. Natural Heritage & Endangered Species Program. State-listed Rare Species Critical Habitat. Retrieved from the Massachusetts Geographic Information System – Rare Species Data Layer. June 2018.

USAF 1987. U.S. Air Force. Final EIS, Proposed Air Force Reserve Mission Change (C-130 to C-5A Aircraft) and Westover Metropolitan Development Corporation Expansion of Civil Aviation Operations through 1995 at Westover Air Force Base. April 1987.

USAF 1995. U.S. Air Force. Supplemental EIS, Military and Civil Aircraft Operations at West-over Air Reserve Base, Massachusetts. January 1995.


USAF 2013. U.S. Air Force. Air Installation Compatible Use Zone Study (AICUZ). Westover Air Reserve Base, Massachusetts. February 2013.

USAF 2015. U.S. Air Force. Final Environmental Assessment Westover Air Reserve Base, Chicopee, Massachusetts, Manage Airfield Vegetation to Protect Flight Safety. April 2015.

USAF 2017. Final EIS, U.S. Air Force. Main Operating Base (MOB) 3 KC-46A Beddown Westover ARB, April 2017.

USFWS 2018. U.S. Fish and Wildlife Service. U.S. Fish and Wildlife Service (USFWS) Information for Planning and Conservation (IPaC) Online System. Hampden County, Massachusetts. June 2018.

Westover ARB 2004b. Westover Air Reserve Base. Westover Air Reserve Base/ Westover Metropolitan Airport Joint Land Use Study (JLUS) Update. October 2004.



**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Appendix A 2018 NEM/NCP Update (DRAFT)
July 5, 2018

Appendix A 2018 NEM/NCP UPDATE (DRAFT)



**Westover Air Reserve Base/
Metropolitan Airport Noise
Exposure Map (NEM) & Noise
Compatibility Plan (NCP) Update**

This document provides an update to the
2014 NEM and 2014 NCP.

June 1, 2018

Prepared for:

Westover Metropolitan Redevelopment
Authority

Prepared by:

Stantec Consulting Services
and
HNTB Corporation



Table of Contents

	<u>Page</u>
Chapter 1: Introduction.....	1
1.1 14 CFR Part 150.....	1
1.2 Noise Exposure Maps.....	2
1.3 Noise Compatibility Program.....	2
1.4 Project Roles and Responsibilities	2
1.4.1 Westover Metropolitan Development Corporation.....	3
1.4.2 439 th Airlift Wing of the Air Force Reserve	3
1.4.3 Pioneer Valley Planning Commission	3
1.4.4 Massachusetts Department of Transportation - Aeronautics Division.....	3
1.4.5 Consultant	3
1.4.6 Federal Aviation Administration (FAA).....	3
1.5 NEM/NCP Update Study Goals.....	4
Chapter 2: Existing and Forecast Flight Operations.....	5
2.1 Airport Location and Layout	6
2.1.1 General information	6
2.1.2 Users.....	6
2.1.3 Weather and Climate	7
2.1.4 Airspace and Air Traffic Control	7
2.2 Existing (2018) Conditions	7
2.2.1 Flight Operations and Fleet Mix	8
2.2.2 Aircraft Flight Profiles.....	14
2.2.3 Runway Use	14
2.2.4 Flight Track Locations and Use.....	15
2.2.5 Run-up/Maintenance Operations	16
2.3 Future (2023) Conditions	16
2.3.1 Flight Operations and Fleet Mix	16
2.3.2 Aircraft Flight Profiles.....	16
2.3.3 Runway Use	16
2.3.4 Flight Track Locations and Use.....	16
2.3.5 Run-up/Maintenance Operations	16
Chapter 3: Noise and Land Use Compatibility	22

3.1	Land Use Guidelines.....	22
3.1.1	Federal Guidelines.....	22
3.1.2	Local Land Use Guidelines	25
3.2	Development of Land Use and Population Data.....	25
3.3	Existing Generalized Land Use	26
3.3.1	Noise-Sensitive Resources	26
3.4	Existing Generalized Zoning	26
3.5	Future Land Use	27
Chapter 4:	Noise Exposure Maps.....	28
4.1	Land Use Base Map	28
4.2	Noise Exposure Map for Existing Conditions (2018)	28
4.3	Noise Exposure Map for Future Conditions (2023).....	29
Chapter 5:	Noise Compatibility Program.....	31
5.1	History of Noise Compatibility Planning at the Airport	31
5.2	2014 Noise Compatibility Program.....	32
5.2.1	Noise Abatement Measures.....	32
5.2.2	Land Use Measures.....	35
5.2.3	Implementation, Monitoring, and Review Measures	39
Chapter 6:	Record of Consultation	42
6.1	Meetings and Coordination	42
6.2	Draft NEM/NCP Update Document	42
6.3	Public Information Workshop	42
6.4	Comments on the Draft Document.....	42

List of Tables

Table 2.1 2018 Average Annual Day Fleet Mix..... 9
Table 2.2 Overall Runway Usage15
Table 2.3 2023 Average Annual Day Fleet Mix.....17
Table 3.1 Part 150 Noise and Land Use Compatibility Guidelines23
Table 4.1 Generalized Land Uses within the Existing (2018) Conditions 65 DNL Noise Exposure Contour.....29
Table 4.2 Generalized Land Uses within the Future (2023) Conditions 65 DNL Noise Exposure Contour.....30

List of Figures

Figure 2-1 Vicinity Map 6
Figure 2-2 Airfield Layout..... 7
Figure 2-3 Flight Tracks – Civilian Fixed Wing Arrival15
Figure 2-4 Flight Tracks – Civilian Fixed Wing Departure.....15
Figure 2-5 Flight Tracks – Civilian Helicopter Arrival15
Figure 2-6 Flight Tracks – Civilian Helicopter Departure15
Figure 3-1 Generalized Existing Land Use.....26
Figure 3-2 Generalized Zoning.....26
Figure 3-3 Regional Land Use Plan Map27
Figure 4-1 Existing (2018) Conditions Noise Exposure Map28
Figure 4-2 Future (2023) Conditions Noise Exposure Map.....29
Figure 5-1 Proposed Rezoning of Residential Parcels with 2023 NEM37

Appendices

Appendix A: Part 150 NEM and NCP Checklists
Appendix B: 1996 and 2015 FAA Records of Approval (ROA)
Appendix C: AEE Coordination
Appendix D: Noise and its Effect on People
Appendix E: Record of Consultation

CHAPTER 1: Introduction

Title 14 of the Code of Federal Regulations (CFR) Part 150, “Airport Noise Compatibility Planning,” sets forth standards for airport operators to use in documenting noise exposure in airport environs and establishing programs to minimize aircraft noise and land use incompatibilities. Federal Aviation Administration (FAA) Advisory Circular 150/5020-1, “Noise Control and Compatibility Planning,” establishes the framework for conducting Part 150 studies. This Circular notes that the goal of the study process is “to develop a balanced and cost-effective program to minimize and/or mitigate the airport’s noise impact on local communities.”

Section 1.1 of this chapter provides an overview of the Part 150 process. Section 1.2 reviews the requirements of Noise Exposure Map (NEM) submittals, Section 1.3 discusses Noise Compatibility Program (NCP) measures, Section 1.4 discusses the project roles and responsibilities, and Section 1.5 explains the study goals.

Chapter Two presents the existing and forecast operations data used in determining the noise environment around Westover Air Reserve Base / Metropolitan Airport (CEF). **Chapter Three** discusses land use and compatibility criteria. **Chapter Four** includes the updated NEMs for 2018 and 2023. **Chapter Five** details the impact to the existing NCP based on the NEMs, and **Chapter Six** provides a summary of consultation completed throughout the NEM/NCP Update process. **Appendices A through E** provides supporting material relevant to this study.

1.1 14 CFR Part 150

14 CFR Part 150 (referred to as Part 150 within this document) prescribes specific standards for the following:

- measuring aircraft noise;
- estimating cumulative aircraft noise exposure using computer models;
- describing aircraft noise exposure (including instantaneous, single event and cumulative levels);
- coordinating NCP development with local land use officials and other interested parties;
- documenting the analytical process and development of the compatibility program;
- submitting documentation to the FAA;
- FAA and public review processes; and
- FAA approval or disapproval of the submission.

A full Part 150 submission to the FAA consists of two elements: NEMs for an existing and forecast condition, and an NCP. The Westover Metropolitan Development Corporation (WMDC) first completed an NEM and NCP under 14 CFR Part 150 for the Airport in 1994. An NEM/NCP Update was conducted in 2003 and again in 2014. The 2014 NEM Update included a review of the 1996 NCP and revisited the mitigation component of the document based on the future 2019 NEM. The FAA issued a Record

of Approval (ROA) for the 2014 NEM/NCP Update in February 2015.

This document provides an update to the 2014 and 2019 NEMs and provides a review of an update to the 2014 NCP.

1.2 Noise Exposure Maps

The FAA developed a checklist for use in reviewing NEM submittals, which must be completed before submission of the final NEM. A copy of the FAA checklist is provided in **Appendix A**. The checklist provides specific requirements for approval of NEMs, along with section references indicating the location in the document where the requirements are addressed.

The NEM documentation describes the airport layout and operation, aircraft-related noise exposure, land uses in the airport environs, and the resulting aircraft noise and land use compatibility status. NEMs include graphic depictions of existing and forecast (i.e., future) noise exposure levels resulting from aircraft operations and land uses in the airport environs. The NEM documentation also describes the data collection and analyses undertaken in its development.

NEMs must address two timeframes: the year of submission (the “existing condition”) and the fifth calendar year following the year of submission (the “forecast condition”). The submission year for this NEM/NCP Update is 2018 and a Future (2023) NEM represents the 5-year forecast noise exposure. Upon acceptance by the FAA, the NEMs replace previously accepted maps from the 2014 NEM Update.

1.3 Noise Compatibility Program

A review of the Airport’s FAA-approved NCP was conducted to evaluate the implementation of the recommended and

approved NCP measures. The NCP analysis also considers the most recent NEMs and how the implementation of the mitigation program would be affected. **Appendix B** provides the FAA’s ROA of the 1996 and 2014 NCPs completed for the Airport. An NCP checklist for this document is provided in **Appendix A** following the NEM checklist.

The NCP is a list of the actions the airport operator, airport users, local governments, and FAA propose to undertake to minimize existing and future aircraft noise and land use incompatibility. The NCP documentation must recount the development of the program, including a description of all measures considered, the reasons that individual measures were accepted or rejected, how measures will be implemented and funded, and the predicted effectiveness of individual measures and the overall program.

1.4 Project Roles and Responsibilities

As discussed below, several groups had major roles in the Part 150 process, including the WMDC, the 439th Airlift Wing of the Air Force Reserve, the project consultant team (Stantec and HNTB Corporation (HNTB)), the Pioneer Valley Planning Commission (PVPC), the Massachusetts Department of Transportation (MassDOT), and the FAA.

The Airport hosts both civilian and military activity. WMDC manages civilian operations at the Airport, while the Air Force Reserve manages military operations. The facility is operated under a joint use agreement with the USAF hosting the WMDC, a quasi-public non-profit development corporation established in 1974.

1.4.1 Westover Metropolitan Development Corporation

As the recognized sponsor of the civilian side of the airport by the FAA, WMDC is the project sponsor and has responsibility for the entire NEM/NCP Update. Using the information provided by the consulting team, the WMDC, in consultation with the FAA, also reviews the previous NCP with the updated NEMs to ensure that these two components of Part 150 are aligned.

1.4.2 439th Airlift Wing of the Air Force Reserve

The 439th Airlift Wing is based at Westover and operates eight C-5M Super Galaxy aircraft. As the primary user of the Airport, the 439th Airlift Wing provided information on military flight operations and procedures.

In February 2013, the Air Force Reserve finalized an Air Installation Compatible Use Zone (AICUZ) Study update. The purpose of the AICUZ program is to promote compatible land development in areas subject to aircraft noise and accident potential. The Study reaffirmed Air Force policy of promoting public health, safety, and general welfare in areas surrounding the Airport. The report presented changes in flight operations since the previous AICUZ Study (1996) and provided current noise zones and future noise zones and compatible use guidelines for land areas.

The Westover Airport Traffic Control Tower (ATCT or Westover Tower) is operated by the USAF and provided significant input into several areas, including existing and future operational procedures and trends.

1.4.3 Pioneer Valley Planning Commission

The PVPC is the regional planning body for the jurisdictions surrounding the Airport.

PVPC serves the member governments within its district and provided land use compatibility assistance for this NEM/NCP Update.

1.4.4 Massachusetts Department of Transportation - Aeronautics Division

The Massachusetts Department of Transportation-Aeronautics Division of Aeronautics provided funding assistance for this NEM/NCP Update and provided a review of the document.

1.4.5 Consultant

The WMDC retained Stantec Consulting Services (Stantec) who in turn retained the services of HNTB to conduct the technical work required to fulfill Part 150 analysis and documentation requirements. Stantec is responsible for the overall document submittal, as well as the forecasting effort. HNTB completed the development of the NEMs and the analysis and update of the NCP program.

1.4.6 Federal Aviation Administration (FAA)

The FAA has ultimate review authority over the NEMs submitted under Part 150. FAA review includes an assessment of both the adequacy of the technical documentation and the broader issues related to satisfying the Part 150 process requirements.

FAA's participation includes the following:

- When the Airport submits the Part 150 documentation to the FAA for review, the FAA's New England Region-Airports Division will conduct an initial, local review to determine if it satisfies all NEM and NCP checklist requirements.

- The FAA's New England Region – Airports Division is responsible for the final review of the NEM documentation for adequacy in satisfying technical and legal requirements and approval of any revisions to the NCP.

1.5 NEM/NCP Update Study Goals

The overall goal of the NEM/NCP Update is to develop an existing condition (2018) and a forecast future condition (2023) NEM, and to update the Airport's NCP thereby defining necessary continued implementation of mitigation programs currently underway. The previous NEMs represented existing (2014) and future (2019) conditions and were accepted by the FAA in September 2014. The WMDC's ongoing voluntary acquisition program uses boundaries established in the existing (2014) NEM.

Several goals have been identified to guide the development of the 14 CFR Part 150 NEM/NCP Update. These goals include:

- Develop an understanding of probable future noise levels including any potential changes to the C-5M mission;
- To characterize and present to the public, local jurisdictions, and other interested parties the existing and reasonably foreseeable future noise levels associated with aircraft activity at the Airport;
- To identify existing and potentially non-compatible land uses within the existing and future 65 and above Day-Night Average Sound Level (DNL) noise exposure contours;
- To identify the status of the measures that were recommended and

previously approved in the Airport's NCP; and

- To identify boundaries for the continuation of the WMDC, MassDOT and FAA-sponsored voluntary acquisition program, if any, based on the revised 65 DNL noise exposure contours and remaining within the context of Federal regulations and eligibility criteria, financial feasibility, and fairness to aviation and non-aviation interests.

CHAPTER 2: Existing and Forecast Flight Operations

This chapter describes existing and forecast aircraft operations at the Airport. Noise exposure is shown in the form of DNL noise contours. Part 150 requires the use of DNL noise contours to describe the noise environment around an airport.

The scope of this study is to quantify noise exposure for the following conditions:

- *Existing (2018) Conditions NEM*, which models anticipated conditions during the current year.
- *Future (2023) Conditions NEM*, which models future conditions in the fifth year following the year of submission.

The FAA requires the analyses of subsonic aircraft noise exposure around airports to be accomplished using the Aviation Environmental Design Tool (AEDT), a computer program distributed by the FAA. The latest version of AEDT (version 2d) was used for this study to model civilian aircraft and helicopter operations. The DoD maintains NOISEMAP a noise modeling tool similar to AEDT which the FAA accepts for the modeling of military aircraft and helicopter operations. The output from each noise model is combined in AEDT, as required by the FAA, to present DNL noise contours.

Both models use representative samples of actual data to develop noise exposure. Annual Average Day (AAD) operations are representative of all aircraft operations that occur over the course of a year and represent annual operations divided by 365

days. Runway and flight track use is also averaged over the same period.

Aircraft operations consist of departures and arrivals categorized by acoustical daytime and nighttime. For noise modeling, acoustical daytime is defined as 7:00 a.m. to 9:59 p.m., and nighttime is defined as 10:00 p.m. to 6:59 a.m. The DNL metric applies a 10-decibel (dB) penalty to nighttime flights due to the added intrusiveness of nighttime operations. Runway use, flight track location and use, and aircraft profiles define the paths that aircraft use as they fly to and from the Airport.

The noise models compute noise exposure (i.e., DNL) at points on the ground around the Airport. From the grid of points generated by the models, contours of equal sound level are drawn and overlaid onto land use maps.

The use of computer-based noise modeling allows for the projection of future forecasted noise exposure, which could not be accomplished with noise monitoring that can only assess existing noise exposure at a limited number of locations. When the calculations are made in a consistent manner, noise models are most accurate for comparing “before-and-after” noise effects resulting from forecast changes or potential alternatives. The noise models allow noise predictions for such forecast change actions without the need for noise monitoring over an extended period of time, or actual implementation of any forecast changes. The noise models allow for the evaluation of aircraft noise exposure at many more points,

thus permitting the development of DNL contours.

2.1 Airport Location and Layout

2.1.1 General information

The Airport is located approximately three (3) miles northeast of downtown Chicopee, Massachusetts, and is a joint-use military (Westover Air Reserve Base, WARB or Base) and civilian airfield (Westover Airport) that consists of approximately 2,500 acres of land in the City of Chicopee and the Town of Ludlow. The facility is operated under a joint use agreement with the USAF hosting the WMDC. The Base is accessed via James Street from Route 33/Memorial Drive. The civilian terminal area can be accessed via Westover Road from Route 33/Memorial Drive. The Airport is accessible from the Massachusetts Turnpike (Interstate I-90) at Route 33 and Interstate 291 (Exit 5). **Figure 2-1** presents the general location of the Airport.

2.1.2 Users

WARB is the nation's largest Air Force Reserve base and is home to the 439th Airlift Wing, which serves as the military host unit. The mission of the 439th Airlift Wing is to provide worldwide air movement of troops, supplies, equipment and medical patients. The Wing's flying unit is the 337th Airlift Squadron, which operates eight Lockheed C-5M Super Galaxy (C-5M) model aircraft. The C-5M is used for missions involving outsized and oversized cargo that no other aircraft can carry.

The Base is also home to several tenant units including 302D Maneuver Enhancement Brigade, 655 Regional Support Group, Marine Support Squadron Six, a marine corps site support element, Marine Wing Support Squadron 472 (Detachment B), and the US Army Corps of


Engineers. Also based at Westover ARB is the Defense Contract Management Administration office, an Armed Forces Reserve Center, a US Army Reserve Center, 302nd Brigade, 665th Area Support Group, 226th and 304th Transportation Company, 382nd Military Police Battalion, the Springfield Military Entrance Processing Station, the Massachusetts National Guard, and two US Marine Corps Recruiting Centers (active and reserve). Transient military aircraft not assigned to one of the military tenants also frequent the facility.

The Airport is an FAA, and Transportation Security Administration certified air carrier facility handling scheduled public charter flights and general aviation traffic. The WMDC has acquired and developed over 1,300 acres of surplus military property to form three industrial parks. The WMDC manages day-to-day operations at the Airport, and the continuing development of commercial and industrial real estate at each of the industrial parks. A 15,000 square foot passenger terminal and over 300,000 square feet of hangar space are available.

The Airport lies at an elevation of approximately 241 feet above mean sea level and maintains two runways (Runway 05/23 and Runway 15/33). The primary runway (Runway 05/23) is oriented in a north-south direction with a length of 11,597 feet and a width of 300 feet. There is a displaced threshold on the Runway 05 end (to the south) of approximately 1,200 feet, meaning the landing threshold is approximately 1,200 feet from the end of the runway. Both Runway 05 and Runway 23 provide an Instrument Landing System for aircraft arrivals in adverse weather.

The crosswind runway (Runway 15/33) is 7,082 feet long and 150 feet wide and is oriented in an east-west direction. The Massachusetts State Police Air Wing is


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

**Vicinity Map
Figure 2-1**



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI

located on the airfield to the northwest of the Runway 05 end and conducts helicopter operations. A drop zone is utilized for military training activity, located on the north side of the Airport.

Figure 2-2 presents an illustration of the airfield layout, including the location of airport users, runways, and other facilities.

2.1.3 Weather and Climate

Runway use and the operational characteristics of aircraft are heavily influenced by weather conditions, including temperature, humidity and wind speed. Weather conditions also influence the propagation of sound. As the temperature increases, the density of air decreases; this reduces wing lift and engine thrust, which results in increased takeoff distance and a lower climb rate. Therefore, departing aircraft are at a lower altitude, and noise exposure generally increases. Conversely, noise exposure is decreased on cold days when aircraft have improved performance capabilities.

Humidity does not significantly impact aircraft performance, however in conjunction with temperature; humidity does impact the propagation of sound. In general, sound travels farther in more humid conditions. Humidity is highest at night and gradually drops during the day, generally reaching its lowest point in the afternoon.

Wind speed and direction primarily determine runway selection and operational flow. Aircraft generally takeoff and land into the wind (known as a headwind) whenever possible. Headwinds reduce an aircraft's takeoff and landing distance and increase climb rate. Aircraft can operate with significant crosswinds (winds blowing to the side of the aircraft): up to about 20 knots for a typical large air carrier size aircraft. Aircraft can operate with limited tailwinds (winds

blowing to the rear of the aircraft): up to 10 knots for a typical large air carrier size aircraft. Tailwinds increase takeoff and landing distance. Winds in excess of crosswind and tailwind limits generally force aircraft to use a different runway. The wind at the Airport is generally from the south and north, and favor operations on the existing runways, which are aligned accordingly.

AEDT default average weather conditions were used as input for each noise model. The default weather temperature for the Airport was missing in AEDT, and the most recent 30-year average temperature was applied. On average, weather conditions at the Airport averaged 50.0 degrees Fahrenheit, 6.6 knots wind speed, and 65.3% relative humidity.

2.1.4 Airspace and Air Traffic Control

The airspace and air traffic control procedures in use at the Airport direct the flow of aircraft in and out of the area. As a result, they are an essential component in determining cumulative noise exposure. The Westover Tower, located near the geographic center of the airport northeast of the East Ramp, is generally staffed and operational between the hours of 7:00 a.m. to 11:00 p.m. Through prior arrangement, the Westover Tower may remain open to accommodate air traffic during the hours of 11:00 p.m. and 7:00 a.m.





2.2 Existing (2018) Conditions

This section describes noise model operational inputs, including flight operations, aircraft database, flight profiles, runway use, and flight track location and use. Each noise model uses these inputs to compute noise exposure on the ground. The data in this section provides an overview of the aircraft operations included in the noise model.

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

-  Westover Air Reserve Base Installation Area
-  Westover Metropolitan Development Corporation Aviation Property
-  County Boundary
-  Town Boundary

**Airfield Layout
Figure 2-2**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

2.2.1 Flight Operations and Fleet Mix

Flight (or aircraft) operations include the numbers of arrivals, departures, and closed pattern (touch-and-go) operations conducted by each type of aircraft. Two groups of users primarily fly operations: USAF users (including operations by the 337th Airlift Squadron (flying the C-5M), other based users, and transient military aircraft); and civilian operators, which include all other operations. Information on the types of aircraft, the time of operations, and other relevant noise model input was determined through consultation with the Westover Tower, FAA, and non-government sources.

Because no single source can provide the level of flight data required for AEDT and NOISEMAP input, flight data activity is the compilation from several sources. The resources include: air traffic activity reports and control tower flight strips for calendar year 2017 from Westover Tower; FAA activity from the Traffic Flow Management Systems County (TFMSC) for the period from January 2017 through March 2018; and flight data from FlightAware, a non-government business that provides flight tracking and data reports for the 12-month period from April 2017 through March 2018. As a supplement consultation with Westover Tower personnel, 439th Airlift Wing pilots and staff, and WMDC staff supplemented the quantitative data.

The data was assembled and organized to form the base year (2018) operations. This data is representative of the average conditions anticipated in the base year.

The noise models contain noise and performance data on nearly all aircraft types commonly flown in the US. Most of the military aircraft data used in AEDT comes from NOISEMAP, the Air Force's computer model for evaluating military aircraft noise

exposure. The data is used to model an aircraft's departure and arrival flight profiles and resultant noise exposure. Aircraft that are not specifically included in the database (such as those with unique engine combinations) are modeled using appropriate substitution aircraft and criteria per the FAA's pre-approved substitution list. Coordination with the FAA's Office of Environment and Energy was undertaken to assist in the identification of appropriate aircraft to be used in the model when a pre-approved substitution was not available and is included in **Appendix C**.

The base year of operations (2018) is presented in **Table 2.1**. The table includes the identification of the fleet mix, its corresponding noise model aircraft type, and the number of average daily arrivals, departures, and closed pattern operations by day and night. On average, the Airport sees approximately 54.1 daily operations (of which 21.21 are performed by the C-5M Super Galaxy), which equates to an annual total of approximately 19,754 aircraft operations.

Overall, operations are predominantly flown by military aircraft (approximately 77%). Most of the aircraft activity at the Airport is flown by the 337th Airlift Squadron flying the C-5 aircraft, which fly approximately 260 days per year. Helicopter operations also represent a significant percentage of the overall activity at the Airport.

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update

Table 2.1
2018 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	* Super Galaxy	C5-M	2.04	0.03	2.04	0.01	17.10	-	21.21
Military	JET	Boeing Globemaster 3	C17	0.29	0.00	0.29	0.00	-	-	0.59
Military	JET	Boeing Sentry TF33/E3C	E3A	0.01	-	0.01	-	-	-	0.02
Military	JET	Boeing F-15 Eagle	F15E	0.28	-	0.28	-	-	-	0.56
Military	JET	Boeing Raptor F22	F22	0.01	-	0.01	-	-	-	0.01
Military	JET	Boeing KC-135 Stratotanker	KC-135R	0.47	-	0.47	-	-	-	0.95
Military	JET	Extender	KC10A	0.28	-	0.28	-	-	-	0.55
Military	MET	Lockheed 130 Hercules	C130H&N&P	0.31	0.00	0.31	0.00	0.82	-	1.45
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.06
Military	HEL	Boeing CH-47 Chinook	CH47D	2.12	-	2.12	-	2.19	-	6.43
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.68	-	4.68	-	2.19	-	11.56
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02
Civil	JET	Airbus A319	A319-131	0.02	-	0.02	-	-	-	0.03
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Boeing 737-400	737400	0.12	-	0.12	-	-	-	0.24
Civil	JET	Boeing 737-700	737700	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing 737-800	737800	0.04	-	0.04	-	-	-	0.09
Civil	JET	Boeing 757-200	757PW or 757RR	0.01	-	0.01	-	-	-	0.02
Civil	JET	Raytheon/Beech Beechjet 400/T-1	MU3001	0.05	-	0.05	-	-	-	0.11
Civil	JET	Cessna Citation CJ2	CNA500	0.07	-	0.07	-	-	-	0.13
Civil	JET	Cessna Citation CJ3	CNA500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna 500/Citation I	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.10	-	0.10	-	-	-	0.20
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	-	0.04	-	-	-	0.07

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update

Table 2.1
2018 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.08	-	0.08	-	-	-	0.17
Civil	JET	Cessna Excel/XLS	CNA560XL	0.13	-	0.13	-	-	-	0.27
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation Sovereign	CNA680	0.06	-	0.06	-	-	-	0.13
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation X	CNA750	0.07	-	0.07	-	-	-	0.14
Civil	JET	Bombardier (Canadair) Challenger 300	CL600	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier Challenger 300	CL600	0.03	-	0.03	-	-	-	0.06
Civil	JET	Bombardier Challenger 600/601/604	CL600	0.10	-	0.10	-	-	-	0.21
Civil	JET	Bombardier CRJ-200	CL600	0.02	-	0.02	-	-	-	0.04
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.05	-	0.05	-	-	-	0.10
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer 190	EMB190	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	CNA55B	0.09	-	0.09	-	-	-	0.18
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Dassault Falcon 2000	CNA750	0.13	-	0.13	-	-	-	0.27
Civil	JET	Dassault Falcon 900	CNA750	0.02	-	0.02	-	-	-	0.04
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	-	0.12	-	-	-	0.23
Civil	JET	Dassault Falcon F7X	CNA750 or GIV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Gulfstream G280	IA1125	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	-	0.01	-	-	-	0.01

Table 2.1
2018 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Gulfstream IV/G400	GIV	0.29	-	0.29	-	-	-	0.58
Civil	JET	Gulfstream V/G500	GV	0.27	-	0.27	-	-	-	0.54
Civil	JET	Gulfstream	GV	0.02	-	0.02	-	-	-	0.05
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	-	0.04	-	-	-	0.07
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	-	0.05	-	-	-	0.09
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	-	0.02	-	-	-	0.04
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	-	0.06	-	-	-	0.12
Civil	JET	Boeing P-8 Poseidon	737800	0.06	-	0.06	-	-	-	0.12
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech Baron 55	BEC58P	0.02	-	0.02	-	-	-	0.03
Civil	MEP	Beech 58	BEC58P	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech 76 Duchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus A400M Atlas	C-130E	0.01	-	0.01	-	-	-	0.02
Civil	MET	Beech Super King Air 350	DHC6	0.38	-	0.38	-	-	-	0.76
Civil	MET	Beech 200 Super King	DHC6	0.88	-	0.88	-	-	-	1.76

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update

Table 2.1
2018 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MET	Raytheon 300 Super King Air	DHC6	0.07	-	0.07	-	-	-	0.13
Civil	MET	Beech King Air 90	DHC6	0.03	-	0.03	-	-	-	0.05
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	CASA CN-235	SF340	0.05	-	0.05	-	-	-	0.10
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American AA-5 Traveler	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza 33	GASEPV	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Beech Bonanza 35	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza 36	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Skyhawk 172/Cutlass	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna 177 Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna Skylane 182	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cessna 206 Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna 210 Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Diamond Star DA40	COMSEP	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01

Table 2.1
2018 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Pilatus PC-12	CNA208	0.43	-	0.43	-	-	-	0.85
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Civil	SET	Raytheon Texan 2	GASEPF	0.01	-	0.01	-	-	-	0.02
Total				15.89	0.03	15.89	0.01	22.30	-	54.12

Source: Stantec and HNTB Analysis, 2018.

DRAFT

2.2.2 Aircraft Flight Profiles

Flight profiles model the vertical paths of aircraft during departure and arrival to determine the altitude, speed, and engine thrust of an aircraft at any point along a flight track. The noise model uses this information to calculate noise exposure on the ground along each track section.

Profiles are unique to each aircraft type and are based on operating procedures, temperature, and aircraft operating weight. Detailed information on aircraft flight profiles, under varying conditions, is stored in the noise model aircraft database.

The climb rate and flight profile of departing aircraft can vary considerably. New, modern aircraft have higher thrust engines and improved wing designs which results in an increased climb rate as compared to older aircraft. Modern jet engines are also much quieter than their predecessors, even though they can produce more thrust. Temperature, takeoff weight, and airline operating procedures are also important factors that affect climb rate.

The AEDT aircraft database groups aircraft-specific profiles by stage length, which refers to the length of the trip to be made by the aircraft type. For departures, AEDT assumes aircraft weight increases with stage, or trip length, because of the need for more fuel and that each aircraft type's takeoff distance and climb performance is different for each stage length. High-weight (long trip, high stage length) aircraft have increased takeoff distances and lower climb rates than lighter (short trip) aircraft for a given aircraft type.

Arriving civilian aircraft do not use stage lengths, as they are modeled using a standard three-degree approach path. AEDT has a database of standard arrival flight profiles for each modeled aircraft type.

When the 2013 AICUZ and the 2014 NEM studies were developed, there were 16 C-5A/Bs based at CEF. The first C-5B left CEF for an upgrade to a C-5M in 2015. Due to budget cuts in 2015, the number of the based C-5s were reduced from 16 to eight. In January 2017, the last C-5B left CEF for the scheduled upgrade. Ever since, all eight C-5Bs have been upgraded to C-5Ms and returned to CEF.

Information for the operations flown by the C-5A/B aircraft were collected and modeled in the 2013 AICUZ study. After consultation with a 439th Airlift Wing C-5M pilot, the flight paths modeled in the 2013 AICUZ study were confirmed to remain valid for the C-5M.¹ The C-5M standard flight profiles were provided by the USAF noise modeling team and were also confirmed by the C-5M pilot.

2.2.3 Runway Use

Runway use is determined by several factors, including safety, wind, weather, traffic demand, runway capacity, direction of flight, and prescribed runway use procedures. The Westover Tower assigns runway use with consideration to all of these factors. Runway use was evaluated based on a series of categories, including by military and civilian operations, and by aircraft type including jets, single and multi-engine turboprop, single- and multi-engine piston, and helicopter operations. **Table 2.2** presents the overall runway use, including military and civilian operations.

Table 2.2
Overall Runway Usage

Civilian			
Operation Type	Runway	Day	Night
Arrival	05	20%	20%
	23	80%	80%
Departure	05	80%	80%
	23	20%	20%
Touch-and-Go	05	20%	0%
	23	80%	0%
Military			
Operation Type	Runway	Day	Night
Arrival	05	19%	38%
	23	61%	59%
	15	0%	0%
	33	1%	2%
	32DZ	1%	1%
	Helipad	19%	0%
Departure	05	13%	29%
	23	27%	59%
	15	1%	2%
	33	3%	10%
	Helipad	56%	0%
Touch-and-Go	05	20%	0%
	23	58%	0%
	15	3%	0%
	33	10%	0%
	32DZ	10%	0%

Notes: Total may not sum due to rounding.
32DZ denotes use of the Drop Zone (see Figure 2-2).


Source: HNTB Analysis.

Civilian operations remain primarily on the main runway (Runway 05/23), and operations are predominantly to and from the north (arrivals to Runway 23, and departures from Runway 05). Military operations use both runways but remain concentrated on the longer primary runway as well. The crosswind runway (Runway 15/33) includes a smaller number of arrivals, departures and closed pattern (touch-and-go) operations.

2.2.4 Flight Track Locations and Use

Modeled flight tracks depict the approximate paths, or ground tracks, that aircraft use as they travel to and from the airport. Flight tracks are intended to be representative of typical aircraft operations at the Airport. As with runway use, flight track use reflects the percentage of annual operations that use a specific flight route, grouped by arrival or departure and daytime or nighttime. **Figures 2-3 through 2-6** present the noise model representative flight tracks used by both


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- Civilian Arrival Flight Track
- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

Flight Tracks – Civilian Fixed Wing Arrival Figure 2-3



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis






Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




Military flight tracks not shown; all remain consistent with the AICUZ.

USDA-FSA-APFO

LEGEND


-  Civilian Departure Flight Track
-  Westover Air Reserve Base Installation Area
-  Westover Metropolitan Development Corporation Aviation Property
-  County Boundary
-  Town Boundary

Flight Tracks – Civilian Fixed Wing Departure Figure 2-4



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis






Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




Military flight tracks not shown; all remain consistent with the AICUZ.

USDA-FSA-APFO

LEGEND


-  Helicopter Arrival Flight Track
-  Westover Air Reserve Base Installation Area
-  Westover Metropolitan Development Corporation Aviation Property
-  County Boundary
-  Town Boundary

Flight Tracks – Civilian Helicopter Arrival Figure 2-5








Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

-  Helicopter Departure Flight Track
-  Westover Air Reserve Base Installation Area
-  Westover Metropolitan Development Corporation Aviation Property
-  County Boundary
-  Town Boundary

Flight Tracks – Civilian Helicopter Departure Figure 2-6



0 1,500 3,000 6,000 Feet

Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis

civilian and military aircraft, including specific procedures flown by the C-5 aircraft.

2.2.5 Run-up/Maintenance Operations

Run-up operations increase the engine throttle while the aircraft is on the ground. Run-ups are usually not associated with arrival or departure operations but are used as part of maintenance and engine warm-up procedures.

The Airport is one of three C-5 inspection/repair facilities for the Air Force and conducts maintenance procedures on both based C-5 aircraft and those assigned to other bases. For the NEM, C-5 maintenance activity was collected for a 12-month period from Base personnel and input into the noise model. Generally, run-ups are performed on the East Ramp with the aircraft oriented at 330 degrees, while a majority of engine run-up activity is conducted between the hours of 7:00 a.m. and 9:59 p.m.

2.3 Future (2023) Conditions

Part 150 regulations require that the forecast condition be representative of operations anticipated to occur five years following the year of submission. As such, conditions were forecast for calendar year 2023, and factors that influence noise exposure, including forecast operations, runway use, flight track locations and use, engine run-up activity, and any changes to the airfield were evaluated. The forecasts were developed based on discussions with staff of the 439th Airlift Wing and WMDC. The Air Force does not anticipate any appreciable increase in operations in the next five years. Whereas WMDC does foresee an increase in flight operations based on improved economic conditions in the region and the opening of MGM Resorts International casino in Springfield, MA in August 2018.

2.3.1 Flight Operations and Fleet Mix

Operations, including the types, frequencies, and time of day of operations, were forecast for 2023. The forecast included a 0.7% annual growth rate with a 3.4% increase over the next five years for military activity resulting in an increase from 15,900 to 16,400 operations in 2023. The military fleet mix will remain unchanged.

Civilian operations were forecast to increase approximately 5.1% per year (25.5% between 2018 and 2023), from 3,870 annual operations to 4,850. The fleet mix is expected to change slightly as larger business jets frequent the airport.

Overall, total aircraft operations will increase from 19,750 to about 21,300 (rounded), or 7.7% in calendar year 2023. This equates to approximately 57.0 operations on an average annual day. **Table 2.3** provides a summary of the forecast (2023) operations.

2.3.2 Aircraft Flight Profiles

There are no changes to the flight profiles used by aircraft in 2023.

2.3.3 Runway Use

Runway use in 2023 is forecast to remain unchanged from the existing (2018) condition.

2.3.4 Flight Track Locations and Use

The location and frequency of use of flight tracks is forecast to remain unchanged from the existing (2018) condition.

2.3.5 Run-up/Maintenance Operations

The run-up operations associated with the C-5M aircraft are forecast to increase at the same rate as the increase of the C-5M operations.

Table 2.3
2023 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	* Super Galaxy	C5A	2.08	0.03	2.08	0.01	17.81	-	22.01
Military	JET	Boeing Globemaster	C17	0.30	0.00	0.30	0.00	-	-	0.61
Military	JET	Boeing Sentry TF33/E3C	E3A	0.02	-	0.02	-	-	-	0.03
Military	JET	Boeing F-15 Eagle	F15A or F15E	0.30	-	0.30	-	-	-	0.60
Military	JET	Boeing Raptor F22	F22	0.01	-	0.01	-	-	-	0.02
Military	JET	Boeing KC-135 Stratotanker	KC-135R	0.49	-	0.49	-	-	-	0.99
Military	JET	Extender	KC10A	0.29	-	0.29	-	-	-	0.58
Military	HEL	Boeing CH-47 Chinook	CH47D	2.16	-	2.16	-	2.19	-	6.52
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.71	-	4.71	-	2.19	-	11.62
Military	MET	Lockheed Hercules	C130HP	0.33	0.00	0.33	0.00	1.10	-	1.76
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.07
Civil	JET	Airbus	A319-131	0.02	-	0.02	-	-	-	0.03
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Boeing	737400	0.14	-	0.14	-	-	-	0.27
Civil	JET	Boeing	737700	0.04	-	0.04	-	-	-	0.08
Civil	JET	Boeing	737800	0.51	-	0.51	-	-	-	1.01
Civil	JET	Boeing	757PW or 757RR	0.02	-	0.02	-	-	-	0.03
Civil	JET	Raytheon Beechjet	MU3001	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna Citation CJ2	CNA500	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna Citation CJ3	CNA500	0.05	-	0.05	-	-	-	0.11
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna 500/Citation I	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.11	-	0.11	-	-	-	0.22
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	-	0.04	-	-	-	0.08
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.10	-	0.10	-	-	-	0.19

Table 2.3
2023 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Cessna Excel/XLS	CNA560XL	0.14	-	0.14	-	-	-	0.27
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation Sovereign	CNA680	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation X	CNA750	0.08	-	0.08	-	-	-	0.16
Civil	JET	Bombardier Challenger	CL600	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier Challenger	CL600	0.03	-	0.03	-	-	-	0.06
Civil	JET	Bombardier Challenger	CL600	0.10	-	0.10	-	-	-	0.21
Civil	JET	Bombardier CRJ-200	CL600	0.02	-	0.02	-	-	-	0.04
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.07	-	0.07	-	-	-	0.14
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer 190	EMB190	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	CNA55B	0.07	-	0.07	-	-	-	0.14
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Falcon 2000	CNA750	0.14	-	0.14	-	-	-	0.27
Civil	JET	Falcon 900LX	CNA750	0.02	-	0.02	-	-	-	0.04
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	-	0.12	-	-	-	0.23
Civil	JET	Falcon 7X	CNA750 or GIV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Gulfstream 280	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier Global 7000	BD-700-1A10 or BD-700-1A11	0.01	-	0.01	-	-	-	0.01

Table 2.3
2023 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Gulfstream IV/G400	GIV	0.29	-	0.29	-	-	-	0.58
Civil	JET	Gulfstream 550	GV	0.27	-	0.27	-	-	-	0.55
Civil	JET	Gulfstream 650	GV	0.03	-	0.03	-	-	-	0.05
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	-	0.04	-	-	-	0.07
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	-	0.05	-	-	-	0.09
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	-	0.02	-	-	-	0.04
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	-	0.06	-	-	-	0.12
Civil	JET	Boeing P-8 Poseidon	737800	0.10	-	0.10	-	-	-	0.19
Civil	JET	Pilatus PC-24	CNA55B	0.07	-	0.07	-	-	-	0.14
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech Baron	BEC58P	0.03	-	0.03	-	-	-	0.05
Civil	MEP	Beech 58	BEC58P	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech Dutchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus	C-130E	0.01	-	0.01	-	-	-	0.02

Table 2.3

2023 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MET	Raytheon Beech King Air	DHC6	0.38	-	0.38	-	-	-	0.77
Civil	MET	Raytheon Beech King Air	DHC6	0.89	-	0.89	-	-	-	1.78
Civil	MET	Raytheon Super King Air	DHC6	0.08	-	0.08	-	-	-	0.16
Civil	MET	Beech King Air 90	DHC6	0.03	-	0.03	-	-	-	0.05
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	CASA CN-235	SF340	0.05	-	0.05	-	-	-	0.10
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza	GASEPV	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Skyhawk	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna Skylane	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cessna Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Diamond Star DA40	GASEPV	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05

Table 2.3

2023 Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Pilatus PC-12	CNA208	0.44	-	0.44	-	-	-	0.88
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Civil	SET	Raytheon Texan 2	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02
Total				16.85	0.03	16.85	0.01	23.29	-	57.03

Source: Stantec and HNTB Analysis, 2018.

CHAPTER 3: Noise and Land Use Compatibility

This section reviews the Federal and local land use guidelines related to compatibility with aircraft noise exposure and aeronautical uses, and the development of land use data needed for the analyses required in Part 150. Note that **Appendix D** presents an introduction to the relevant fundamentals of acoustics and noise terminology and the effects of noise on human activity.

A discussion of existing and future land use compatibility relative to the Existing (2018) and Future (2023) NEMs is included in Chapter Four.

3.1 Land Use Guidelines

Land use guidelines provide the primary means of preventing new non-compatible development within the 65 db DNL noise contours. The following sections provide a description of federal and local land use guidelines.

3.1.1 Federal Guidelines

The degree of annoyance that people experience from aircraft noise varies, depending on their activities at any given time. For example, people are usually less disturbed by aircraft noise when they are shopping, working, or driving than when they are at home. Transient hotel and motel residents seldom express as much concern with aircraft noise as do permanent residents of an area. The concept of “land use compatibility” has arisen from this systematic variation in community reaction to noise.

In a Part 150 Study, DNL noise values have the following two principal uses:

- Provide a basis for comparing existing noise conditions to the effects of noise abatement procedures and/or forecast changes in airport activity; and
- Provide a quantitative basis for identifying potential noise impacts and mitigation.

Both of these functions require the application of objective criteria for evaluating noise impacts. Reproduced in **Table 3.1**, Part 150 provides the FAA’s recommended guidelines for noise and land use compatibility evaluation. In setting the various compatibility guidelines, however, the regulations state that the designations do not constitute a Federal determination that any use of land covered by the [noise compatibility] program is acceptable or unacceptable under federal, state, or local law. The responsibility for determining the acceptable and permissible land uses and the relationship between specific properties and specific noise contours rests with the local authorities. FAA determinations under Part 150 are not intended to substitute federally determined land uses for those determined to be appropriate by local authorities in response to locally determined needs and values in achieving noise compatible land uses.

The FAA’s guidelines represent a compilation of the results of scientific research into noise-related activity interference and attitudinal response.

However, reviewers of DNL contours should recognize the highly subjective nature of an individual's response to noise, and that special circumstance can affect individual tolerances. For example, a high, non-aircraft background noise level can reduce the significance of aircraft noise, such as in areas consistently exposed to relatively high levels of vehicular traffic noise. Alternatively, residents of areas with unusually low

background noise levels may find relatively low levels of aircraft noise annoying.

The response may also be affected by expectation and experience. People may become accustomed to a level of exposure that guidelines typically indicate may be unacceptable. Conversely, minor changes in exposure may generate a response that is far greater than that which the guidelines suggest.

Table 3.1
Part 150 Noise and Land Use Compatibility* Guidelines

Land Use	Yearly Day-Night Average Sound Level, DNL, in Decibels					
	<65	65-70	70-75	75-80	80-85	>85
<i>Residential Use</i>						
Residential, other than mobile homes and transient lodgings	Y	N(a)	N(a)	N	N	N
Mobile home parks	Y	N	N	N	N	N
Transient lodgings	Y	N(a)	N(a)	N(a)	N	N
<i>Public Use</i>						
Schools	Y	N(a)	N(a)	N	N	N
Hospitals and nursing homes	Y	25	30	N	N	N
Churches, auditoriums, and concert halls	Y	25	30	N	N	N
Governmental services	Y	Y	25	30	N	N
Transportation	Y	Y	Y(b)	Y(c)	Y(d)	Y(d)
Parking	Y	Y	Y(b)	Y(c)	Y(d)	N
<i>Commercial Use</i>						
Offices, business and professional	Y	Y	25	30	N	N
Wholesale and retail--building materials, hardware and farm equipment	Y	Y	Y(b)	Y(c)	Y(d)	N
Retail trade--general	Y	Y	25	30	N	N
Utilities	Y	Y	Y(b)	Y(c)	Y(d)	N
Communication	Y	Y	25	30	N	N
<i>Manufacturing and Production</i>						
Manufacturing, general	Y	Y	Y(b)	Y(c)	Y(d)	N
Photographic and optical	Y	Y	25	30	N	N
Agriculture (except livestock) and forestry	Y	Y(f)	Y(g)	Y(h)	Y(h)	Y(h)
Livestock farming and breeding	Y	Y(f)	Y(g)	N	N	N
Mining and fishing, resource production and extraction	Y	Y	Y	Y	Y	Y
<i>Recreational</i>						
Outdoor sports arenas and spectator sports	Y	Y(e)	Y(e)	N	N	N
Outdoor music shells, amphitheaters	Y	N	N	N	N	N
Nature exhibits and zoos	Y	Y	N	N	N	N
Amusements, parks, resorts and camps	Y	Y	Y	N	N	N
Golf courses, riding stables, and water recreation	Y	Y	25	30	N	N

Table 3.1

Part 150 Noise and Land Use Compatibility* Guidelines

Key to Table 3.1	
SLUCM	Standard Land Use Coding Manual
Y(Yes)	Land use and related structures compatible without restrictions.
N(No)	Land use and related structures are not compatible and should be prohibited.
NLR	Noise Level Reduction (outdoor to indoor) to be achieved through incorporation of noise attenuation into the design and construction of the structure.
25, 30, or 35	Land use and related structures generally compatible; measures to achieve NLR of 25, 30, or 35 dB must be incorporated into design and construction of structure.

* The designations contained in this table do not constitute a Federal determination that any use of land covered by the program is acceptable or unacceptable under Federal, state, or local law. The responsibility for determining the acceptable and permissible land uses and the relationship between specific properties and specific noise contours rests with the local authorities. FAA determinations under Part 150 are not intended to substitute Federally determined land uses for those determined to be appropriate by local authorities in response to locally determined needs and values in achieving noise compatible land uses.

Notes to Table 3.1

- (a) Where the community determines that residential or school uses must be allowed, measures to achieve outdoor-to-indoor NLR of at least 25 dB and 30 dB should be incorporated into building codes and be considered in individual approvals. Normal residential construction can be expected to provide a NLR of 20 dB, thus, the reduction requirements are often stated as 5, 10, or 15 dB over standard construction and normally assume mechanical ventilation and closed windows year round. However, the use of NLR criteria will not eliminate outdoor noise problems.
- (b) Measures to achieve NLR of 25 dB must be incorporated into the design and construction of portions of these buildings where the public is received, office areas, noise-sensitive areas or where the normal noise level is low.
- (c) Measures to achieve NLR of 30 dB must be incorporated into the design and construction of portions of these buildings where the public is received, office areas, noise-sensitive areas or where the normal noise level is low.
- (d) Measures to achieve NLR of 35 dB must be incorporated into the design and construction of portions of these buildings where the public is received, office areas, noise-sensitive areas or where the normal noise level is low.
- (e) Land use compatible provided special sound reinforcement systems are installed.
- (f) Residential buildings require an NLR of 25.
- (g) Residential buildings require an NLR of 30.
- (h) Residential buildings not permitted.

Source: 14 Code of Federal Regulations Part 150, *Airport Noise Compatibility Planning*, Appendix A, Table 1.

The cumulative nature of DNL means that the same level of noise exposure can be achieved in an infinite number of ways. For example, a reduction in a small number of relatively noisy operations may be counterbalanced by an increase in relatively

quiet flights, with no net change in DNL. Residents of the area may be highly annoyed by the increased frequency of operations, despite the seeming maintenance of the noise *status quo*.

Part 150 guidelines specify that all land uses are normally compatible with aircraft noise exposure levels at or below 65 DNL. This guideline is supported formally by standards adopted by the Department of Housing and Urban Development (HUD). HUD standards address whether sites are eligible for Federal funding support. These standards, set forth in 24 CFR Part 51 *Environmental Criteria and Standards*, define areas with DNL exposure not exceeding 65 dB as acceptable for HUD assistance or subsidy. Areas exposed to noise levels between 65 and 75 DNL are “normally unacceptable,” and require special abatement measures and review. Those areas at 75 DNL and above are “unacceptable” except under limited circumstances.

As with the previous Part 150 Study and NEM Updates, this NEM/NCP Update uses the Federal Part 150 guidelines to assist in identifying potential land use incompatibilities surrounding the Airport.

3.1.2 Local Land Use Guidelines

The Airport is located in the City of Chicopee and Town of Ludlow in Hampden County, Massachusetts and is bordered to the north by the towns of South Hadley and Granby in Hampshire County. The area was relatively undeveloped when the Westover Base was dedicated in 1946; however, development has increased to the south and west and industrial, and low-to-medium density residential development has emerged to the north and east. The Airport is now located close to the largest population center in Western Massachusetts but is also near rural areas that could be susceptible to sprawling residential development. The region is unique in that it continues to experience suburban sprawl without population growth.²

Each of the cities/towns have a municipal zoning ordinance to regulate land use.

Despite recommendations in previous Part 150 studies and updates, the Town of Ludlow is the only community within the affected noise area (within the DNL 65 dB contour) with land use tools that have been implemented to mitigate or prevent non-compatible uses. Ludlow’s Aircraft Flight overlay district prohibits the use of adult care facilities, schools, hospitals, daycare centers, auditoriums, places of worship and concert halls.

As stated in the 2013 WARB AICUZ, local governments have implemented height restrictions to help maintain existing land use characteristics. While none of these height restrictions were designed specifically by FAA (i.e., FAR Part 77) obstruction limits, they tend to be compatible with them.

PVPC serves as a regional planning agency for these jurisdictions, and is the primary agency responsible “for increasing communication, cooperation, and coordination among all levels of government within the region’s 43 cities and towns as well as the private business and civic sectors in order to benefit the Pioneer Valley region and to improve its residents’ quality of life.”³ PVPC provides planning guidance to communities and maintains general zoning data, but the agency does not regulate zoning or subdivision regulations.

3.2 Development of Land Use and Population Data

This section describes the development of land use and population data, and existing and future land use in the vicinity of the Airport. Land use and population data, and ultimately the noise impact analysis discussed in Chapter 4 was developed using a Geographic Information System (GIS). The GIS facilitated a detailed, comprehensive analysis of the geographical relationships

and patterns emerging from the region surrounding the Airport.

Land use data and aerial photography were obtained from the Office of Geographic Information (MassGIS).⁴ The most recent available US Census Bureau data (2010) was used to compile demographic information, such as housing units and population. Population estimates were developed using the population in the affected Census blocks in Hampden County and Hampshire County. Demographic data was correlated to land use data using GIS. This data served as the baseline land use database for the NEM/NCP Update.

3.3 Existing Generalized Land Use

Generalized land use was collected from MassGIS, and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. **Figure 3-1** depicts the types of existing land uses surrounding the Airport. Land uses were generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Transportation, and Water. Requests for land use verification were submitted to nearby jurisdictions (Chicopee, Ludlow, Granby). Any updates to the land use maps were made based on responses from these communities. Correspondence is included in **Appendix E**. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified in Figure 3-1.

Land use north of the Airport, in Granby, is classified as Open/Agricultural/Recreational and Residential, with small pockets of Commercial/ Industrial. In Ludlow to the east of the Airport, land use is predominantly Open/ Agricultural/ Recreational (Westover Conservation Area) and Residential. Public/Quasi-Public land use (Hampden

County Jail) is adjacent to the Base to the east. On the west side of the Airport in Chicopee, nearest to the James Street Gate, land uses are a combination of Public/Quasi-Public and Residential. Adjacent to Airport property, just west of the Runway 5 end are Commercial/Industrial uses (Westover Industrial Park). Further to the west of the Airport in Chicopee is more dense land use development, including predominantly residential areas with pockets of commercial uses. To the south, land uses in Chicopee are predominantly Open/ Agricultural/Recreational and Residential with interspersed Industrial and Commercial uses. Further south, Springfield is developed with primarily Residential, Industrial and Commercial land uses.

3.3.1 Noise-Sensitive Resources


Part 150 requires consideration of noise sensitive public buildings and historic properties. MassGIS data for historic resources were used to identify locations of schools and historic properties. Places of worship were identified using the most recent information available using Google Maps.

3.4 Existing Generalized Zoning

Zoning establishes permitted and non-permitted uses in areas within a town, municipality or county. A jurisdiction's zoning code, through an ordinance and a map, provides regulations pertaining to the types of uses allowed and elements of buildings such as height, density, and siting. A zoning code helps to promote orderly growth within a community. Each jurisdiction in the vicinity of the Airport is responsible for the development and implementation of its own zoning regulations.

Generalized zoning GIS data was collected from PVPC, except the City of Chicopee and is shown in **Figure 3-2**. The City provided

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




USDA-FSA-APFO

LEGEND


- | | |
|---|---|
| ■ Commercial/Industrial | ■ Transportation |
| ■ Open/Agricultural/Recreational | ■ Water |
| ■ Public/Quasi-Public | ■ WARB Installation Area |
| ■ Residential | ■ WMDC Aviation Property |
| ■ Previously Acquired Property under the Voluntary Acquisition Program | ■ County Boundary |
| ■ Cemetery | ■ Town Boundary |
| ■ Institutional | ⚓ Place of Worship |
| | ⚓ School |
| | ○ National Register of Historic Places |
| | △ Local Historic District |

Generalized Existing Land Use Figure 3-1



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




USDA-FSA-APFO

LEGEND

- | | | |
|------------------------|---|-------|
| WARB Installation Area | Mixed Use | Water |
| WMDC Aviation Property | Residential (Single Family) | |
| Central Business | Residential (Multi Family, Low/Med Density) | |
| General Business | Residential (Multi Family, High Density) | |
| General Industrial | Residential-Agricultural | |
| Highway Business | Professional & Research Park | |
| Limited Business | Not Zoned | |

Generalized Zoning Figure 3-2



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Chicopee Planning Department - January 2018
 WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

updated (January 2018) zoning GIS data, which was converted into the generalized zoning categories for purposes of showing all zoning.⁵

The majority of the Airport and several areas adjacent to the west and northwest are zoned General Industrial, including the WMDC Aviation Property. To the west in Chicopee, the area is zoned predominantly Residential (Single-Family, Multi-Family [low/mid-density]), with properties along Memorial Drive and other roadways identified as Limited Business and Highway Business. The area adjacent to the Airport's James Street is zoned Mixed Use. South of the Airport in Chicopee is predominantly zoned Single-Family Residential with areas zoned as General Industrial, Limited Business, and Highway Business interspersed further south. South of Chicopee, the City of Springfield comprises the area's urban center and zoning classifications are more varied.

To the north of the Airport in Granby, land is predominantly zoned Single-Family Residential. The area beyond the Runway 23 end along the northeastern border of the Airport and immediately beyond in Ludlow (including the Westover Conservation Area) is zoned Residential-Agricultural. The area immediately east of the Airport in Ludlow is zoned Professional and Research Park.

3.5 Future Land Use

Valley Vision 4 is the Pioneer Valley's regional land use plan developed by the PVPC. The land use plan is intended to serve as a general guide and planning tool for the communities and others in managing growth and development. The map associated with future land use in the Pioneer Valley⁶ illustrates PVPC Priority Areas for Development and Priority Areas for Protection. Priority Areas suitable for development at


various densities, lands suitable for open space protection, and identifies areas that are suitable for study as Smart Growth Districts, as is shown in **Figure 3-3**. Land use in the vicinity of the Airport in the regional land use plan is primarily designated as Existing Developed Land area, with several areas of Land Suitable for Low-Density Residential, Agriculture or Forestry.

Land to the north and east of the Airport are identified as Land Suitable for Protected Open Space and Farmland. An area within the installation boundary near the Runway 05 end is classified as Developed Land Possibly Suitable for Infill.

In February 2014, the PVPC updated the regional land use plan with *Valley Vision 4: the Regional Land Use Plan for the Pioneer Valley*. *Valley Vision 4* is an update to *Valley Vision*, the Regional Land Use Plan for the Pioneer Valley. *Valley Vision* focuses on smart growth planning, in that "it is designed to promote compact, mixed-use growth in and around existing urban and town centers while promoting the protection of open space and natural resources."⁷ *Valley Vision 4* specifically provides updated smart growth strategies; a smart growth toolbox, Transit Oriented Development (TOD) Priority Locations, Strategies and Market Analysis; and Strategies for Enhancing Equity and Environmental Justice.














Potential impacts to future land use within the Future (2023) NEM are discussed in Section 4.3.

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




USDA-FSA-APFO

LEGEND

-  WARB Installation Area
-  WMDC Aviation Property
-  Open Water
-  Existing Developed Land
-  Existing Protected Land
-  Land Suitable for Protected Openspace & Farmland
-  Land Suitable for Environmental Protection and Low Density Residential, Agriculture or Forestry
-  Undeveloped Land Suitable for Smart Growth Districts
-  Land Suitable for Industrial or Commercial Development
-  Developed Land Possibly Suitable for Infill Development
-  Sensitive Land Within Smart Growth Boundary
-  County Boundary
-  Town Boundary

Regional Land Use Plan Map Figure 3-3



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Pioneer Valley Planning Commission, Aerial - USDA 2016, ESRI Data and HNTB Analysis

CHAPTER 4: Noise Exposure Maps

This chapter presents the land use information for the geographic area within the 65 DNL contour for the Existing (2018) and Future (2023) NEMs. The 65 DNL is the Federal significance threshold for aviation noise analysis.

Section 4.1 summarizes the development of the base map. Section 4.2 presents and discusses the graphic and tabular information for the Existing (2018) NEM. Section 4.3 presents the graphic and tabular information for the Future (2023) NEM.

4.1 Land Use Base Map

Noise exposure contours, when superimposed on the land use map, allow assessment of the underlying land use compatibility for existing and forecast noise exposure conditions. As discussed in Section 3.2, land use data and aerial photography were obtained from MassGIS.⁸ US Census Bureau data was not used or needed to compile demographic information for this NEM/NCP Update, as there are no residences (or population) within the 65+ DNL contours of the Existing (2018) or Future (2023) NEMs, as discussed in Sections 4.2 and 4.3.

As noted in Section 3.3, existing land uses in the vicinity of the Airport include Commercial/Industrial, Open/Agricultural/Public/Quasi-Public, Recreational, Residential, Cemetery, Institutional, Water, and Wetland.

The land uses within the affected noise area (within the 65+ DNL noise contours) fall within the jurisdictions of Chicopee and Ludlow, in Hampden County.

4.2 Noise Exposure Map for Existing Conditions (2018)


Figure 4-1 represents the existing conditions for the year of submission (2018), with the existing aircraft flight procedures, airport layout, aircraft operations, and other noise modeling assumptions described in Chapter 2.

The 65+ DNL noise exposure contours encompass approximately 613 acres (almost one square mile) in total. Of this acreage, approximately 597 acres are within Airport property. **Table 4.1** presents the range of land uses encompassed by the 65+ DNL noise exposure contour under the existing conditions. There are no residential land uses within the 65+ DNL noise exposure contour, nor are there any properties previously acquired by the Airport for noise abatement. An aerial map was also reviewed to determine if any houses exist within the 65+ DNL noise exposure contour. As no houses appear to be present, population counts were not needed. There are also no recreational uses or noise-sensitive locations within the 65+ DNL noise exposure contour. Thus there are no incompatible land uses when considering the FAA's Part 150 land use guidelines.

The entire 70+ DNL noise contour (approximately 229 acres/0.36 square miles) remains within the boundaries of the Airport. There are no incompatible land uses within the 70+ DNL noise contour.

There are no known non-residential noise-sensitive land uses, such as hospitals, places of worship, schools, historic sites, or nursing homes, within the 65+ DNL noise contours.


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| 2018 DNL Noise Contour | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | School |
| | National Register of Historic Places |
| | Local Historic District |
| | Place of Worship |

**Existing (2018) Conditions
Noise Exposure Map
Figure 4-1**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

Table 4.1
**Generalized Land Uses within the Existing (2018)
 Conditions 65 DNL Noise Exposure Contour**

Generalized Land Use	Land within Contour (acres)			
	65-70 DNL	70-75 DNL	75+ DNL	Total (65+ DNL)
Airport Property	368.4	171.3	57.2	596.9
Commercial/Industrial	1.7	0	0	1.7
Open/Agricultural	13.8	0	0	13.8
Recreational	0	0	0	0
Residential	0	0	0	0
Transportation/Utility	0	0	0	0
Voluntary Acquisition Property	0	0	0	0
Water	0.6	0	0	0.6
Wetland	0	0	0	0
Grand Total (acres)	384.5	171.3	57.2	613.0

Source: MassGIS, HNTB, 2018.

4.3 Noise Exposure Map for Future Conditions (2023)


DNL noise exposure contours prepared for the Future (2023) NEM are shown in **Figure 4-2**. The overall size of the 65 DNL noise exposure contour increases by approximately 40 acres to nearly 653 acres (slightly more than one square mile), due to an increase in operations. **Table 4.2** presents the existing land uses within the 65+ DNL noise exposure contours of the Future (2023) NEM. The Future (2023) NEM is based on forecast conditions without the implementation of any of the measures included in this study's NCP.

comprehensive plan (*Valley Vision 4*), future land uses within the 65-70 DNL noise exposure contour off Airport property include Existing Protected Land and Open Water only; uses that are not considered incompatible with the FAA's Part 150 land use guidelines.

The 65+ DNL noise exposure contour does not include any residential or recreational land uses. No population counts were needed as no residences appear to exist within the 65+ DNL noise exposure contour.

According to the Regional Land Use Plan Map associated with the most recent PVPC


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| 2023 DNL Noise Contour | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | School |
| | National Register of Historic Places |
| | Local Historic District |
| | Place of Worship |

**Future (2023) Conditions
Noise Exposure Map
Figure 4-2**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

Table 4.2

**Generalized Land Uses within the Future (2023)
Conditions 65 DNL Noise Exposure Contour**

Generalized Land Use	Land within Contour (acres)			
	65-70 DNL	70-75 DNL	75+ DNL	Total (65+ DNL)
Airport Property	386.8	163.7	76.2	626.7
Commercial/Industrial	1.8	0	0	1.8
Open/Agricultural	20.9	0	0	20.9
Recreational	0	0	0	0
Residential	0	0	0	0
Transportation/Utility	0	0	0	0
Voluntary Acquisition Property	0	0	0	0
Water	3.3	0	0	3.3
Wetland	0	0	0	0
Total	412.8	163.7	76.2	652.7

Source: MassGIS, HNTB 2018.

DRAFT

CHAPTER 5: Noise Compatibility Program

5.1 History of Noise Compatibility Planning at the Airport

Noise compatibility planning surrounding CEF began in earnest in the early 1990s through a series of joint studies. A Joint Land Use Study (JLUS) led by the PVPC was completed in 1995.

The JLUS was followed shortly thereafter by the Airport's first 14 CFR Part 150 Noise Compatibility Program study, sponsored by the WMDC. The JLUS recommendations were incorporated into the measures submitted to the FAA under the Part 150 NCP. The NEMs (for existing 1993 and forecast 1998 conditions) were completed in 1995. The FAA issued a Record of Approval of the NCP on January 26, 1996.

In 2001, a JLUS Update was undertaken. The JLUS Update coincided with an update of NEMs, developed for the FAA by HNTB Corporation. The updated land compatibility maps in the JLUS Project include the results of the NEM update. Work began in December 2001, and the final report was completed in October 2004. NEMs under the Part 150 study were prepared for existing 2003 and forecast 2008 conditions. A JLUS Update is currently under development as a cooperative land use planning effort by the USAF, PVPC, and WARB.⁹

The land use mitigation recommendations of the 2004 JLUS Update were included in the NEM Update for the Airport, consistent with the NCP that the FAA had reviewed in 1996. The FAA's responsibility for review of the NCP focused on the eligibility of the mitigation components (voluntary acquisition

and sound insulation). The FAA's comments and approval status of each of the measures are discussed under the detailed description of each.

In 2013, the USAF completed an AICUZ study, which included the development of a 2009 Noise Exposure Contour and a 2014 Forecast Noise Exposure Contour. Following completion of the AICUZ, an NEM/NCP Update was conducted with existing 2014 and future 2019 conditions. The purpose of resubmitting that NCP was to gain FAA approval of revising the voluntary acquisition program to include properties located in the future 2019 NEM. The FAA accepted the NEMs in September 2014 and issued a Record of Approval of the NCP on February 6, 2015.

This NEM/NCP Update is being conducted in response to a change in the fleet mix that was anticipated to result in a possible change to the noise contour. Since the last NEM/NCP Update in 2014, the 439th Airlift Wing transitioned from the C-5A/B Galaxy to the C-5M Super Galaxy, an upgraded version with new (quieter) engines and improved avionics. Due to the reduced size of the noise contours, it is prudent to update the NCP, and specifically the Airport's noise mitigation program.

It should be noted that this document only discusses those elements of the recommended NCP submitted in 1996, and the updated NCP approved in 2015. Other land use management strategies, as recommended by the previous or ongoing JLUS Update or AICUZ, are not discussed in

this document. It should also be noted that the FAA evaluation of these measures is done within the context of the Existing (2018) and forecast Future (2023) NEMs, and the reader should recognize that noise exposure can and will fluctuate based on the fleet mix at the Airport as well as the types and frequency of operations.

Noise programs at the Airport are funded through a combination of Federal, State and local funding. Nearly \$21 million has been used for noise studies and land acquisition through 2017. Of this funding amount, the FAA has contributed \$19.53 million, the MassDOT Aeronautics Division has contributed \$824,000, and the WMDC has contributed \$522,000.

5.2 2014 Noise Compatibility Program

The 2014 NCP consisted of an update to the 1996 NCP based on the noise contours of the existing 2014 and future 2019 NEMs. The Study provided an overview of all the noise mitigation measures previously approved in the 1996 ROA, with one proposed change; the WMDC proposed to expand the noise-land acquisition boundary from the 70 DNL noise contour, out to the 65 DNL noise contour. This measure was approved. All other previously approved (1996) measures were reviewed for their updated status, and for consistency with Part 150.

In February 2015, the FAA approved the NCP, which was submitted following the FAA's acceptance of the NEMs. The FAA's 1996 and 2015 Records of Approval are included in *Appendix B*.

The NCP included noise abatement measures, compatible land use measures, and program measures designed to abate

and mitigate the impacts of aircraft noise surrounding the Airport.

The following sections provide an overview and status update of each of the measures recommended in the NCP, including noise abatement, compatible land use planning, and program or implementation measures.

5.2.1 Noise Abatement Measures

Noise abatement measures are procedures or techniques used by aircraft to minimize the impact of noise on surrounding communities. Noise abatement measures are evaluated based on their feasibility, including regarding the aircraft's performance capabilities, the air traffic control environment, and their potential to reduce noise impacts within the 65 DNL noise contour.

The 2014 NCP evaluated the approved noise abatement measures originally included in the 1996 NCP. These measures were initially modeled and compared to the noise exposure contours developed under the 1996 Study, and those which provided a benefit (a reduction in the number of residences and estimated population within the 65 DNL noise contour) were included in the Airport's recommended plan submitted to the FAA. For the 1996 NCP, each of the four approved measures included consultation with the Westover Tower and Bradley Approach Control, the air traffic facility whose jurisdiction surrounds that of the Westover Tower. As part of the 2014 NCP review, the FAA disapproved two of the noise abatement measures, as they "provided no measurable benefit inside the 65 DNL noise contour:" the noise abatement departure procedures for civilian aircraft on Runway 23 and noise abatement departure procedures for civilian aircraft on Runway 05.

Measures were proposed for both civilian and military operations. The following

sections describe each of the measures, the FAA's conclusions at the time (approval or disapproval) and evaluates the procedure in the current environment.

Nighttime Preferential Runway Use for Civilian Aircraft

Description: This measure calls for civilian aircraft to use Runway 05 for departures and Runway 23 for arrivals to the maximum extent practicable. The WMDC Board of Directors first adopted this preferential runway use in 1987. Thus, the recommended pattern of civilian operations would be departures to the north and arrivals from the north, taking advantage of the lower density of residential land uses in Granby and Ludlow. If nighttime operations increased to levels predicted at the time, the WMDC would reevaluate the measure to achieve a more balanced level of runway use.

This non-mandatory measure was recommended in part to assist noise abatement efforts once the Westover Tower remained open for 24 hours per day. At the time, civilian operations could not operate at the Airport when the Westover Tower was closed (11:00 p.m. to 7:00 a.m.) without prior arrangement. The 1996 NCP included the assumption that the Westover Tower would begin 24-hour operations, although this has not yet occurred. Implementing this measure was forecast to reduce the estimated population within the 65 DNL noise contour south of the Airport.

FAA Finding 1996: The FAA approved this measure as voluntary.

FAA Finding 2015: Re-approved.

Current Status: Preferential runway use for civilian operations remains consistent, mostly due to the location of the general aviation facilities (FBO/terminal area).

Approximately 80% of civilian operations occur to or from the north. The Westover Tower remains closed to civilian operations from 11:00 p.m. to 7:00 a.m., although the WMDC can request a waiver for the Westover Tower to open before 7:00 a.m. or remain open past 11:00 p.m. if needed.

Costs associated with implementing this measure would be administrative, and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

Noise Abatement Departure Procedures for Military Aircraft on Runway 23

The 1996 NCP proposed that select military C-5M departures from Runway 23 follow a noise abatement procedure. Military operations primarily depart from Runway 23 (south). At the time of the study, C-5M Runway 23 departures were required to climb on runway heading (approximately 230 degrees) until radar contact is confirmed with Bradley Approach Control, located 20 miles south of Westover. Due to the distance between the radar and aircraft, this sometimes resulted in the overflight of heavily populated areas until radar contact was established and aircraft were instructed to turn towards their destination. The proposed flight paths included earlier left or right turns, coordinated with the Bradley Approach Control.

FAA Finding 1996: The FAA approved this measure as voluntary, as implementation was shown to reduce the estimated population within the 65 DNL noise contour.

FAA Finding 2015: Re-approved.

Current Status: The military continues to use Runway 23 as the primary departure runway. C-5M operations use an early turn to

the west to avoid overflight of more densely populated areas.

Noise Abatement Departure Procedures for Civilian Aircraft on Runway 23

Description: This measure proposed that civilian aircraft, notably larger and louder aircraft that depart from Runway 23, use a noise abatement heading of 205 or 255 degrees, rather than flying a runway heading (approximately 230 degrees).

FAA Finding 1996: The FAA approved this measure as voluntary. Implementation of this measure would have, at the time, assisted in reducing the number of residences within the 65 DNL noise contour.

FAA Finding 2015: Disapproved. This measure provides no measurable benefit within the 65 DNL contour at this time. Meaningful noise abatement procedures may be designed and recommended under a future NCP update, as the local conditions warrant.

Current Status: Many of the larger aircraft that operated at the Airport before 2000, such as 727's or 737-200's, were phased out of the fleet through the passage of the Airport Noise and Capacity Act of 1990 (Stage 2 aircraft weighing less than 75,000 pounds will be prohibited from operating in 2015). As a result, the overall fleet of passenger aircraft is quieter. Noise modeling input data, developed in consultation with the Westover Tower, indicates that a majority (approximately 72%) of civilian departures from Runway 23 depart on a course that follows the runway heading (approximately 230 degrees), while approximately 28% depart from the runway and turn towards a heading of approximately 270 degrees.

In consideration of the current and forecast levels of civilian air traffic, the current types

of aircraft in use at the airport, and the predominant noise characteristics of the military fleet, it is not expected that use of the noise abatement procedure would reduce the noise-sensitive land uses within the 65 DNL however it continues to be recommended as a voluntary measure.

Costs associated with implementing this measure would be administrative and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

Noise Abatement Departure Procedures for Civilian Aircraft on Runway 05

Description: The measure called for aircraft, upon departure from Runway 05 and once safely airborne, to turn to an ATC-assigned heading of 080 degrees, then follow instructions issued by Bradley Approach Control towards their respective navigation fix. This early turn of approximately 30 degrees would route departing aircraft further away from the Acrebrook subdivision, taking advantage of more compatible land uses. The measure was proposed to be applied between the hours of 10:00 p.m. and 6:00 a.m. and was estimated to reduce potential noise impacts in the Acrebrook subdivision, which was also proposed for eligibility under the voluntary acquisition program. The measure was proposed contingent upon FAA approval of the voluntary acquisition program (discussed in Section 5.2.2) to reduce noise north of the Airport, specifically in the Acrebrook neighborhood.

FAA Finding 1996: The FAA approved this measure as voluntary, as it would reduce the number of residences and estimated population within the 65 DNL noise contour.

FAA Finding 2015: Disapproved. This measure provides no measurable benefit within the 65 DNL contour at this time. Meaningful noise abatement procedures may be designed and recommended under a future NCP update, as the local conditions warrant.

Current Status: Generally, aircraft departures from Runway 05 fly a runway heading of approximately 50 degrees. In consideration of the current and forecast levels of civilian air traffic, the current types of aircraft in use at the airport, and the predominant noise characteristics of the military fleet, it is not expected that use of the noise abatement procedure would reduce the noise-sensitive land uses within the 65 DNL however it continues to be recommended as a voluntary measure.

Costs associated with implementing this measure would be administrative and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

5.2.2 Land Use Measures

Land use measures seek to correct existing non-compatible land uses and to prevent the development of land uses that could be impacted by noise from aircraft operations. It is essential to discuss the lines of authority for implementing any recommended measures. The WMDC does not control the land uses surrounding the Airport but can make recommendations in consultation with local jurisdictions. The recommended land use measures have historically included mitigation programs (voluntary acquisition and relocation, sound insulation) and preventive measures, which seek to limit the possibility of future non-compatible development.

All of the land use measures approved in the 1996 NCP continued to be recommended as part of the 2014 NCP, with one update to the voluntary land acquisition and relocation program, which the WMDC has continued to implement.

Voluntary Land Acquisition and Relocation Program

Description: The intent of the voluntary land acquisition and relocation program was to eliminate or significantly reduce the number of people remaining in areas of high noise exposure. The 1996 NCP identified approximately 150 residences exposed to 70 DNL, which was updated under the 2004 NEM Update to include approximately 416 potentially eligible structures (single and multi-family structures) within the 70 DNL of the 2003 NEM. The WMDC received funding from the FAA to initiate the voluntary acquisition program in 2005.

FAA Finding 1996: The FAA approved this measure as voluntary.

FAA Finding 2015 / Status: The boundaries for participation in the Voluntary Land Acquisition and Relocation Program were modified as part of the 2014 NCP to include residences exposed to noise levels 65 DNL and above of the Future (2019) NEM be included in the program. This was a change from the previously approved noise land acquisition program in the 70 DNL contour, and was the one measure proposed for revision in the 2014 NCP. Overall, the WMDC identified approximately 48 parcels for continued participation in the voluntary acquisition program.

The 2015 ROA approved the revised Voluntary Acquisition and Relocation Program, except for the identified parcels removed from the eligible noise contour. Due to changes in the aircraft fleet mix and

level of operations, some parcels once eligible for noise mitigation [were] not eligible at the time of the 2014 NCP.

Current Status: To date, a total of 55 properties, accounting for approximately 220 acres, have been acquired. Since the 2014 NCP, additional properties have been acquired, all to the north of the Airport. On the acquired properties, the homes have been or will be demolished (if present), and the land remains vacant (therefore compatible with aircraft operations). The WMDC is currently involved in negotiations with additional eligible properties.

Of the 55 total acquired properties, 46 properties are located in residential areas north of the airport; 30 properties in Granby and 16 properties in Ludlow, while the nine remaining properties are located to the south of the Airport in Chicopee. For each acquired property, an aviation easement is attached to the deed after parcel assembly is completed. Once acquired, the properties are maintained by the WMDC until a complete reuse and disposal plan is developed.

The anticipated benefit associated with this program was the elimination of non-compatible land uses within and adjacent to the 65 DNL noise contour. As there are no residences exposed to noise levels above 65 DNL within the Existing (2018) or Future (2023) NEM, this measure is not proposed for continuation in this NCP.

Voluntary Sound Insulation Program

Description: A sound insulation program is a voluntary program with the goal of providing acoustic treatment to eligible homes to reach a 5 dB improvement compared to existing indoor levels. FAA guidelines for sound insulation programs aim for an interior noise level of 45 dB.

The sound insulation program was initially identified to include those residences within the 65 DNL noise contour, in addition to residences located in the 70 DNL noise contour that declined participation in the voluntary acquisition program. In exchange for the installation of sound insulating materials, which typically include acoustically-rated windows and doors, and could include upgrades to mechanical systems, the property owner would be required to grant a noise easement.

FAA Finding 1996: The FAA approved this program.

FAA Finding 2015 / Status: The sound insulation program had not been implemented as of the 2014 NEM/NCP Update, and was not recommended in the 2014 NCP. The WMDC preferred to complete the voluntary acquisition program before initiating a sound insulation program. Any initiation of a sound insulation program would be approved in advance by the FAA, to ensure conformance with Part 150.

Current Status: As there are no residences exposed to noise levels above 65 DNL within the Existing (2018) or Future (2023) NEM, there is no proposal at this time for a sound insulation program. Thus, this measure is not proposed for continuation in this NCP.

Compatible Use Zoning

Description: Zoning for compatible land uses includes rezoning land that may be developed with noise-sensitive land uses, such as residences, places of worship, or schools. Rezoning would change the development potential of the land to a use that is more compatible with aircraft operations, such as industrial or open space. The 1996 NCP included specific recommendations for each city or town to minimize chances that new noncompatible

land uses will be developed within the 65 DNL contour. The 1996 NCP suggested that Chicopee, Granby, and Ludlow maintain their existing zoning but consider adopting overlay zoning and that Springfield and South Hadley maintain their existing industrial zoning classifications.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure for Part 150.

FAA Finding 2015 / Status: Portions of the Future (2019) NEM 65 DNL contour included residential zoning in Granby, residential-agricultural zoning in Ludlow, and general industrial and residential zoning in Chicopee. The 65 DNL noise contour did not include land within South Hadley or Springfield. The WMDC would continue to work with each jurisdiction to determine the feasibility of implementing the measure.

Current Status: Based on zoning information provided by MassGIS and the City of Chicopee, the Existing (2018) and Future (2023) NEM 65 DNL noise contour extends just off Airport property to the north into land zoned for Residential-Agricultural in the Town of Ludlow and to the south into a small area of land zoned for Residential (Single Family) in the City of Chicopee. Currently both areas where the noise contours extend into residentially-zoned areas are not developed. The Existing (2018) and Future (2023) NEM 65 DNL noise contours do not include land within Granby, South Hadley or Springfield, although aircraft do overfly these areas.

Although the 65 DNL noise contours do not impact existing residential development, it is recommended to prevent future non-compatible land uses by rezoning the residentially-zoned areas within the Future (2023) NEM in Chicopee and Ludlow to a

compatible zoning category to ensure that these areas are not developed with residential use in the future. This would prevent any future development of uses that are incompatible with airport operations. See **Figure 5-1** for the residentially-zoned properties proposed for rezoning and/or an airport overlay district, discussed in the next section.

Costs associated with implementing this measure would be administrative for the jurisdiction(s) if implemented, and the timeline for implementation would be dependent upon the jurisdictions' processes and requirements for approval.


Airport Overlay District

Description: An overlay district is a zoning technique which identifies additional restrictions on development in addition to the underlying zoning, by modifying (but not eliminating) the underlying zoning. Overlay districts offer an option to provide a more flexible development control than that of changing the allowed uses in entire zoning districts and focusing on only the portion of the community with potential non-compatible land uses.

Since 1992, the Town of Ludlow has had an Aircraft Flight Overlay District intended to protect the public health, safety, and general welfare, and to protect human life and property from hazards of aircraft noise and accident potential created by the Town's proximity to Westover.

By 1996, Ludlow had implemented the aircraft flight overlay district, encompassing the noise and accident potential zones from the AICUZ. At that time, hospitals, nursing homes, auditoriums and concert halls were prohibited within the overlay districts. Educational and religious institutions are permitted by right in all districts according to


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|------------------------|---|
| 2023 DNL Noise Contour | Residential (Single Family) |
| WARB Installation Area | Residential (Multi Family, Low/Med Density) |
| WMDC Aviation Property | Residential (Multi Family, High Density) |
| Central Business | Residential-Agricultural |
| General Business | Professional & Research Park |
| General Industrial | Not Zoned |
| Highway Business | Water |
| Limited Business | Proposed for Rezoning to Compatible Use |
| Mixed Use | |

Proposed Rezoning of Residential Parcels with 2023 NEM Figure 5-1



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Chicopee Planning Department - January 2018
 WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

the Massachusetts Zoning Enabling Act, and the Town had sought and received home rule authority from the state legislature to allow restriction of development of schools, day care centers, and houses of worship within accident potential zones. The existing overlay district does not prohibit residential land uses or impose sound insulating requirements on residential lands.

The initial NCP recommended that Chicopee and Granby adopt an airport overlay district which encompasses land within the 65 DNL contour and that the Town of Ludlow change the boundaries of its airport overlay district to include all of the land within the forecasted 1998 contour.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure for the purposes of Part 150.

FAA Finding 2015 / Status: No changes to the Town of Ludlow's overlay district had been implemented, and no other jurisdictions had developed an overlay district to date. The 65 DNL noise contour of the Future (2019) NEM extended into Ludlow, Granby and Chicopee. The WMDC would continue to work with each jurisdiction to determine the feasibility of implementing this measure.

Current Status: Changes to the Town of Ludlow's overlay district have still not been implemented, and no other jurisdictions have developed an overlay district to date. Although the Existing (2018) and Future (2023) NEM 65 DNL noise contours do not impact existing residential areas, implementation of an airport overlay district within the residentially-zoned areas of the Future (2023) NEM contour is recommended as it offers an additional level of protection and safety for residents. An overlay zone would prevent any future noncompatible

uses with airport operations. See Figure 5-1 for the residentially-zoned properties proposed for rezoning and/or an airport overlay district.

Costs associated with implementing this measure would be administrative for the jurisdiction(s) if implemented, and the timeline for implementation would be dependent upon the jurisdictions' processes and requirements for approval.

Subdivision Regulations

Description: Subdivision regulations describe the procedures and standards for the division of parcels of land, most notably for sale or development as smaller parcels. The use of subdivision regulations by a municipality prescribes certain conditions that must be met by a developer before receipt and recordation of a plat. Generally, amending subdivision regulations is most practical when large amounts of undeveloped land are present.

The 1996 NCP recommended that the Town of Granby, as the jurisdiction with the most notable assemblage of undeveloped land within the 65 DNL noise contour, amend their subdivision regulations to require noise easements to be obtained on newly created lots within the 65 DNL noise contour.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure for Part 150.

FAA Finding 2015 / Status: The Town of Granby had not included the recommendations requiring noise easements into their subdivision regulations. The 65 DNL noise exposure contour of the Future (2019) NEM extended into Granby, in areas where the WMDC was offering voluntary acquisition at the time. The WMDC

would work with Granby to determine the feasibility of implementing this measure.

Current Status: The 65 DNL noise exposure contour of the Existing (2018) and Future (2023) NEMs do not extend into the Town of Granby; thus, this measure is not proposed for continuation for this NCP.

5.2.3 Implementation, Monitoring, and Review Measures

Implementation, monitoring, and review measures are those that can be undertaken by the WMDC to track the progress of the recommended noise compatibility program. They include measures that are designed to increase awareness of noise abatement and mitigation, and provisions for the continued monitoring of noise surrounding an Airport.

The 1996 NCP identified four measures for inclusion in the program, as described in the following sections. The status of the measures was updated as part of the 2014 NCP. The current status provides the current update for this NCP.

Pilot Awareness Program

Description: This measure identified that the WMDC would publish a pamphlet of noise abatement practices to be distributed to civilian pilots through the aviation services provider and WMDC's airport management. The pamphlet would include a map of noise sensitive areas around the airport and describe the operational measures which WMDC has adopted for noise abatement, including the use of noise abatement departure procedures recommended by the National Business Aircraft Association or by individual aircraft manufacturers. The measure suggested that the WMDC would install signs in all terminal areas frequented by civilian pilots and along ramp and taxiway

areas controlled by WMDC, instructing pilots to follow noise abatement procedures.

FAA Finding 1996: This measure was approved by the FAA, with the caveat that the location and content of signs may be subject to FAA approval.

FAA Finding 2015 / Status: The WMDC had installed signs in the terminal area pilot lounge and in areas leading to airside facilities directing pilots to be aware of noise-sensitive locations around the Airport. The WMDC would further evaluate the feasibility of installing more permanent signs encouraging the use of the noise abatement procedures for civilian aircraft from Runways 5 and 23.

Current Status: No new signs have been added to encourage the use of the noise abatement procedures for civilian aircraft from Runways 5 and 23.

Costs associated with implementing this measure would be administrative and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

Public Awareness Program

Description: This measure served to increase public awareness in the surrounding communities regarding the latest developments in the noise compatibility program.

FAA Finding 1996: The FAA approved this measure.

FAA Finding 2015 / Status: As part of the voluntary acquisition program, the WMDC had maintained contact with property owners within the 65 DNL noise contours of the previous NEMs.

Current Status: Although the Voluntary Acquisition and Relocation Program is not proposed as part of this NCP as there are no residences within the 65 DNL contours, it is recommended that the WMDC continue to maintain contact with property owners within past program areas.

Costs associated with implementing this measure would be administrative and minimal to continue.

Monitoring Nighttime Operations and Runway Use

Description: This measure was intended to assist in the identification and quantification of nighttime aircraft activity, specifically during the hours in which the Westover Tower was closed. Information to be collected included the time, type of aircraft, registration/flight number, landing or take-off, runway used, and wind and weather conditions. The information would be used to determine compliance with WMDC's nighttime noise rule and to help provide guidance to Air Force contract tower personnel to determine compliance with the preferential runway use program.

FAA Finding 1996: The FAA approved in part and disapproved in part this measure. The FAA stated that using the data to ensure compliance with any rules that would essentially limit aircraft operations would require an additional noise study.

FAA Finding 2015 / Status: The Westover Tower tracked operations during hours the tower is open. Minimum operations occur during nighttime hours (10:00 p.m. to 7:00 a.m.). The additional information noted in the 1996 FAA Finding was not submitted, and therefore the partial disapproval remained in effect.

Current Status: The Westover Tower tracks operations during hours the tower is open.

Minimum operations occur during nighttime hours (10:00 p.m. to 7:00 a.m.).

However, the Airport is currently considering opening the Westover Airport for 24 hours per day and an Environmental Assessment is underway to evaluate potential impacts. Monitoring nighttime operations and runway use would help determine compliance with WMDC's nighttime noise rule and to help guide Air Force tower personnel to determine compliance with the preferential runway use program, if more nighttime operations were to occur. This measure is therefore carried forward.

Costs associated with implementing this measure would be administrative, and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

Periodic Updates of Noise Exposure

Description: This measure recommended the ongoing monitoring of changes in noise exposure at the Airport, primarily by focusing on the changes that would likely have the greatest impact to cause an increase in cumulative noise exposure. The original measure identified, as primary potential drivers of noise exposure, any planned changes in scheduled jet operations by civilian aircraft, any planned changes in nighttime operations by civil aircraft, or annual changes in total civil operations. Further, once noise exposure reached levels forecasted in the original NEM, the WMDC would update the Part 150 study.

1996 FAA Finding: The FAA approved this measure.

FAA Finding 2015 / Status: The WMDC has completed or supported multiple evaluations of noise exposure as a result of changes in

operations, including the 2014 NEM/NCP Update.

Current Status: As indicated in the introduction to the NCP in this chapter, the WMDC has completed or supported multiple evaluations of noise exposure as a result of changes in operations, including this update. WMDC will provide periodic NEM updates as required by law and regulation.

Costs associated with implementing this measure would be administrative, and the timeline for implementation would be dependent upon FAA and/or other responsible agency(ies) requirements for approval.

DRAFT

CHAPTER 6: Record of Consultation

The following sections describe the consultation with various parties as required by 14 CFR Part 150, including coordination meetings and plans for public involvement via public review of the Draft NEM/NCP Update document and a subsequent public meeting.

6.1 Meetings and Coordination

Multiple meetings and teleconferences were held throughout the development of the NEMs and update to the NCP to obtain and share information to ensure the most accurate information was available and incorporated into the NEMs. Consultation was undertaken with the 439th Airlift Wing to ensure C-5M flight paths from the 2013 AICUZ study and the standard C-5M flight procedures in the noise model are accurate. Site visits and multiple teleconferences were held with the Westover Tower to collect data on aircraft operations, including the frequency, types, and times of day of operations. Consultation was undertaken with other operators at the Airport, including the Massachusetts State Police Air Wing.

Land use verification letters were submitted to the nearby jurisdictions of Chicopee, Ludlow, and Granby to confirm the use of the most recent land use data available. To date, Ludlow and Chicopee have responded to confirm the existing land use mapping. Ludlow provided several updates to the Town's land use which were incorporated into the land use mapping. Correspondence with these jurisdictions is included in *Appendix E*.

6.2 Draft NEM/NCP Update Document

The updated NEMs, NCP, and related study data will be made available to the public for review and comment to satisfy Part 150 public involvement requirements. This opportunity for comment on the NEMs and NCP will be provided with the publication of the Draft NEM/NCP Update document and at a subsequent public meeting.

The locations where the hard copies of the Draft NEM/NCP Update are provided will be included in the Final NEM/NCP Update.

6.3 Public Information Workshop

This section will be updated with Public Information Workshop information once available. This workshop is intended to provide the public the opportunity to discuss the draft NEMs and NCP with project team members and to provide comments. *Appendix E* will provide copies of sign-in sheets, newspaper advertisements, meeting handouts, display boards and comments received.

The range of topics discussed at the public meeting will include the draft existing and future NEMs, a review of the Airport's existing NCP, and proposed revisions to the NCP.

6.4 Comments on the Draft Document

The publishing of the Draft document will include a 30-day comment period. A summary table of the comments and a response to each comment will be provided in the Final NEM/NCP Update. The comment letters will be provided in *Appendix E*.

Notes

- 1 In-person interview and email consultation with Colonel Ian Coogan of the Massachusetts Air Force Reserve 439th Airlift Wing.
- 2 Pioneer Valley Planning Commission, *Valley Vision 4: The Regional Land Use Plan for the Pioneer Valley*, Executive Summary, March 2014. <http://www.pvpc.org/sites/default/files/Executive%20Summary%20Land%20Use.pdf>, accessed 4/25/18, p. 4.
- 3 Pioneer Valley Planning Commission, “What is the Pioneer Valley Planning Commission?” <http://www.pvpc.org/about>, accessed 4/25/18.
- 4 Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, <http://www.mass.gov/anf/research-and-tech/it-serv-and-support/application-serv/office-of-geographic-information-massgis/datalayers/layerlist.html>, WMDC 2018, HNTB GIS (2018), Land Use (2005); USDA-FSA-APFO Massachusetts 2016 60cm NAIP Imagery.

City of Chicopee		Generalized Zoning (MassGIS)
BusA	Business A Districts	General Business
BusB	Business B Districts	Highway Business
BusC	Business C Districts	Highway Business
CBD	Central Business Districts	Central Business
ComA	Commercial A Districts	Limited Business
ComA1	Commercial A-1 Districts	Limited Business
Ind	Industrial Districts	General Industrial
Ind_IPUD1	Garden Industrial Planned Unit Development	General Industrial
Ind_IPUD2	Garden Industrial Planned Unit Development, Type II	General Industrial
MIXED	Mixed Use MXD District	Mixed Use
ResA	Residential A Districts	Residential (Single Family)
ResB	Residential B Districts	Residential (Multi Family, Low/Med Density)
ResC	Residential C Districts	Residential (Multi Family, Low/Med Density)
ResD	Residential D Districts	Residential (Multi Family, High Density)

- 6 Pioneer Valley Planning Commission, “PVPC Priority Areas for Development & Protection,” <http://www.pvpc.org/content/pvpc-priority-areas-development-protection>, accessed 5/8/2018.
- 7 Pioneer Valley Planning Commission, *Valley Vision 4: The Regional Land Use Plan for the Pioneer Valley*, February 2014 (accessed 5/17/18). <http://www.pvpc.org/sites/default/files/PVPC%20Valley%20Vision%204%20Land%20Use%20Plan%20FINAL%202-18-14.pdf>, p. 5 (accessed 5/17/18).
- 8 Executive Office for Administration and Finance, MassGIS Datalayers, <http://www.mass.gov/anf/research-and-tech/it-serv-and-support/application-serv/office-of-geographic-information-massgis/datalayers/layerlist.html>, Land Use (2005); USGS Color Ortho Imagery (2013).
- 9 Westover Air Reserve Base – Joint Land Use Plan Update 2018, http://www.pvpc.org/westover_jlus (accessed 5/24/18).

APPENDIX A

Part 150 NEM and NCP Checklists

[This page is left intentionally blank]

DRAFT

PART 150 NEM CHECKLIST – PART I

PROGRAM REQUIREMENT	YES	NO	SUPPORTING PAGES/REVIEW COMMENTS
I. Submitting And Identifying The NEM:			
A. Submission is properly identified:			
1. 14 C.F.R. Part 150 NEM?	✓		Chapter 1
2. NEM and NCP together?	✓		Letter of Transmittal, Sponsor Certification
3. Revision to NEMs FAA previously determined to be in compliance with Part 150?	✓		Chapter 1, Section 1.2
B. Airport and Airport Operator's name are identified?	✓		Letter of Transmittal, Sponsor Certification, Chapter 1, Section 1.4
C. NCP is transmitted by airport operator's dated cover letter, describing it as a Part 150 submittal and requesting appropriate FAA determination?	✓		Letter of Transmittal
II. Consultation: [150.21(b), A150.105(a)]			
A. Is there a narrative description of the consultation accomplished, including opportunities for public review and comment during map development?	✓		Chapter 6, Appendix E
B. Identification of consulted parties:			
1. Are the consulted parties identified?	✓		Chapter 6
2. Do they include all those required by 150.21(b) and A150.105(a)?	✓		Chapter 6
3. Agencies in 2, above, correspond to those indicated on the NEM?	✓		Chapter 6
C. Does the documentation include the airport operator's certification, and evidence to support it, that interested persons have been afforded adequate opportunity to submit their views, data, and comments during map development and in accordance with 150.21(b)?	✓		Sponsor Certification, Chapter 6 and Appendix E
D. Does the document indicate whether written comments were received during consultation and, if there were comments, that they are on file with the FAA regional airports division manager?	✓		Chapter 6, Appendix E
III. General Requirements: [150.21]			

A. Are there two maps, each clearly labeled on the face with year (existing condition year and one that is at least 5 years into the future)?	✓		Figures 4-1 and 4-2, Figures NEM-1 and NEM-2
B. Map currency:			
1. Does the year on the face of the existing condition map graphic match the year on the airport operator's NEM submittal letter?	✓		Sponsor Certification, Figure 4-1, Figure NEM-1
2. Is the forecast year map based on reasonable forecasts and other planning assumptions and is it for at least the fifth calendar year after the year of submission?	✓		Section 2.3 and 4.3, Figure 4-2, Figure NEM-2
3. If the answer to 1 and 2 above is no, the airport operator must verify in writing that data in the documentation are representative of existing condition and at least 5 years' forecast conditions as of the date of submission?			N/A
C. If the NEM and NCP are submitted together:			
1. Has the airport operator indicated whether the forecast year map is based on either forecast conditions without the program or forecast conditions if the program is implemented?	✓		Chapter 4
2. If the forecast year map is based on program implementation:			
a. Are the specific program measures that are reflected on the map identified?	✓		Chapter 5
b. Does the documentation specifically describe how these measures affect land use compatibilities depicted on the map?	✓		Chapter 5
3. If the forecast year NEM does not model program implementation, the airport operator must either submit a revised forecast NEM showing program implementation conditions [B150.3(b), 150.35(f)] or the sponsor must demonstrate the adopted forecast year NEM with approved NCP measures would not change by plus/minus 1.5 DNL? (150.21(d))			N/A
IV. Map Scale, Graphics, And Data Requirements: [A150.101, A150.103, A150.105, 150.21(a)]			
A. Are the maps of sufficient scale to be clear and readable (they must not be less than 1" to 2,000'), and is the scale indicated on the maps? <i>(Note (1) if the submittal uses separate graphics to depict flight tracks and/or noise monitoring sites, these must be of the same</i>	✓		Figures 4-1 and 4-2, Figures NEM-1 and NEM-2

<i>scale, because they are part of the documentation required for NEMs.)</i> <i>(Note (2) supplemental graphics that are not required by the regulation do not need to be at the 1" to 2,000' scale)</i>			
B. Is the quality of the graphics such that required information is clear and readable? (Refer to C. through G., below, for specific graphic depictions that must be clear and readable)	✓		Figures 4-1 and 4-2, Figures NEM-1 and NEM-2
C. Depiction of the airport and its environs:			
1. Is the following graphically depicted to scale on both the existing condition and forecast year maps?			
a. Airport boundaries	✓		NEM-1, NEM-2
b. Runway configurations with runway end numbers	✓		NEM-1, NEM-2
2. Does the depiction of the off-airport data include?			
a. A land use base map depicting streets and other identifiable geographic features	✓		NEM-1, NEM-2
b. The area within the DNL ¹ 65 dB (or beyond, at local discretion)	✓		NEM-1, NEM-2
c. Clear delineation of geographic boundaries and the names of all jurisdictions with planning and land use control authority within the DNL 65 dB (or beyond, at local discretion)	✓		NEM-1, NEM-2
D. 1. Continuous contours for at least the DNL 65, 70, and 75 dB?	✓		NEM-1, NEM-2
2. Has the local land use jurisdiction(s) adopted a lower local standard and if so, has the sponsor depicted this on the NEMs?		✓	
3. Based on current airport and operational data for the existing condition year NEM, and forecast data representative of the selected year for the forecast NEM?	✓		NEM-1, NEM-2, Chapter 2
E. Flight tracks for the existing condition and forecast year timeframes (these may be on supplemental graphics which must use the same land use base map and scale as the existing condition and forecast year NEM), which are numbered to correspond to accompanying narrative?	✓		Figure Noise Model Flight Tracks, Chapter 2, Figures 2-3 through 2-6
F. Locations of any noise monitoring sites <i>(these may be on</i>			N/A

<i>supplemental graphics which must use the same land use base map and scale as the official NEMs)</i>			
G. Noncompatible land use identification:			
1. Are noncompatible land uses within at least the DNL 65 dB noise contour depicted on the map graphics?	✓		NEM-1, NEM-2
2. Are noise sensitive public buildings and historic properties identified? (Note: If none are within the depicted NEM noise contours, this should be stated in the accompanying narrative text.)			None within 65 DNL contour, Section 4.2 and 4.3
3. Are the noncompatible uses and noise sensitive public buildings readily identifiable and explained on the map legend?	✓		None within 65 DNL contour, NEM-1, NEM-2
4. Are compatible land uses, which would normally be considered noncompatible, explained in the accompanying narrative?	✓		Section 4.2, previously acquired properties
V. Narrative Support Of Map Data: [150.21(a), A150.1, A150.101, A150.103]			
A. 1. Are the technical data and data sources on which the NEMs are based adequately described in the narrative?	✓		Chapter 2
2. Are the underlying technical data and planning assumptions reasonable?	✓		Sponsor Certification
B. Calculation of Noise Contours:			
1. Is the methodology indicated?	✓		Chapter 2
a. Is it FAA approved?	✓		Section 2.2
b. Was the same model used for both maps? <i>(Note: The same model also must be used for NCP submittals associated with NEM determinations already issued by FAA where the NCP is submitted later, unless the airport sponsor submits a combined NEM/NCP submittal as a replacement, in which case the model used must be the most recent version at the time the update was started.)</i>	✓		Section 2.2
c. Has AEE approval been obtained for use of a model other than those that have previous blanket FAA approval?			N/A
2. Correct use of noise models:			
a. Does the documentation indicate, or is there evidence, the airport operator (or its consultant) has adjusted or calibrated	✓		Section 2.2, Appendix C

FAA-approved noise models or substituted one aircraft type for another that was not included on the FAA's pre-approved list of aircraft substitutions?			
b. If so, does this have written approval from AEE, and is that written approval included in the submitted document?	✓		Section 2.2, Appendix C
3. If noise monitoring was used, does the narrative indicate that Part 150 guidelines were followed?			N/A
4. For noise contours below DNL 65 dB, does the supporting documentation include an explanation of local reasons? <i>(Note: A narrative explanation, including evidence the local jurisdiction(s) have adopted a noise level less than DNL 65 dB as sensitive for the local community(ies), and including a table or other depiction of the differences from the Federal table, is highly desirable but not specifically required by the rule. However, if the airport sponsor submits NCP measures within the locally significant noise contour, an explanation must be included if it wants the FAA to consider the measure(s) for approval for purposes of eligibility for Federal aid.)</i>			N/A
C. Noncompatible Land Use Information:			
1. Does the narrative (or map graphics) give estimates of the number of people residing in each of the contours (DNL 65, 70 and 75, at a minimum) for both the existing condition and forecast year maps?	✓		No residents residing in the contours, Section 4.2 and 4.3
2. Does the documentation indicate whether the airport operator used Table 1 of Part 150?	✓		Section 3.1.1
a. If a local variation to table 1 was used:			
(1) Does the narrative clearly indicate which adjustments were made and the local reasons for doing so?			N/A
(2) Does the narrative include the airport operator's complete substitution for table 1?			N/A
3. Does the narrative include information on self-generated or ambient noise where compatible or noncompatible land use identifications consider non-airport and non-aircraft noise sources?			N/A
4. Where normally noncompatible land uses			N/A

are not depicted as such on the NEMs, does the narrative satisfactorily explain why, with reference to the specific geographic areas?			
5. Does the narrative describe how forecast aircraft operations, forecast airport layout changes, and forecast land use changes will affect land use compatibility in the future?	✓		Section 4.3
VI. Map Certifications: [150.21(b), 150.21(e)]			
A. Has the operator certified in writing that interested persons have been afforded adequate opportunity to submit views, data, and comments concerning the correctness and adequacy of the draft maps and forecasts?	✓		Sponsor Certification
B. Has the operator certified in writing that each map and description of consultation and opportunity for public comment are true and complete under penalty of 18 U.S.C. § 1001?	✓		Sponsor Certification

DRAFT

PART 150 NCP CHECKLIST – PART I

PROGRAM REQUIREMENT	YES	NO	SUPPORTING PAGES/REVIEW COMMENTS
I. Submitting And Identifying The NCP:			
A. Submission is properly identified:			
1. 14 C.F.R. Part 150 NCP?	✓		Letter of Transmittal, Sponsor Certification, Chapter 1
2. NEM and NCP together?	✓		Letter of Transmittal, Sponsor Certification
3. Program revision? (To what extent has it been revised?)	✓		Letter of Transmittal
B. Airport and Airport sponsor's name are identified?	✓		Letter of Transmittal, Sponsor Certification, Chapter 1, Section 1.4
C. NCP is transmitted by airport sponsor's cover letter?	✓		Letter of Transmittal
II. Consultation: (including public participation): [150.23]			
A. Documentation includes narrative of public participation and consultation process?	✓		Chapter 6, Appendix E
B. Identification of consulted parties:			
1. All parties in 150.23(c) consulted?	✓		Chapter 6
2. Public and planning agencies identified?	✓		Chapter 6
3. Agencies in 2, above, correspond to those affected by the NEM noise contours?	✓		Chapter 6
C. Satisfies 150.23(d) requirements by:			
1. Documentation shows active and direct participation of parties in B., above?	✓		Chapter 6
2. Active and direct participation of general public and opportunity to submit their views, data, and comments on the formulation and adequacy of the NCP?	✓		Chapter 6
3. Participation was prior to and during development of NCP and prior to submittal to FAA?	✓		Chapter 6
4. Indicates adequate opportunity afforded to all consulted parties to submit views, data, etc.?	✓		Chapter 6
D. Evidence is included there was notice and opportunity for a public hearing on the final NCP?	✓		Chapter 6
E. Documentation of comments:			
1. Includes summary of public hearing comments, if hearing was	✓		Chapter 6

held?			
2. Includes copy of all written material submitted to operator?	✓		Chapter 6, Appendix E
3. Includes operator's responses/disposition of written and verbal comments?	✓		Chapter 6, Appendix E
F. Is there written evidence from the appropriate office within the FAA that the sponsor received informal agreement to carry out proposed flight procedures?			N/A
III. Noise Exposure Maps: [150.23, B150.3; 150.35(f)] <i>(This section of the checklist is not a substitute for the Noise Exposure Map checklist. It deals with maps in the context of the Noise Compatibility Program submission.)</i>			
A. Inclusion of NEMs and supporting documentation:			
1. Map documentation either included or incorporated by reference?	✓		Chapter 4
2. Maps previously found in compliance by FAA?			NEMs submitted with NCP
3. FAA's compliance determination still valid?			
a. Existing condition NEM represents conditions at the airport at the time of submittal of the NCP for FAA approval?	✓		Letter of Transmittal, NEM-1, Chapter 4
b. Forecast condition NEM represents conditions at the airport at least 5 years into the future from the date of submittal of the NCP to the FAA for approval?	✓		Letter of Transmittal, NEM-2, Chapter 4
c. Sponsor letter confirming elements (a) and (b), above, if date of submission is either different than the year of submittal of the previously approved NEMs or over 12 months from the date shown on the face of the NEM?			N/A
d. If (a) through (c) cannot be validated, the NEMs must be redone and resubmitted as per 150.21.			N/A
4. Does 180-day period have to wait for map compliance finding?	✓		
B. Revised NEMs submitted with program: (Review using NEM checklist if map revisions included in NCP submittal. Report the applicable findings in the spaces below after a full review using the NEM checklist and narrative.)			
1. Revised NEMs included with program?	✓		NEM-1, NEM-2
2. Has airport sponsor requested in writing that FAA make a determination on the NEM(s), showing NCP measures in place, when NCP	✓		Letter of Transmittal

approval is made?			
C. If program analysis uses noise modeling:			
1. INM, HNM, or FAA-approved equivalent?	✓		AEDT, Chapter 4
2. Monitoring in accordance with A150.5?			N/A
D. One existing condition and one forecast-year map clearly identified as the official NEMs?	✓		NEM-1, NEM-2
IV. Consideration of Alternatives: [B150.7, 150.23(e)(2)]			
A. At a minimum, were the alternatives below considered, or if they were rejected was the reason for rejection reasonable and based on accurate technical information and local circumstances?			
1. Land acquisition and interests therein, including air rights, easements, and development rights?	✓		NCP Update only, Section 5.2.2
2. Barriers, acoustical shielding, public building soundproofing		✓	NCP Update only, Chapter 5
3. Preferential runway system	✓		NCP Update only, Section 5.2.1
4. Voluntary flight procedures	✓		NCP Update only, Section 5.2.1
5. Restrictions described in B 150.7 (taking into account Part 161 requirements)		✓	NCP Update only, Chapter 5
6. Other actions with beneficial impact not listed in the regulation		✓	NCP Update only, Chapter 5
7. Other FAA recommendations (see D, below)		✓	NCP Update only, Chapter 5
B. Responsible implementing authority identified for each considered alternative?	✓		Chapter 5
C. Analysis of alternative measures:			
1. Measures clearly described?	✓		Chapter 5
2. Measures adequately analyzed?	✓		Chapter 5
3. Adequate reasoning for rejecting alternatives?	✓		Chapter 5
D. Other actions recommended by the FAA: As the FAA staff person familiar with the local airport circumstances, determine whether other actions should be added? <i>(List separately, or on back, actions and describe discussions with airport sponsor to have them included prior to the start of the 180-day cycle. New measures recommended by the airport sponsor must meet applicable public participation and consultation with officials before they can be submitted to the FAA for action. See E., below.)</i>			N/A

V. Alternatives Recommended for Implementation: [150.23(e), B150.7(c); 150.35(b), B150.5]			
A. Document clearly indicates:			
1. Alternatives that are recommended for implementation?	✓		Chapter 5
2. Final recommendations are airport sponsor's, not those of consultant or third party?	✓		Letter of Transmittal
B. Do all program recommendations:			
1. Relate directly or indirectly to reduction of noise and noncompatible land uses? <i>(Note: All program recommendations, regardless of whether previously approved by the FAA in an earlier Part 150 study, must demonstrate a noise benefit if the airport sponsor wants FAA to consider the measure for approval in a program update. See E., below.)</i>	✓		Chapter 5
2. Contain description of each measure's relative contribution to overall effectiveness of program?	✓		Chapter 5
3. Noise/land use benefits quantified to extent possible to be quantified? <i>(Note: some program management measures cannot be readily quantified and should be described in other terms to show their implementation contributes to overall effectiveness of the program.)</i>	✓		Chapter 5
4. Does each alternative include actual/anticipated effect on reducing noise exposure within noncompatible area shown on NEM?	✓		Chapter 5
5. Effects based on relevant and reasonable expressed assumptions?	✓		Chapter 5
6. Does the document have adequate supporting data that the measure contributes to noise/land use compatibility?	✓		Chapter 5
C. Analysis appears to support program standards set forth in 150.35(b) and B150.5?	✓		Chapter 5
D. When use restrictions are recommended for approval by the FAA:			
1. Does (or could) the restriction affect Stage 2 or Stage 3 aircraft operations <i>(regardless of whether they presently operate at the airport)? (If the restriction affects Stage 2 helicopters, Part 161 also applies.)</i>			N/A
2. If the answer to D.1 is yes, has the			N/A

airport sponsor completed the Part 161 process and received FAA Part 161 approval for a restriction affecting Stage 3 aircraft? Is the FAA's approval documented? For restrictions affecting only Stage 2 aircraft, has the airport sponsor successfully completed the Stage 2 analysis and consultation process required by Part 161 and met the regulatory requirements, and is there evidenced by letter from FAA stating this fact?			
3. Are non-restrictive alternatives with potentially significant noise/compatible land use benefits thoroughly analyzed so that appropriate comparisons and conclusions among all alternatives can be made?			N/A
4. Did the FAA regional or ADO reviewer coordinate the use restriction with APP-400 prior to making determination on start of 180-days?			N/A
E. Do the following also meet Part 150 analytical standards?			
1. Recommendations that continue existing practices and that are submitted for FAA re-approval? <i>(Note: An airport sponsor does not have to request FAA re-approval if noise compatibility measures are in place from previously approved Part 150 studies. If the airport has implemented the measures as approved in the previous NCP, the measures may be reported and modeled as baseline conditions at the airport.)</i>			N/A
2. New recommendations or changes proposed at the end of the Part 150 process?		✓	
F. Documentation indicates how recommendations may change previously adopted noise compatibility plans, programs, or measures?	✓		Chapter 5
G. Documentation also:			
1. Identifies agencies that are responsible for implementing each recommendation?	✓		Chapter 5
2. Indicates whether those agencies have agreed to implement?	✓		Chapter 5
3. Indicates essential government actions necessary to implement recommendations?	✓		Chapter 5

H. Timeframe:			
1. Includes agreed-upon schedule to implement alternatives?	✓		Chapter 5
2. Indicates period covered by the program?	✓		Chapter 5
I. Funding/Costs:			
1. Includes costs to implement alternatives?	✓		Chapter 5
2. Includes anticipated funding sources?	✓		Chapter 5
VI. Program Revision: [150.23(e)(9)] Supporting documentation includes provision for revision? <i>(Note: Revision should occur when it is likely a change has taken place at the airport that will cause a significant increase or decrease in the DNL noise contour of 1.5 dB or greater over noncompatible land uses. See §150.21(d))</i>	✓		Letter of Transmittal

DRAFT

APPENDIX B

1996 and 2015

FAA Record of Approval (ROA)

[This page is left intentionally blank]

DRAFT

Part 150: Records of Approval

Westover Air Reserve Base, Chicopee Falls, Massachusetts

Approved on 1/26/96

1.0 INTRODUCTION

The Westover Metropolitan Development Corporation sponsored an Airport Noise Compatibility Planning Study under a Federal Aviation Administration (FAA) grant, in compliance with Federal Aviation Regulations (FAR), Part 150. The Noise Exposure Maps (NEM) were developed and submitted to FAA on January 26, 1994. The NEM was determined to be in compliance on July 31, 1995. The determination was announced in the Federal Register on August 11, 1995. The Noise Compatibility Program (NCP) was submitted to FAA for review and approval on June 2, 1995 and notice of FAA's review of the NCP was announced concurrently in the August 11, 1995, Federal Register.

The Part 150 Study was closely monitored by an advisory committee which represented area municipalities, airport users, and community residents. A series of advisory committee meetings was held, with the airport's consultant presenting material and findings. Two public information meetings were held. The consultant addressed comments at all of these meetings, and subsequent written comments as well.

The study focused on defining an optimum set of noise and land use mitigation measures to improve compatibility between airport operations and community land use, presently and in the future.

The resultant program is described in detail in the "Noise Compatibility Program" section of the study, sections 2 and 3. Section 2 describes the NCP elements and Section 3 analyzes alternatives and contains an implementation plan. The program elements below summarize as closely as possible the airport operator's recommendations in the noise compatibility program and are cross-referenced to the program. The statements contained within the summarized recommendations and before the indicated FAA approval, disapproval, or other determinations do not represent the opinions or decisions of the FAA.

The approvals which follow include actions which the Westover Metropolitan Development Corporation recommends be taken by FAA. It should be noted that these approvals indicate only that the actions would, if implemented, be consistent with the purposes of Part 150. These approvals do not constitute decisions to implement the actions. Later decisions concerning possible implementation of these actions may be subject to applicable environmental or other procedures or requirements.

2.0 PROGRAM ELEMENTS

2.1 Noise Abatement Elements

2.1.1. Extension of Existing Civil Aircraft Preferential Runway (Runway 5 for departures and Runway 23 for landings) when the tower begins operations on a full 24-hour schedule. Use from

11 pm to 7 am, until Forecasted 1998 operations of 3-4 nighttime turbojet (above 75,000 pounds) operations occur (sections 2.1.1 and 3.1.1) (identified as "Original 1998 Forecast" in Table 3.2). This measure is recommended in combination with the next noise abatement element.

Approved as voluntary. There are currently no civil operations between 11 pm and 7 am, since the airport is closed. The hours of operation of the ATCT and airport (7 am to 11 pm) are established by the Air Force Reserve. A noise abatement benefit of approximately 1.5 DNL would conservatively accrue to occur to up to 2400 people who reside in more densely populated areas to the south of the airport within the 65-75 DNL contour areas (Figure 3.1 and Tables 3.1 and 3.2). A reevaluation of this measure will be needed in order to compare continued preferential use with implementation of the related land use measure to acquire or soundproof residences.

2.1.2. Noise Abatement Departure Procedures for Military Aircraft on Runway 23 (sections 2.1.2 and 3.1.2). The Air Force operates mainly to the south due to placement of NAVAIDS. As part of noise mitigation for the flow of military operations for C-5s that remain in the local area, Air Force and Bradley Tower (the parent FAA air traffic control facility for Westover) would develop procedures for a right turn after take-off or missed approach to a heading of approximately 360 degrees at an altitude of 600 feet above ground level. Traffic permitting, Bradley would provide individual clearances through Westover Tower. After the initial right turn and upon positive radar contact, aircraft would be vectored by Bradley along a downwind leg and then cleared to turn inbound to intercept a final approach course of one of the instrument approaches used for training in the local area. For C-5s or other military aircraft departing the local area ATC would provide a clearance to turn after takeoff based on aircraft destination--either to a heading of 205 degrees (a 25 degree left turn) for aircraft departing towards the Hartford, Dream, Putnam, Norwich, Gardner, and Madison navigational fixes, or to an initial heading of 255 degrees (25 degree right turn) towards Keene, Pawling, Chester, and Barnes. As above, individual clearances would be through Westover Tower prior to take-off. Following positive radio and radar contact with Bradley, aircraft would be vectored on course. Noise abatement headings could be expected between 10 pm (2200) and 6 am (0600). During other hours, it is recommended that Westover Tower request a noise abatement heading, recognizing that each military jet aircraft cleared to turn will be left to the discretion of Bradley Approach Control.

Approved as voluntary. C-5 aircraft SEL contour analysis indicates that, given the Air Force Reserve right-hand local traffic pattern, noise exposure can be minimized with earlier turns (Figure 3.2). For traffic departing the local area, this analysis indicates that, given the need to avoid traffic conflicts within the Bradley Approach Control area and the need to vector aircraft somewhat in accordance with flight plan routes, earlier turns to the left or right can reduce population exposure (Figure 3.2).

2.1.3. Noise Abatement Departure Procedures for Civilian Aircraft on Runway 23. When civil aircraft operate to the south, the Air Force and Bradley Approach Control would develop IFR procedures that would permit civil aircraft to make early turns to 205 or 255 degrees after take-off from Runway 23. As in the previous noise abatement measure, assigned headings would be based on aircraft route of flight, issued to pilots by Westover Tower so that turns may be initiated prior to radar contact with Bradley, and expected between 10 pm (2200) and 6 am (0600). At other times Westover Tower would request the noise abatement headings for Stage 2 aircraft and it would be issued at Bradley's discretion, traffic permitting.

Approved as voluntary. This noise abatement element, in conjunction with the next noise abatement element, Noise Abatement Departure Procedures for Civilian Aircraft on Runway 5, would reduce noise exposure to approximately 200 people within the DNL 65-75 contour areas (Figure 3.3 and Table 3.3).

2.1.4. Noise Abatement Departure Procedures for Civilian Aircraft on Runway 5. This measure is proposed in conjunction with the voluntary acquisition and relocation program proposed below. It

would be applicable between 10 pm (2200) and 6 am (0600) and consists of a departure heading of 080 degrees, extended as practical to 205 or 255 degrees for traffic with clearance toward Hartford and Pawling, respectively. Traffic with clearance toward Chester would be given a subsequent left turn when at least 3 DME from the Westover VOR (in order to remain clear of the Acrebrook subdivision). Clearances would be issued by Westover Tower after agreement on departure clearance procedures with Bradley Approach Control. They would be issued by Westover Tower to pilots prior to take-off so that turns may be initiated as soon as possible , prior to radar contact with Bradley.

Approved as voluntary. As stated in the approval of the previous measure, this noise abatement element, in conjunction with Noise Abatement Departure Procedures for Civilian Aircraft on Runway 23, would reduce noise exposure to approximately 200 people within the 65-75 DNL contour areas (Figure 3.3 and Table 3.3).

2.2 Land Use Elements

2.2.1. Voluntary Land Acquisition and Relocation Program. For approximately 150 residences exposed to 70 DNL or above, the Westover Metropolitan Development Corporation (WMDC) proposes to implement a voluntary purchase and relocation program to eliminate or significantly reduce the number of people remaining in areas of high noise exposure after implementation of all other operational noise abatement elements. WMDC would consider including additional homes in the purchase program on a case-by-case basis. A noise easement would be secured on all acquired property.

Approved. It is not considered within the meaning of the Uniform Act, to be a “voluntary” transaction if the homeowners’ property is destroyed and converted to other compatible land uses. If the property’s use will be the same, it is considered a voluntary transaction under the Uniform Act, but the homeowner does not qualify for relocation payments. Only tenant occupants would be eligible for relocation payments.

2.2.2. Voluntary Sound Insulation Program. This measure would apply to approximately 900 residences within the 65 DNL contour, as well as those within the 70 DNL contour but not sold under the voluntary acquisition program. A noise easement would be acquired in exchange for sound insulation.

Approved.

2.2.3. Compatible Use Zoning. To minimize chances that new noncompatible land uses will be developed within the DNL 65 dB contour, it is proposed that each of the five communities of Chicopee, Granby, Ludlow, Springfield, and South Hadley consider adopting suitable zoning to limit residential use in high noise exposed areas. **Approved.** FAA strongly discourages new noncompatible development within the DNL 65 dB contour, and new development may not be eligible for future mitigation using Federal funding.

2.2.4. Airport Overlay District. WMDC would recommend that the communities of Chicopee and Granby adopt an airport overlay district which encompasses land within the 65 DNL contour. They would also recommend that the town of Ludlow change the boundaries of its airport overlay district to include all of the land within the forecasted 1998 contour.

Approved.

Subdivision Regulations. WMDC would recommend that the town of Granby amend its subdivision regulations to require noise easements on all newly created lots within the airport’s 65

DNL contour. WMDC would work with town officials in preparing amendments to the Bylaws of the Town of Granby, Volume IV, Chapter XXII.

Approved. FAA strongly discourages new noncompatible development within the DNL 65 dB contour, and new development may not be eligible for future mitigation using Federal funding.

2.3 Implementation, Monitoring, and Review Elements

2.3.1 Pilot Awareness Program. WMDC would publish a pamphlet of noise abatement practices to be distributed to civilian pilots through the Fixed Base Operator and WMDC's airport management. The pamphlet would include a map of noise sensitive areas around the airport and describe the operational measures which WMDC has adopted for noise abatement, including use of noise abatement departure procedures recommended by the National Business Aircraft Association or by individual aircraft manufacturers. WMDC would also install signs in all terminal areas frequented by civilian pilots and along ramp and taxiway areas controlled by WMDC, instructing pilots to follow noise abatement procedures.

Approved. The content and location of airfield signs are subject to specific approval by appropriate FAA officials outside of the Part 150 process and are not approved in advance by this action. Such signs must not be construed as mandatory air traffic procedures.

2.3.2 Public Awareness Program. To promote good public relations WMDC would issue from time to time public releases, which it would send to local papers, town libraries, and other public facilities, describing the latest developments in its noise compatibility program.

Approved.

2.3.3 Monitoring Nighttime Operations and Runway Use. WMDC would log nighttime activity between 10 pm (2200) and 7 am (0700). Logs would include time, type aircraft, registration/flight number, landing or take-off, runway used, and wind and weather conditions. The information would be used to determine compliance with WMDC's nighttime noise rule and to help provide guidance to Air Force contract tower personnel to determine compliance with the preferential runway use program.

Approved in part; disapproved in part, pending submission of additional information to make an informed analysis. This measure is approved for purposes of Part 150, except with respect to the information being used to determine compliance with the nighttime noise rule. The WMDC has not submitted for review under Part 150 either the current nighttime restriction or the proposed amendments to its nighttime noise rule (pages 13-15 and 39-42 of the NCP). There is insufficient information for the FAA to determine whether compliance with the noise rule would meet the approval standards contained in 14 CFR Part 150.

Airport noise and access restrictions proposed after October 1, 1990, must be adopted in compliance with the Airport Noise and Capacity Act of 1990 (recodified at P.L. 103-272), 49 USC 47521 (hereinafter referred to as "ANCA"), as implemented by 14 CFR Part 161.

2.3.4 Using a basic spreadsheet program, WMDC would compute estimates of changes in noise exposure related to changes in scheduled civil jet operations, changes in civil nighttime operations, or changes in total nighttime civil operations. WMDC would submit an Environmental Notification Form (ENF) to the Massachusetts Secretary of Environmental Affairs for any change in noise exposure greater than 1.5 dBA above the forecasted exposure included in the noise compatibility planning program and would initiate a review of its Noise Compatibility Program. Finally, if noise exposure reaches that forecasted in the noise exposure map, WMDC would initiate an update to the noise compatibility planning study in 1999 and 5-year intervals thereafter.

Each update would address fully the noise exposure and incompatible land use existing at the time.

Approved. A basic spreadsheet program may be used as a screening tool. A screening tool, such as the FAA's Area Equivalent Method, may be a useful indicator as to whether there has been a significant change in the noise environment warranting a revision to the NEM per section 150.21 of Part 150.

DRAFT



Federal Aviation Administration

Memorandum

Date: January 6, 2015

From: Richard Doucette, Manager, Environmental Programs, ANE-610 RTD



To: Mary Walsh, Manager, Airports Division, ANE-600
John Donnelly, Regional Counsel, ANE-7

Subject: Westover Metropolitan Airport, Part 150 Record of Approval

Attached is the Record of Approval for the Noise Compatibility Program developed by the Westover Metropolitan Development Corporation for the Westover Metropolitan Airport. One change to the existing Noise Compatibility Program measures is proposed. The Airport Sponsor proposes to expand the noise-land acquisition boundary from the 70DNL noise contour, out to the 65DNL noise contour. After discussion with APP-400, two other measures were disapproved, as they provide no measurable benefit inside the 65DNL noise contour

No written comments were received during the FAA comment period.

Upon your concurrence/approval below, the *Federal Register* Notice of FAA's approval of the Noise Compatibility Program can be submitted.

 _____ John Donnelly Regional Counsel, ANE-7	<u>2/6/2015</u> Date	<input checked="" type="checkbox"/> Concur	<input type="checkbox"/> Nonconcur
 _____ Mary Walsh Manager, Airports Division, ANE-600	<u>2/6/2015</u> Date	<input checked="" type="checkbox"/> Approved	<input type="checkbox"/> Disapproved

RECORD OF APPROVAL

Westover Metropolitan Airport
Chicopee and Ludlow, Massachusetts

FAR PART 150 NOISE COMPATIBILITY PROGRAM

1.0 Introduction

The Westover Metropolitan Airport sponsored an Airport Noise Compatibility Planning Study under a Federal Aviation Administration (FAA) grant, in compliance with Federal Aviation Regulation, Part 150. Westover Municipal Development Corporation produced a report entitled "*Westover Metropolitan Airport/Westover Air Reserve Base Noise Exposure Map and Noise Compatibility Program Update.*" The Noise Compatibility Program (NCP) and its associated Noise Exposure Maps (NEM) were developed concurrently and submitted to FAA for review and approval on September 25, 2014. The NEM was determined to be in compliance on September 25, 2014. This determination was announced in the Federal Register on October 10, 2014.

The study provides an overview of all the noise mitigation measure previously approved in the January 1, 1996 Record of Approval. This overview can be found in Chapter 5 of the NEM/NCP document. The one change proposed in the NCP Update is expanding the noise land acquisition boundary from the 70DNL noise contour out to the 65DNL noise contour. This measure is approved. All other previously approved (1996) measures were reviewed for their current status, and for consistency with Part 150. As part of this review, the FAA now disapproves two previously approved measures: the Runway 23 and Runway 05 noise abatement departure procedures for civilian aircraft. These measures do not currently provide benefits within the 65 DNL contour. Meaningful noise abatement procedures may be designed and recommended under a future NCP update.

2.0 Noise Abatement Measures

The 1996 NCP evaluated and recommended several noise abatement measures. These measures were modeled and compared to the noise exposure contours developed under that study, and those which provided a benefit (a reduction in the number of residences and estimated population within the 65 DNL noise contour) were included in the Airport's recommended plan submitted to the FAA. Each of the four approved measures included consultation with the Westover Tower and Bradley Approach Control, the air traffic facility whose jurisdiction surrounds that of the Westover Tower.

Measures were proposed for both civilian and military operations. The following sections describe each of the measures, the FAA's conclusions at the time (approval or disapproval), and evaluates the procedure in the current environment.

2.1 Nighttime Preferential Runway Use for Civilian Aircraft

Description: This measure calls for civilian aircraft to use Runway 05 for departures and Runway 23 for arrivals to the maximum extent practicable. This preferential runway use was first adopted by the WMDC Board of Directors in 1987. Thus, the recommended pattern of civilian operations would be departures to the north and arrivals from the north, taking advantage of the lower density of residential land uses in Granby and Ludlow. If nighttime operations increased to levels predicted at the time, the WMDC would reevaluate the measure to achieve a more balanced level of runway use.

This non-mandatory measure was recommended in part to assist noise abatement efforts once the Westover Tower remained open for 24 hours per day. At the time, civilian operations could not operate at the Airport when the Westover Tower was closed (11:00 p.m. to 7:00 a.m.) without prior arrangement. The 1996 NCP included the assumption that the Westover Tower would begin 24-hour operations, although this has not yet occurred. Implementing this measure was forecast to reduce the estimated population within the 65 DNL noise contour south of the Airport.

FAA Finding 1996: Approved this voluntary measure.

Current Status: Preferential runway use for civilian operations remains consistent, mostly due to the location of the general aviation facilities (FBO/terminal area). Approximately 80% of civilian operations occur to or from the north. The Westover Tower remains closed to civilian operations from 11:00 p.m. to 7:00 a.m., although the WMDC can request a waiver for the Westover Tower to open prior to 7:00 a.m. or remain open past 11:00 p.m. if needed.

2.2 Noise Abatement Departure Procedures for Military Aircraft on Runway 23

The 1996 NCP proposed that select military C-5 departures from Runway 23 follow a noise abatement procedure. Military operations primarily depart from Runway 23 (south). At the time of the study, C-5 Runway 23 departures were required to climb on runway heading (approximately 230 degrees) until radar contact is confirmed with Bradley Approach Control, located 20 miles south of Westover. Due to the distance between the radar and aircraft, this sometimes resulted in the overflight of heavily populated areas until radar contact was established and aircraft were instructed to turn towards their destination. The proposed flight paths included earlier left or right turns, coordinated with the Bradley Approach Control.

FAA Finding 1996: Approved as voluntary, as implementation was shown to reduce the estimated population within the 65 DNL noise contour.

Current Status: The military continues to use Runway 23 as the primary departure runway. Due to the change in the mission of C-5 aircraft, the types of operations flown have changed to meet wartime flying requirements. C-5 operations do use an early turn to the west to avoid overflight of more heavily populated areas.

2.3 Noise Abatement Departure Procedures for Civilian Aircraft on Runway 23

Description: This measure proposed that civilian aircraft, particularly larger and louder aircraft that depart from Runway 23, use a noise abatement heading of 205 or 255 degrees, rather than flying a runway heading (approximately 230 degrees).

FAA Finding 1996: Approved this voluntary measure. Implementation of this measure would have, at the time, assisted in reducing the number of residences within the 65 DNL noise contour.

Current Status: Many of the larger aircraft that operated at the Airport prior to 2000, such as 727's or 737-200's, were phased out of the fleet through the passage of the Airport Noise and Capacity Act of 1990 (Stage 2 aircraft weighing less than 75,000 pounds will be prohibited from operating in 2015). As a result, the overall fleet of passenger aircraft is quieter. Noise modeling input data, developed in consultation with the Westover Tower, indicates that a majority (approximately 72%) of civilian departures from Runway 23 depart on a course that follows the runway heading (approximately 230 degrees), while approximately 28% depart from the runway and turn towards a heading of approximately 270 degrees.

In consideration of the current and forecast levels of civilian air traffic, the current types of aircraft in use at the airport, and the predominant noise characteristics of the military fleet, it is not expected that use of the noise abatement procedure would reduce the noise-sensitive land uses within the 65 DNL.

FAA Finding 2015: Disapproved. This measure provides no measurable benefit within the 65 DNL contour at this time. Meaningful noise abatement procedures may be designed and recommended under a future NCP update, as the local conditions warrant.

2.4 Noise Abatement Departure Procedures for Civilian Aircraft on Runway 05

Description: The measure called for aircraft, upon departure from Runway 05 and once safely airborne, to turn to an ATC-assigned heading of 080 degrees, then follow instructions issued by Bradley Approach Control towards their respective navigation fix. This early turn of approximately 30 degrees would route departing aircraft further away from the Acrebrook subdivision, taking advantage of more compatible land uses. The measure was proposed to be applicable between the hours of 10:00 p.m. and 6:00 a.m. and was estimated to reduce potential noise impacts in the Acrebrook subdivision, which was also proposed for eligibility under the voluntary acquisition program. The measure was proposed contingent upon FAA approval of the voluntary acquisition program (discussed in Section 5.2.2) to reduce noise north of the Airport, specifically in the Acrebrook neighborhood.

FAA Finding 1996: Approved this voluntary measure. This measure would reduce the number of residences and estimated population within the 65 DNL noise contour.

Current Status: Generally, aircraft departures from Runway 05 fly a runway heading of approximately 50 degrees. In consideration of the current and forecast levels of civilian air traffic, the current types of aircraft in use at the airport, and the predominant noise characteristics of the military fleet, it is not expected that use of the noise abatement procedure would reduce the noise-sensitive land uses within the 65 DNL.

FAA Finding 2015: Disapproved. This measure provides no measurable benefit within the 65 DNL contour at this time. Meaningful noise abatement procedures may be designed and recommended under a future NCP update, as the local conditions warrant.

3.0 Land Use Measures

Land use measures seek to correct existing non-compatible land uses and to further inhibit the development of land uses that could be impacted by noise from aircraft operations. The WMDC does not control the land uses surrounding the Airport, but can make recommendations in consultation with local jurisdictions. The recommended land use measures include mitigation programs (voluntary acquisition and relocation, sound insulation) and preventive measures, which seek to limit the possibility of future non-compatible development.

3.1 Voluntary Land Acquisition and Relocation Program

Description: The intent of the voluntary purchase and relocation program is to eliminate or significantly reduce the number of people remaining in areas of high noise exposure. The 1996 NCP identified approximately 150 residences exposed to 70 DNL, which was updated under the 2004 NEM Update to include approximately 416 potentially eligible structures (single and multi-family structures) within the 70 DNL of the 2003 NEM. The WMDC received funding from the FAA to initiate the voluntary acquisition program in 2005.

FAA Finding 1996: Approved this voluntary measure.

Current Status: **Figure 5-1** presents a map depicting those properties which have been acquired as of December 2013. These 48 properties, accounting for approximately 203 acres, have been acquired, any homes have been demolished, and the land remains vacant (therefore compatible with aircraft operations).

Of the 48 total acquired properties, 39 properties are located in residential areas north of the airport; 23 properties in Granby and 16 properties in Ludlow, while the 9 remaining properties are located to the south of the Airport in Chicopee. For each acquired property, an aviation easement will be attached to the deed after parcel assembly is completed. Once acquired, the properties are maintained by the WMDC until a complete reuse and disposal plan is developed.

FAA Finding 2015: This NCP is proposing that residences exposed to noise levels 65 DNL and above be included in the voluntary acquisition program. The continuation of the program is discussed in Section 5.3. This is a change from the previously-approved noise land acquisition program in the 70 DNL contour, and is the one measure proposed for revision at this time.

Voluntary Acquisition of land is approved, except for those identified parcels now removed from the eligible noise contour. Due to changes in the aircraft fleet mix and level of operations, a number of parcels once eligible for noise mitigation are not eligible at this time. If the level of operations and fleet mix change over time, causing the noise contour to grow, the NEM should once again be updated. This could make more properties eligible for noise mitigation in the future. Noise land acquisition will be accomplished within the parameters of Part 150, the AIP Handbook, and the Uniform Relocation Act.

3.2 Voluntary Sound Insulation Program

Description: A sound insulation program is a voluntary program with the goal of providing acoustic treatment to eligible homes to reach a 5 dB improvement compared to existing indoor levels. The sound insulation program was initially identified to include those residences within the 65 DNL noise contour, in addition to residences located in the 70 DNL noise contour that declined participation in the voluntary acquisition program. In exchange for the installation of sound insulating materials, which typically include acoustically-rated windows and doors, and could include upgrades to mechanical systems, the property owner would be required to grant a noise easement.

FAA Finding 1996: Approved this voluntary measure.

Current Status: A sound insulation program has not been implemented. The WMDC began the voluntary acquisition program once funding became available for homes that experienced higher noise levels. This NCP is proposing that residences exposed to noise levels above 65 DNL within the Future (2019) NEM be included in the voluntary acquisition program. The WMDC prefers to complete the voluntary acquisition program prior to initiating a sound insulation program. Any initiation of a sound insulation program will be approved in advance by the FAA, to ensure conformance with Part 150.

3.3 Compatible Use Zoning

Description: Zoning for compatible land uses includes rezoning land that may be developed with noise-sensitive land uses, such as residences, places of worship, or schools. Rezoning would change the development potential of the land to a use that is more compatible with aircraft operations, such as industrial or open space. The 1996 NCP included specific recommendations for each city or town in order to minimize chances that new noncompatible land uses will be developed within the 65 DNL contour. The 1996 NCP suggested that

Chicopee, Granby and Ludlow maintain their existing zoning but consider adopting overlay zoning, and that Springfield and South Hadley maintain their existing industrial zoning classifications.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure.

Current Status: Based on zoning information provided by MassGIS, portions of the Future (2019) NEM 65 DNL contour include residential zoning in Granby, residential-agricultural zoning in Ludlow, and general industrial and residential zoning in Chicopee. The 65 DNL noise contour does not include land within South Hadley or Springfield, although aircraft do overfly these areas. The WMDC will continue to work with each jurisdiction to determine the feasibility of implementing this measure.

3.4 Airport Overlay District

Description: An overlay district is a zoning technique which identifies additional restrictions on development in addition to the underlying zoning, by modifying (but not eliminating) the underlying zoning. Overlay districts offer an option to provide a more flexible development control than that of changing the allowed uses in entire zoning districts and focusing on only the portion of the community with potential non-compatible land uses.

Since 1992, the Town of Ludlow has had an Aircraft Flight Overlay District intended to protect the public health, safety, and general welfare; and to protect human life and property from hazards of aircraft noise and accident potential created by the Town's proximity to Westover. By 1996, Ludlow had implemented the aircraft flight overlay district, encompassing the noise and accident potential zones from the AICUZ. At that time, hospitals, nursing homes, auditoriums and concert halls were prohibited within the overlay districts. Educational and religious institutions are permitted by right in all districts according to the Massachusetts Zoning Enabling Act, and the Town had sought and received home rule authority from the state legislature to allow restriction of development of schools, day care centers, and houses of worship within accident potential zones. The existing overlay district does not prohibit residential land uses or impose sound insulating requirements on residential lands.

The initial NCP recommended that Chicopee and Granby adopt an airport overlay district which encompasses land within the 65 DNL contour, and that the town of Ludlow change the boundaries of its airport overlay district to include all of the land within the forecasted 1998 contour.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure for the purposes of Part 150.

Current Status: No further changes to the Town of Ludlow's overlay district have been implemented, and no other jurisdictions have developed an overlay district to date. The 65 DNL noise contour of the Future (2019) NEM extends into Ludlow, Granby and Chicopee. The WMDC will continue to work with each jurisdiction to determine the feasibility of implementing this measure.

3.5 Subdivision Regulations

Description: Subdivision regulations describe the procedures and standards for the division of parcels of land, most notably for sale or development as smaller parcels. The use of subdivision regulations by a municipality prescribes certain conditions that must be met by a developer prior to receipt and recordation of a plat. Generally, amending subdivision regulations is most practical when large amounts of undeveloped land are present.

The 1996 NCP recommended that the Town of Granby, as the jurisdiction with the most notable assemblage of undeveloped land within the 65 DNL noise contour, amend their subdivision regulations to require noise easements to be obtained on newly created lots within the 65 DNL noise contour.

FAA Finding 1996: The FAA, although it has no jurisdiction in local land use affairs, approved this measure for the purposes of Part 150.

Current Status: The Town of Granby has not included the recommendations requiring noise easements into their subdivision regulations. The 65 DNL noise exposure contour of the Future (2019) NEM extends into Granby, in areas in which the WMDC is currently offering voluntary acquisition. The WMDC will continue to work with Granby to determine the feasibility of implementing this measure.

4.0 Implementation, Monitoring, and Review Measures

Implementation, monitoring, and review measures are those that can be undertaken by the WMDC to track the progress of the recommended noise compatibility program. They include measures that are designed to increase awareness of noise abatement and mitigation, and provisions for the continued monitoring of noise surrounding an Airport. The 1996 NCP identified four measures for inclusion in the program, as described in the following sections.

4.1 Pilot Awareness Program

Description: This measure identified that the WMDC would publish a pamphlet of noise abatement practices to be distributed to civilian pilots through the aviation services provider and WMDC's airport management. The pamphlet would include a map of noise sensitive areas around the airport and describe the operational measures which WMDC has adopted for noise abatement, including use of noise abatement departure procedures recommended by the National Business Aircraft Association or by individual aircraft manufacturers. The measure suggested that the WMDC would install signs in all terminal areas frequented by civilian pilots and along ramp and taxiway areas controlled by WMDC, instructing pilots to follow noise abatement procedures.

FAA Finding 1996: This measure was approved, with the caveat that the location and content of signs may be subject to FAA approval.

Current Status: The WMDC has installed signs in the terminal area pilot lounge and in areas leading to airside facilities directing pilots to be aware of noise-sensitive locations around the Airport. The WMDC is further evaluating the feasibility of installing more permanent signs encouraging the use of the noise abatement procedures for civilian aircraft from Runways 5 and 23.

4.2 Public Awareness Program

Description: This measure served to increase public awareness in the surrounding communities regarding the latest developments in the noise compatibility program.

FAA Finding 1996: Approved this voluntary measure.

Current Status: WMDC currently offers a voluntary acquisition and relocation program to property owners within the updated 2003 NEM. As part of that practice, the WMDC maintains contact with property owners within the 65 DNL noise contours.

4.3 Monitoring Nighttime Operations and Runway Use

Description: This measure was intended to assist in the identification and quantification of nighttime aircraft activity, specifically during the hours in which the Westover Tower was closed. Information to be collected included the time, type aircraft, registration/flight number, landing or take-off, runway used, and wind and weather conditions. The information would be used to determine compliance with WMDC's nighttime noise rule and to help provide guidance to Air Force contract tower personnel to determine compliance with the preferential runway use program.

FAA Finding 1996: The FAA approved in part and disapproved in part this measure. The FAA required the submittal of additional information regarding the noise rule, and stated that using the data to ensure compliance with any rules that would essentially limit aircraft operations would require an additional noise study.

Current Status: The Westover Tower tracks operations during hours the tower is open. Minimum operations occur during nighttime hours (10:00 p.m. to 7:00 a.m.). The additional information noted in the 1996 FAA Finding has not been submitted, and therefore the partial disapproval remains in effect.

4.4 Periodic Updates of Noise Exposure

Description: This measure recommended the ongoing monitoring of changes in noise exposure at the Airport, primarily by focusing on the changes that would likely have the greatest impact to cause an increase in cumulative noise exposure. The original measure identified, as primary potential drivers of noise exposure, any planned changes in scheduled jet operations by civilian aircraft, any planned changes in nighttime operations by civil aircraft, or annual changes in total civil operations.

FAA Finding 1996: Approved.

Current Status: As indicated in the introduction to the NCP in this chapter, the WMDC has completed or supported multiple evaluations of noise exposure as a result of changes in operations, including this update. WMDC will provide periodic NEM updates as required by law and regulation.

APPENDIX C

AEE Coordination

[This page is left intentionally blank]

DRAFT

MEMORANDUM



To
Richard Doucette
Environmental Program Manager
New England Region
Federal Aviation Administration
12 New England Executive Park
Burlington, MA 01803

From
Yue Xu, HNTB

Cc
Gordon Hutchinson, WMDC
Ervin Deck, Stantec
Randall Christensen, Stantec
Kim Hughes, HNTB

Subject
Request for Non-standard Substitution
Aircraft and Weather Parameters for
Westover Air Reserve/Metropolitan Airport
Noise Exposure Map Update and EA

Date
April 19, 2018

The Westover Metropolitan Development Corporation (WMDC) has initiated a Part 150 Update and an Environmental Assessment (EA) for Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF), with the assistance of Stantec Consulting Services and HNTB Corporation. The WMDC oversees civilian operations at CEF which is currently open 16 hours per day. The Airport is also home to the Massachusetts Air Force Reserve 439th Airlift Wing, which previously operated Lockheed C-5A Galaxy aircraft and has upgraded to the C-5M Super Galaxy. The Part 150 Update is being prepared to assess the impacts of the C-5M Super Galaxy fleet upgrade. The WMDC has proposed to extend CEF operating hours to 24 hours per day and the EA is being prepared to assess the potential environmental impacts of this proposed change in operating hours.

HNTB is preparing noise exposure contours representative of existing conditions in 2018 and forecast conditions in 2023 using the Aviation Environmental Design Tool (AEDT) 2d and NOISEMAP Version 7.363 for both the Part 150 Update and EA. Four aircraft identified in the existing and forecast fleet mixes do not have direct AEDT type or pre-approved AEDT substitutions, as shown in **Table 1**. This request is in accordance with the required protocol to obtain approval of non-standard aircraft substitution related to AEDT¹.

¹ *Guidance on Using the Aviation Environmental Design Tool (AEDT) to Conduct Environmental Modeling for FAA Actions Subject to NEPA*, FAA, October 27, 2017.

Table 1
Non-standard AEDT Aircraft Substitution for Westover Part 150/EA

Aircraft Code	Aircraft Description	AEDT Model / Substitution Model	Recommended EQUIP_ID	ANP_ID	BADA_ID
BE35	Beech Bonanza 35	Raytheon Beech Bonanza 36	1276	CNA208	TBM8
DA40	Diamond Star DA40	EADS Socata TB-10 Tobago	1904	GASEPV	TB21
F22	Boeing Raptor F22	Boeing F-15E Strike Eagle	4235	F15E29	FGTN
S22T	Cirrus SR-22 Turbo	Cirrus SR22	1325	COMSEP	SR22

Sources: Westover Air Traffic Control Tower and HNTB analysis, 2018.

BE35 – Beech Bonanza 35

The Beech Bonanza 35 is a single-engine general aviation aircraft powered by a Continental E-185-1 engine (185 hp) with an MTOW of 3,400 lbs. HNTB recommends using the Raytheon Beech Bonanza 36 (AEDT Equipment ID = 1276, ANP Code = CNA208, and BADA ID = TBM8) as a substitute. The Raytheon Beech Bonanza 36 is a single-engine aircraft powered by a Continental IO-550-B engine (300 hp) with an MTOW of 3,650 lbs.

DA40 - Diamond Star DA40

The Diamond Star DA40 is a low-wing, single-engine piston aircraft with an MTOW of 2,535 lbs. It is powered by a Lycoming IO-360-M1A engine producing 180 hp. The Diamond DA40 has a two or three-blade, constant speed variable pitch propeller. HNTB recommends using the EADS Socata TB-10 Tobago (AEDT Equipment ID = 1904, ANP Code = GASEPV, and BADA ID = TB21) as a substitute. The ADS Socata TB-10 Tobago has a MTOW of 2,530 lbs. and is powered by a Lycoming O-360-A1AD engine producing 180 hp. The ADS Socata TB-10 Tobago and Diamond Star DA40 have similar engines and MTOWs.

F22 – Boeing Raptor F22

The Boeing Raptor F22 is a twin-engine fighter aircraft powered by two Pratt & Whitney F119-PW-100 turbofans and has an MTOW of 83,500 lbs. HNTB recommends using the Boeing F-15E Strike Eagle (AEDT Equipment ID = 4235, ANP Code = F15E29, and BADA ID = FGTN) as a substitute. The Boeing F-15E Strike Eagle is a twin-engine fighter aircraft powered by two Pratt & Whitney F100-PW-229 turbofans and has an MTOW of 81,000 lbs. The Boeing Raptor F22 and Boeing F-15 Eagle have similar engines and MTOWs.

S22T - Cirrus SR22 Turbo

The Cirrus SR22 Turbo is a turbocharged version of the Cirrus SR-22. It has an MTOW of 3,600 lbs and is powered by a Tornado Alley turbonormalizing upgrade kit (310 hp) or a ground-boosted Continental TSIO-550K engine producing (315 hp). HNTB recommends using the Cirrus SR22 (AEDT Equipment ID = 1325, ANP Code = COMSEP, and BADA ID = SR22) as a substitute. Considering the relatively low altitude of Westover Airport (245ft), it is doubtful that the turbocharged version of the Cirrus SR22 produces considerably different noise signature than the standard version.

HNTB also proposes to apply the 30-year average temperature and pressure at CEF² as the AEDT default temperature and pressure are missing for CEF, as shown in **Table 2**. HNTB collected temperature and pressure data of the weather station 744910 – Westover AFB/Metropolitan Airport (between April 1989 and March 2018). The calculated average temperature and pressure, together with other AEDT default weather parameters, are recommended to be applied in the study.

Table 2
Temperature and Pressure

Parameter	AEDT Default	Recommended Value
Temperature	0	50.0 (°F)
Pressure	0	1,006.6 (millibars)

Sources: FAA AEDT 2d and NOAA, 2018.

We are requesting the approval or recommendation of five non-standard AEDT aircraft substitutions and 30-year average temperature and pressure for use in the Westover Part 150 and EA noise analysis. Should you have any additional questions, please do not hesitate to contact me. Thank you in advance for your consideration of this request.

Best regards,



Yue Xu, Ph.D., P.E.
Aviation/Environmental Planner
HNTB Corporation

² Global Summary of the Day, Climate Data Online, National Centers for Environmental Information, National Oceanic and Atmospheric Administration, <https://www.ncdc.noaa.gov/cdo-web/datasets>, accessed April 2018.



U.S. Department
of Transportation
**Federal Aviation
Administration**

Office of Environment and Energy

800 Independence Ave., S.W.
Washington, D.C. 20591

5/8/2018

Richard Doucette
Airports Division
Federal Aviation Administration,
New England Region
1200 District Avenue
Burlington, MA 01803

Dear Richard,

The Office of Environment and Energy (AEE) has received the memo dated April 19th 2018, referencing the 14 CFR Part 150 for Westover Air Reserve Base/Metropolitan Airport (WARB/CEF) for the user defined AEDT aircraft substitutions and user entered atmospheric conditions listed below:

Aircraft Code	Aircraft Description	AEDT Model / Substitution Model	Recommended EQUIP_ID	ANP_ID	BADA_ID	AEE Requirement
BE35	Beech Bonanza 35	Raytheon Beech Bonanza 36	1276	CNA208	TBM8	Concur
DA40	Diamond Star DA40	EADS Socata TB-10 Tobago	1904	GASEPV	TB21	Concur
F22	Boeing Raptor F22	Boeing F-15E Strike Eagle	4235	F15E29	FGTN	Model with DOD NoiseMap
S22T	Cirrus SR-22 Turbo	Cirrus SR22	1325	COMSEP	SR22	Concur

AEE grants approval for all of the recommended substitutions **except** for the Boeing Raptor F22. Due to the unique noise and performance characteristics of fifth generation, military fighter aircraft AEE is unable to approve AEDT substitution requests for these aircraft. Noise modeling for F22 operations should therefore be conducted using the DOD NoiseMap model. The NoiseMap noise results should then be combined with the civil aircraft AEDT noise results, using tools available in AEDT.

Parameter	AEDT Default	Recommended Value	AEE Recommendation
Temperature (°F)	NA	50.0	Concur
Pressure (millibars)	NA	1,006.6	Concur
Sea Level Pressure (millibars)	1016.52		Update with NOAA data
Relative humidity (%)	65.33		Update with NOAA data
Dew Point (°F)	38.74		Update with NOAA data
[Average] Wind Speed (knots)	6.62		Update with NOAA data

AEE concurs with the use of the NOAA Global Summary of the Day, Climate Data Online, National Centers for Environmental Information Data for use in providing updated atmospheric data. Due to the lack of available temperature and pressure information in the AEDT standard database, AEE recommends that to ensure data consistency that all of the required parameters be updated to use the same NOAA data source.

Please understand that this approval is limited to this particular 14 CFR Part 150 evaluation at Westover Air Reserve Base/Metropolitan Airport and that other non-standard AEDT inputs for additional projects at this or any other site will require separate approval.

Sincerely,



Rebecca Cointin
 Manager
 AEE-100/Noise Division

cc: Airports Contact (Jim Byers APP-400)

APPENDIX D

Noise and Its Effect on People

TABLE OF CONTENTS

	<u>Page</u>
D.1 Noise and its Metrics	1
D.1.1 The Decibel (dB)	1
D.1.2 A-Weighted Decibel (dBA).....	2
D.1.3 Maximum Sound Level (L_{max})	4
D.1.4 Sound Exposure Level (SEL)	7
D.1.5 Equivalent Sound Level (L_{eq})	8
D.1.6 Day-Night Average Sound Level (DNL).....	8
D.1.7 Time-Above a Specified Level (TA).....	10
D.2 The Effects of Aircraft Noise on People	10
D.2.1 Community Annoyance	10
D.2.2 Speech Interference	12
D.2.3 Sleep Disturbance	13

LIST OF FIGURES

	<u>Page</u>
Figure D-1 Frequency Response Characteristics of Various Weighting Networks.....	3
Figure D-2 Sound Levels of Typical Noise Sources (dBA)	5
Figure D-3 Variation of Community Noise in a Suburban Neighborhood	5
Figure D-4 Common Aircraft Departure Noise Levels.....	6
Figure D-5 Relationship Between Single Event Noise Metrics	7
Figure D-6 Typical Range of Outdoor Community Day Night Average Sound Levels.....	9
Figure D-7 Relationship Between Annoyance and Day Night Average Sound Level	11
Figure D-8 Percent Sentence Intelligibility	13
Figure D-9 Sleep Disturbance Dose Response Relationship	14

APPENDIX D

Noise and Its Effect on People

Aircraft noise exposure in this document is primarily addressed using the Day-Night Average Sound Level (DNL) metric. This study also involves the use of supplemental noise metrics in addition to DNL to provide comprehensive analysis for quantifying a specific situation. To assist reviewers in interpreting complex noise metrics, this appendix presents an introduction to the relevant fundamentals of acoustics and noise terminology, and the effects of noise on human activity.

D.1 Noise and its Metrics

Noise, often defined as unwanted sound, is one of the most common environmental issues associated with aircraft operations. Of course, aircraft are not the only sources of noise in an urban or suburban surrounding, where interstate and local roadway traffic, rail, industrial and neighborhood sources may also intrude on the everyday quality of life. Nevertheless, aircraft are readily identifiable to those affected by their noise and are typically singled out for criticism. Consequently, aircraft noise problems often dominate analyses of environmental impacts.

A “metric” is defined as something “of, involving, or used in measurement.” As used in environmental noise analyses, a metric refers to the unit or quantity that quantitatively measures the effect of noise on the environment. Noise studies have typically involved a confusing proliferation of noise metrics used by individual researchers who have attempted to understand and represent the effects of

noise. As a result, literature describing environmental noise or environmental noise abatement has included many different metrics.

Various federal agencies involved in environmental noise mitigation have agreed on common metrics for environmental impact analysis documents. Furthermore, the Federal Aviation Administration (FAA) has specified which metrics, such as DNL, should be used for federal aviation noise assessments.

This section discusses the following acoustic terms and metrics:

- Decibel (dB)
- A-Weighted Decibel (dBA)
- Maximum Sound Level (L_{max})
- Sound Exposure Level (SEL)
- Equivalent Sound Level (L_{eq})
- Day-Night Average Sound Level (DNL)
- Time-Above a Specified Level (TA)

D.1.1 The Decibel (dB)

All sounds come from a sound source—a musical instrument, a speaking voice, or an airplane passing overhead. It takes energy to produce sound. The sound energy produced by any sound source is transmitted through the air in sound waves—tiny, quick oscillations of pressure just above and just below atmospheric

pressure. These oscillations, or sound pressures, impinge on the ear creating the sound we hear.

Our ears are sensitive to a wide range of sound pressures. The loudest sound that we hear without pain has about one trillion times more energy than the quietest sounds we hear. On a linear scale, this range is unwieldy. Therefore we compress the total range of sound pressures to a more meaningful range by introducing the concept of sound pressure level (SPL) and its logarithmic unit of decibel (dB).

SPL is a measure of the sound pressure of a given noise source relative to a standard reference value (typically the quietest sound that a young person with good hearing can detect). Decibels are logarithmic quantities—logarithms of the ratio of the two pressures, the numerator being the pressure of the sound source of interest, and the denominator being the reference pressure (the quietest sound we can hear).

The logarithmic conversion of sound pressure to SPL means that the quietest sound we can hear (the reference pressure) has a SPL of about zero decibels, while the loudest sounds we hear without pain have SPLs less than or equal to about 120 dB. Most sounds in our day-to-day environment have SPLs from 30 to 100 dB.

Because decibels are logarithmic quantities, they require logarithmic math and not simple (linear) addition and subtraction. For example, if two sound sources each produce 100 dB and are operated together, they produce only 103 dB—not 200 dB as might be expected. Four equal sources operating simultaneously result in a total SPL of 106 dB. In fact, for every doubling of the number of equal sources, the SPL (of all of the sources combined) increases another three decibels. A ten-fold increase in the

number of sources makes the SPL increase by 10 dB. A hundredfold increase makes the level increase by 20 dB, and it takes a thousand equal sources to increase the level by 30 dB.

If one source is much louder than another, the two sources together will produce the same SPL (and sound to our ears) as if the louder source were operating alone. For example, a 100 dB source plus an 80 dB source produce 100 dB when operating together. The louder source “masks” the quieter one. But if the quieter source gets louder, it will have an increasing effect on the total SPL. When the two sources are equal, as described above, they produce a level 3 decibels above the sound level of either one by itself.

From these basic concepts, note that one hundred 80 dB sources will produce a combined level of 100 dB; if a single 100 dB source is added, the group will produce a total SPL of 103 dB. Clearly, the loudest source has the greatest effect on the total.

There are two useful rules of thumb to remember when comparing SPLs: (1) most of us perceive a 6 to 10 dB increase in the SPL to be an approximate doubling of loudness, and (2) changes in SPL of less than about 3 dB are not readily detectable outside of a laboratory environment.

D.1.2 A-Weighted Decibel (dBA)


Another important characteristic of sound is its frequency, or “pitch.” This is the rate of repetition of the sound pressure oscillations as they reach our ear. Frequency can be expressed in units of cycles per second (cps) or Hertz (Hz). Although cps and Hz are equivalent, Hz is the preferred scientific unit and terminology.

A very good ear can hear sounds with frequencies from 16 Hz to 20,000 Hz. However, most people hear from approximately 20 Hz to approximately 10,000-15,000 Hz. People respond to sound most readily when the predominant frequency is in the range of normal conversation, around 1,000 to 4,000 Hz. Acousticians have developed and applied “filters” or “weightings” to SPLs to match our ears’ sensitivity to the pitch of sounds and to help us judge the relative loudness of sounds made up of different frequencies. Two such filters, “A” and “C,” are most applicable to environmental noises.

A-weighting significantly de-emphasizes noise at low and high frequencies (below approximately 500 Hz and above approximately 10,000 Hz) where we do not hear as well. The filter has little or no effect at intervening frequencies where our hearing is most efficient. **Figure D-1** shows a graph of the A-weighting as a function of frequency and its aforementioned characteristics. Because this filter generally matches our ears’ sensitivity, sounds having higher A-weighted sound levels are usually judged to be louder than those with lower A-weighted sound levels, a relationship which does not always hold true for unweighted levels. Therefore, A-weighted sound levels are normally used to evaluate environmental noise. SPLs measured through this filter are referred to as A-weighted decibels (dBA).

Figure D-1

Frequency Response Characteristics of Various Weighting Networks



Source: ANSI S1.4-1983 “Specification of Sound Level Meters.”

As shown in Figure D-1, C-weighting is nearly flat throughout the audible frequency range, hardly de-emphasizing the low frequency noise. C-weighted levels are not used as frequently as A-weighted levels, but they may be preferable in evaluating sounds whose low-frequency components are responsible for secondary effects such as the shaking of a building, window rattle, perceptible vibrations or other factors that can cause annoyance and complaints. Uses include the evaluation of blasting noise, artillery fire, sonic boom, and in some cases, aircraft noise inside buildings. SPLs measured through this filter are referred to as C-weighted decibels (dBC).

Other weighting networks have been developed to correspond to the sensitivity and perception of other types of sounds, such as the “B” and “D” filters. However, A-weighting has been adopted as the basic measure of community environmental noise by the U.S. Environmental Protection Agency (EPA) and nearly every other agency concerned with aircraft noise throughout the United States.

Figure D-2 presents typical A-weighted sound levels of several common environmental sources. Sound levels measured (or computed) using A-weighting are most properly called “A-weighted sound levels” while sound levels measured without any frequency weighting are most properly called “sound levels.” However, since this document deals only with A-weighted sound levels, the adjective “A-weighted” will be hereafter omitted, with A-weighted sound levels referred to simply as sound levels. As long as the use of A-weighting is understood, there is no difference implied by the terms “sound level” and “A-weighted sound level” or by the dB or dBA units.

An additional dimension to environmental noise is that sound levels vary with time and typically have a limited duration, as shown in **Figure D-3**. For example, the sound level increases as an aircraft approaches, then falls and blends into the background as the aircraft recedes into the distance (although even the background varies as birds chirp, the wind blows or a vehicle passes by). Sounds can be classified by their duration as continuous like a waterfall, impulsive like a firecracker or sonic boom or intermittent like an aircraft overflight or vehicle passby.

D.1.3 Maximum Sound Level (L_{max})

The variation in sound level over time often makes it convenient to describe a particular noise “event” by its maximum sound level, abbreviated as L_{max} . For the aircraft overflight event in Figure D-3, the L_{max} is approximately 67 dBA.

Figure D-4 shows L_{max} values for a variety of common aircraft from the FAA’s Integrated Noise Model (INM) database. These L_{max} values for each aircraft type are for aircraft performing a maximum stage (trip) length departure on a day with standard atmospheric conditions at a reference distance of 3.5 nautical miles (NM) from their brake release point. Of the dozen aircraft types listed on the figure, the Concorde has the highest L_{max} and the Saab 340 (SF340) has the lowest L_{max} .

The maximum level describes only one dimension of an event; it provides no information on the cumulative noise exposure generated by a sound source. In fact, two events with identical maxima may produce very different total exposures. One may be of short duration, while the other may continue for an extended period. The metric, discussed later in this appendix, corrects for this deficiency.

Figure D-2

Sound Levels of Typical Noise Sources (dBA)





Figure D-3


Variation of Community Noise in a Suburban Neighborhood



Source: "Community Noise," NTID 300.3 EPA, December 1971.

Figure D-4

Common Aircraft Departure Noise Levels



D.1.4 Sound Exposure Level (SEL)


A frequently used metric of noise exposure for a single aircraft flyover is the Sound Exposure Level, or SEL. SEL may be considered an accumulation of the sound energy over the duration of an event. The shaded area in **Figure D-5** illustrates that portion of the sound energy (or “dose”) included in an SEL computation. The dose is then normalized (standardized) to a duration of one second. This “revised” dose is the SEL, shown as the shaded rectangular area in Figure D-5. Mathematically, the SEL represents the sound level of the constant sound that would, in one second, generate the same acoustic energy as the actual time-varying noise event. For events that last more than one second, SEL does not directly represent the sound level heard at any given time, but rather provides a measure of the net impact of the entire acoustic event.

Note that, because the SEL is normalized to one second, it will always be larger in magnitude than the maximum A-weighted level for an event that lasts longer than one second. In fact, for most aircraft overflights, the SEL is on the order of 7 to 12 dBA higher than the L_{max} . The fact that it is a cumulative measure means that not only do louder flyovers have higher SELs than quieter ones (of the same duration), but longer flyovers also have greater SELs than shorter ones (of the same L_{max}).

It is the SEL’s inclusion of both the intensity and duration of a sound source that makes SEL the metric of choice for comparing the single-event levels of varying duration and maximum sound level. This metric provides a comprehensive basis for modeling a noise event in determining overall noise exposure.

Figure D-5

Relationship Between Single Event Noise Metrics



D.1.5 Equivalent Sound Level (L_{eq})

Maximum A-weighted level and SEL are used to measure the noise associated with individual events. The following metrics apply to longer-term cumulative noise exposure that often includes many events.

The first cumulative noise metric, the Equivalent Sound Level (abbreviated L_{eq}), is a measure of the exposure resulting from the accumulation of A-weighted sound levels over a particular period of interest (e.g., an hour, an 8-hour school day, nighttime or a full 24-hour day). However, because the length of the period can be different depending on the time frame of interest, the applicable period should always be identified or clearly understood when discussing the metric. Such durations are often identified through a subscript, for example $L_{eq(8)}$ or $L_{eq(24)}$.

As for its application to aircraft noise issues, L_{eq} is often presented for consecutive 1-hour periods to illustrate how the hourly noise dose rises and falls throughout a 24-hour period, as well as how certain hours are significantly affected by a few loud aircraft. Since the period of interest for this study is in a full 24-hour day, $L_{eq(24)}$ is the proper nomenclature.

Conceptually, L_{eq} may be thought of as a constant sound level over the period of interest that contains as much sound energy as the actual time-varying sound level with its normal “peaks” and “valleys,” as illustrated in Figure D-3. In the context of noise from typical aircraft flight events and as noted earlier for SEL, L_{eq} does not represent the sound level heard at any particular time, but rather represents the total sound exposure for the period of interest. Also, it should be noted that the “average” sound level suggested by L_{eq} is

not an arithmetic value, but a logarithmic, or “energy-averaged,” sound level. Thus, loud events tend to dominate the noise environment described by the L_{eq} metric.

D.1.6 Day-Night Average Sound Level (DNL)

DNL is the same as L_{eq} (an energy-average noise level over a 24-hour period) except that 10 dB is added to those noise events occurring at night (between 10 p.m. and 7 a.m.). This weighting reflects the added intrusiveness of nighttime noise events attributable to the fact that community background noise levels typically decrease by about 10 dB during those nighttime hours. DNL does not represent the sound level heard at any particular time, but rather represents the total (and partially weighted) sound exposure.

Typical DNL values for a variety of noise environments are shown in **Figure D-6** to indicate the range of noise exposure levels usually encountered.


Due to the DNL metric’s excellent correlation with the degree of community annoyance from aircraft noise, DNL has been formally adopted by most federal agencies for measuring and evaluating aircraft noise for land use planning and noise impact assessment. Federal interagency committees such as the Federal Interagency Committee on Urban Noise (FICUN) and the Federal Interagency Committee on Noise (FICON) which include the EPA, FAA, Department of Defense, Department of Housing and Urban Development (HUD), and Veterans Administration, found DNL to be the best metric for land use planning. They also found no new cumulative sound descriptors or metrics of sufficient scientific standing to substitute for DNL. Other cumulative

metrics could be used only to supplement, not replace DNL. Furthermore, FAA Order 1050.1E for environmental documents requires that DNL be used in describing cumulative noise exposure and in identifying aircraft noise/land use compatibility issues.^{1 2 3 4 5}

Measurements of DNL are practical only for obtaining values for a relatively limited number of points. Instead, many noise studies, including this document, are based on estimates of DNL using an FAA-approved computer-based noise model.

Figure D-6

Typical Range of Outdoor Community Day-Night Average Sound Levels



Source: U.S. Department of Defense, Departments of the Air Force, the Army, and the Navy, 1978. *Planning in the Noise Environment*. AFM 19-10, TM 5-803-2, and NAVFAC P-970. Washington, D.C.: U.S. DoD.

D.1.7 Time-Above a Specified Level (TA)

The Time-Above a Specified Level (TA) metric describes the total number of minutes that instantaneous sound levels (usually from aircraft) are above a given threshold. For example, if 65 dB is the specified threshold, the metric would be referred to as “TA65.” Like DNL, the TA metric is typically associated with a 24-hour annual average day or only for the DNL nighttime period of 10 p.m. to 7 a.m.

When the TA calculation is expressed as a percentage of the day it is referred to as “%TA.” Although the threshold chosen for the TA calculation is arbitrary, it is usually the ambient level for the location of interest or 65 dB for comparison to a level of 65 dB DNL.

D.2 The Effects of Aircraft Noise on People

To many people, aircraft noise can be an annoyance and a nuisance. It can interfere with conversation and listening to television, disrupt classroom activities in schools and disrupt sleep. Relating these effects to specific noise metrics aids in the understanding of how and why people react to their environment. This section addresses three ways we are potentially affected by aircraft noise: annoyance, interference of speech and disturbance of sleep.

D.2.1 Community Annoyance

The primary potential effect of aircraft noise on exposed communities is one of annoyance. The U.S. EPA defines noise annoyance as any negative subjective reaction on the part of an individual or group.¹

Scientific studies^{1 2 3 6 7} and a large number of social/attitudinal surveys^{8 9} have been conducted to appraise the U.S. and international community of annoyance due to all types of environmental noise, especially aircraft events. These studies and surveys have found the DNL to be the best measure of that annoyance.

This relation between community annoyance and time-average sound level has been confirmed, even for infrequent aircraft noise events.¹⁰ For helicopter overflights occurring at a rate of 1 to 52 per day, the stated reactions of community individuals correlated with the daily time-average sound levels of the helicopter overflights.

The relationship between annoyance and DNL that has been determined by the scientific community and endorsed by many federal agencies, including the FAA, is shown in **Figure D-7**. Two lines in Figure D-7 represent two large sets of social/attitudinal surveys: one for a curve fit of 161 data points compiled by an individual researcher, Ted Schultz, in 1978⁸ and one for a curve fit of 400 data points (which include Schultz’s 161 points) compiled in 1992 by the U.S. Air Force.¹¹ The agreement of these two curves simply means that when one combines the more recent studies with the early landmark surveys in 1978, the results of the early surveys (i.e., the quantified effect of noise on annoyance) are confirmed.

Figure D-7 shows the percentage of people “highly annoyed” by a given DNL. For example, the two curves in the figure yield a value of about 13% for the percentage of people that would be highly annoyed by a DNL exposure of 65 dB. The figure also shows that at very low values of DNL, such as 45 dB or less, 1% or less of the exposed


population would be highly annoyed. Furthermore, at very high values of DNL, such as 90 dB, more than 80% of the exposed population would be highly annoyed.

Recently, the use of DNL has been criticized as not accurately representing community annoyance and land-use compatibility with aircraft noise. One frequent criticism is based on the inherent feeling that people react more to single

noise events and not as much to “meaningless” time-average sound levels. In fact, a time-average noise metric, such as DNL, takes into account both the noise levels of all individual events which occur during a 24-hour period and the number of times those events occur. As described briefly above, the logarithmic nature of the decibel unit causes the noise levels of the loudest events to control the 24-hour average.

Figure D-7

Relationship Between Annoyance and Day-Night Average Sound Level



Source: Federal Interagency Committee on Noise (FICON), "Federal Agency Review of Selected Airport Noise Analysis Issues", August 1992, p. 3-6, Figure 3.1

As a simple example of this characteristic, consider a case in which only one aircraft overflight occurs in daytime hours during a 24-hour period, creating a sound level of 100 dB for 30 seconds. During the remaining 23 hours 59 minutes and 30 seconds of the day, the ambient sound level is 50 dB. The DNL for this 24-hour period is 65.5 dB. As a second example, assume that 10 such 30-second overflights occur in daytime hours during the next 24-hour period, with the same ambient sound level of 50 dB during the remaining 23 hours and 55 minutes of the day. The DNL for this 24-hour period is 75.4 dB. Clearly, the averaging of noise over a 24-hour period does not ignore the louder single events and tends to emphasize both the sound levels and number of those events. This is the basic concept of a time-average sound metric, and, specifically, the DNL.

It is often suggested that a lower DNL, such as 60 or 55 dB, be adopted as the threshold of community noise annoyance for FAA environmental analysis documents. While there is no technical reason why a lower level cannot be measured or calculated for comparison purposes, a DNL of 65 dB:

- Provides a valid basis for comparing and assessing community noise effects.
- Represents a noise exposure level that is normally dominated by aircraft noise and not other community or nearby highway noise sources.
- Reflects the FAA's threshold for grant-in-aid funding of airport noise mitigation projects.
- HUD also established a DNL standard of 65 dB for eligibility for federally guaranteed home loans.

D.2.2 Speech Interference


A primary effect of aircraft noise is its tendency to drown out or “mask” speech, making it difficult to carry on a normal conversation.

Speech interference associated with aircraft noise is a primary cause of annoyance to individuals on the ground. The disruption of routine activities, such as radio or television listening, telephone use or family conversation, causes frustration and aggravation. Research has shown that “whenever intrusive noise exceeds approximately 60 dB indoors, there will be interference with speech communication.”¹

Indoor speech interference can be expressed as a percentage of sentence intelligibility among two people speaking in relaxed conversation approximately one meter apart in a typical living room or bedroom.¹ The percentage of sentence intelligibility is a non-linear function of the (steady) indoor background sound level, as shown in **Figure D-8**. This curve was digitized and curve-fitted for the purposes of this document. Such a curve-fit yields 100 percent sentence intelligibility for background levels below 57 dB and yields less than 10 percent intelligibility for background levels above 73 dB. Note that the function is especially sensitive to changes in sound level between 65 dB and 75 dB. As an example of the sensitivity, a 1 dB increase in background sound level from 70 dB to 71 dB yields a 14 percent decrease in sentence intelligibility.

In the same document from which Figure D-8 was taken, the EPA established an indoor criterion of 45 dB DNL as requisite to protect against speech interference indoors.

Figure D-8



Source: EPA 1974

D.2.3 Sleep Disturbance

Sleep disturbance is another source of annoyance associated with aircraft noise. This is especially true because of the intermittent nature and content of aircraft noise, which is more disturbing than continuous noise of equal energy and neutral meaning.


Sleep disturbance can be measured in one of two ways: "Arousal" represents awakening from sleep, while a change in "sleep stage" represents a shift from one of four sleep stages to another stage of lighter sleep without awakening. In general, arousal requires a higher noise level than does a change in sleep stage.

In terms of average daily noise levels, some guidance is available to judge sleep disturbance. The EPA identified an indoor DNL of 45 dB as necessary to protect against sleep interference.¹

In June 1997, the Federal Interagency Committee on Aviation Noise (FICAN) reviewed the sleep disturbance issue and presented a sleep disturbance dose-response prediction curve.¹² FICAN based their curve on data from field studies^{13 14 15} and recommends the curve as the tool for analysis of potential sleep disturbance for residential areas. **Figure D-9** shows this curve which, for an indoor SEL of 60 dB, predicts that a maximum of approximately 5 percent of the residential population exposed are expected to be behaviorally awakened. FICAN cautions that this curve should only be applied to long-term adult residents.

Figure D-9

Sleep Disturbance Dose-Response Relationship



Source: FICAN, 1997

DRAFT

Endnotes

- ¹ U.S. Environmental Protection Agency, "Information on Levels of Environmental Noise Requisite to Protect the Public Health and Welfare with an Adequate Margin of Safety," Report 550/9-74-004, March 1974.
- ² "Guidelines for Considering Noise in Land Use Planning and Control," Federal Interagency Committee on Urban Noise (FICUN), June 1980.
- ³ "Federal Agency Review of Selected Airport Noise Analysis Issues," Federal Interagency Committee on Noise (FICON), August 1992.
- ⁴ 14 CFR Part 150, Airport Noise Compatibility Planning, Amendment 150-3, Updated April 2012.
- ⁵ FAA Order 1050.1E, Chg 1, Environmental Impacts: Policies and Procedures, Department of Transportation, Federal Aviation Administration, March 20, 2006.
- ⁶ "Sound Level Descriptors for Determination of Compatible Land Use," American National Standards Institute Standard ANSI S3.23-1980.
- ⁷ "Quantities and Procedures for Description and Measurement of Environmental Sound, Part I," American National Standards Institute Standard ANSI S21.9-1988.
- ⁸ Schultz, T.J., "Synthesis of Social Surveys on Noise Annoyance," *J. Acoust. Soc. Am.*, 64, 377-405, August 1978.
- ⁹ Fidell, S., Barger, D.S., Schultz, T.J., "Updating a Dosage-Effect Relationship for the Prevalence of Annoyance Due to General Transportation Noise." *J. Acoust. Soc. Am.*, 89, 221-233, January 1991.
- ¹⁰ "Community Reactions to Helicopter Noise: Results from an Experimental Study," *J. Acoust. Soc. Am.*, 479-492, August 1987.
- ¹¹ Finegold, L.S., C.S. Harris, H.E. VonGierke., "Applied Acoustical Report: Criteria for Assessment of Noise Impacts on People." *J. Acoust. Soc. Am.*, June 1992.
- ¹² Federal Interagency Committee on Aviation Noise (FICAN), "Effects of Aviation Noise on Awakenings from Sleep," June 1997.
- ¹³ Pearson, K.S., Barber, D.S., Tabachnick, B.G., "Analyses of the Predictability of Noise-Induced Sleep Disturbance," USAF Report HSD-TR-89-029, October 1989.
- ¹⁴ Ollerhead, J.B., Jones, C.J., Cadous, R.E., Woodley, A., Atkinson, B.J., Horne, J.A., Pankhurst, F., Reyner, L, Hume, K.I., Van, F., Watson, A., Diamond, I.D., Egger, P., Holmes, D., McKean, J., "Report of a Field Study of Aircraft Noise and Sleep Disturbance." London Department of Safety, Environment, and Engineering, 1992.
- ¹⁵ Fidell, S., Pearsons, K., Howe, R., Tabachnick, B., Silvati, L., Barber, D.S. "Noise-Induced Sleep Disturbance in Residential Settings," AL/OH-TR-1994-0131, Wright Patterson AFB, OH, Armstrong Laboratory, Occupational and Environmental Health Division, 1994.
- ¹⁶ Fidell, S., Howe, R., Tabachnick, B., Pearsons, K., Sneddon, M., "Noise-Induced Sleep Disturbance in Residences Near Two Civil Airports," Langley Research Center, 1995.

APPENDIX E

Record of Consultation

[This page is left intentionally blank]

DRAFT

APPENDIX E

Record of Consultation

This appendix includes the following attachments:

1. Land Use Verification Letters to City of Chicopee, Town of Granby, and Town of Ludlow (May 3, 2018)
2. Land Use Verification Response from Town of Ludlow (May 7, 2018)
3. Public Notice of Draft Document Availability and Public Meeting Documents (*to be provided*)

DRAFT

[This page is left intentionally blank]

DRAFT

Attachment 1:
Land Use Verification Letters
to City of Chicopee, Town of Granby, and Town of Ludlow
May 3, 2018

Lee M. Pouliot, ASLA
Director, Planning Department
City of Chicopee
274 Front Street
4th Floor Annex
Chicopee, MA 01013



May 3, 2018

Dear Mr. Pouliot,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Planning Department at the City of Chicopee review the attached land use map to confirm the land use information is accurate and satisfactory to the City's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the City submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you

agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy Street, Suite 600, Arlington, VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT

On behalf of the City of Chicopee Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Lee M. Pouliot, ASLA (or designee)
Planning Department
City of Chicopee

Date

DRAFT

Cathy Leonard
Town Administrator's Assistant / Planning Board Contact
Town Hall/ Senior Center Building
10-B West State Street
2nd Floor
Granby, MA 01033



May 3, 2018

Dear Ms. Leonard,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Town of Granby review the attached land use map to confirm the land use information is accurate and satisfactory to the Town's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the Town submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy Street, Suite 600, Arlington,

VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT

On behalf of the Town of Granby Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Cathy Leonard (or designee)
Town of Granby

Date

DRAFT

Douglas J. Stefancik
Town Planner
Town of Ludlow
488 Chapin Street
Ludlow, MA 01056



May 3, 2018

Dear Mr. Stefancik,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Planning Department at the Town of Ludlow review the attached land use map to confirm the land use information is accurate and satisfactory to the Town's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the Town submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy

Street, Suite 600, Arlington, VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT


On behalf of the Town of Ludlow Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Douglas J. Stefancik (or designee)
Planning Department
Town of Ludlow

Date

DRAFT

Westover Air Reserve Base / Metropolitan Airport
 DRAFT Generalized Existing Land Use



LEGEND

- | | | |
|---|--|--|
| ■ Commercial/Industrial | ■ Transportation | ■ Local Historic District |
| ■ Open/Agricultural/Recreational | ■ Water | ⛪ Place of Worship |
| ■ Public/Quasi-Public | ■ WARB Installation Area | 🎓 School |
| ■ Residential | ■ WMDC Aviation Property | |
| ■ Previously Acquired Property under the Voluntary Acquisition Program | ■ County Boundary | |
| ■ Cemetery | ■ Town Boundary | |
| ■ Institutional | ○ National Register of Historic Places | |
| | ■ National Register Historic District | |




Figure 1

Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

[This page is left intentionally blank]

DRAFT

Attachment 2:
Land Use Verification
Response from Town of Ludlow
May 7, 2018

On behalf of the Town of Ludlow Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Douglas J. Stefancik *
Douglas J. Stefancik (or designee)
Planning Department
Town of Ludlow

May 7, 2018
Date

* Note #1 Marianna Lane is all Residential.
Note #2 483-485 Wolvok St is Commercial/Industrial.

DRAFT

Attachment 3:
Public Notice of Draft Document Availability
and Public Meeting Documents
(to be provided)

[This page is left intentionally blank]

DRAFT

APPENDIX E

Record of Consultation

[This page is left intentionally blank]

DRAFT

APPENDIX E

Record of Consultation

This appendix includes the following attachments:

1. Land Use Verification Letters to City of Chicopee, Town of Granby, and Town of Ludlow (May 3, 2018)
2. Land Use Verification Responses
3. Public Notice of Draft Document Availability and Public Meeting Documents (*to be provided*)

DRAFT

[This page is left intentionally blank]

DRAFT

Attachment 1:
Land Use Verification Letters
to City of Chicopee, Town of Granby, and Town of Ludlow
May 3, 2018

Lee M. Pouliot, ASLA
Director, Planning Department
City of Chicopee
274 Front Street
4th Floor Annex
Chicopee, MA 01013



May 3, 2018

Dear Mr. Pouliot,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Planning Department at the City of Chicopee review the attached land use map to confirm the land use information is accurate and satisfactory to the City's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the City submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you

agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy Street, Suite 600, Arlington, VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT

On behalf of the City of Chicopee Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Lee M. Pouliot, ASLA (or designee)
Planning Department
City of Chicopee

Date

DRAFT

Cathy Leonard
Town Administrator's Assistant / Planning Board Contact
Town Hall/ Senior Center Building
10-B West State Street
2nd Floor
Granby, MA 01033



May 3, 2018

Dear Ms. Leonard,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Town of Granby review the attached land use map to confirm the land use information is accurate and satisfactory to the Town's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the Town submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy Street, Suite 600, Arlington,

VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT

On behalf of the Town of Granby Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Cathy Leonard (or designee)
Town of Granby

Date

DRAFT

Douglas J. Stefancik
Town Planner
Town of Ludlow
488 Chapin Street
Ludlow, MA 01056



May 3, 2018

Dear Mr. Stefancik,

The Westover Metropolitan Development Corporation (WMDC) is conducting an update to the Title 14 Code of Federal Regulations (CFR) Part 150 Noise Compatibility Study (Part 150 Study) at Westover Air Reserve Base/ Metropolitan Airport (CEF). The Airport is operated under a joint-use agreement with the Department of Defense (DoD) and the WMDC. Title 14 CFR Part 150, *Airport Noise Compatibility Planning*, is the primary Federal regulation guiding and controlling planning for aviation noise compatibility on and around airports. The general purpose of a Part 150 Study is to recommend a program of airport operations and land use controls that will help to reduce aircraft noise and prevent future development which would be incompatible with airport noise.

The WMDC completed a Part 150 Study Update including updated noise exposure maps in 2014 with a Record of Approval (ROA) issued by the Federal Aviation Administration (FAA) in early 2015. Due to technology upgrades in aircraft and improved avionics at CEF an update to the Part 150 Study is proposed due to the potential to change the airport's noise contours.

Stantec and HNTB are assisting the WMDC in the development of the Part 150 Study Update. In order to evaluate demographic and land use impacts, the enclosed **Figure 1** has been developed to depict the generalized land use for the area surrounding the Airport. Land uses are generalized into the following categories: Commercial/ Industrial, Open/ Agricultural/ Recreational, Public/ Quasi-Public, Residential, Cemetery, Institutional, Water, and Transportation. Noise sensitive locations such as schools, places of worship and historic resources are also identified. This map was developed using generalized land use data from the Bureau of Geographic Information (MassGIS), and was refined based on MassGIS parcel boundary outlines and aerial photo interpretation. Areas that have been acquired under the WMDC's voluntary acquisition program are also identified. We are aware of the combined efforts of the Westover Joint Land Use (JLUS) Steering Committee and the Pioneer Valley Planning Commission (PVPC) to review and update current "Land Use" GIS data in the PVPC system. We intend to remain in communication with the JLUS/PVPC up until our project deadlines to ensure inclusion of any updated data they may generate in this interim period.

We are requesting that the Planning Department at the Town of Ludlow review the attached land use map to confirm the land use information is accurate and satisfactory to the Town's standards. Any comments or information that is provided will be corrected, and will be pertinent to the overall quality and accuracy of the study. HNTB is submitting the Draft Part 150 Study Update to the WMDC (Airport Sponsor) for review in May. Given that this is a draft submittal, any comments or changes the Town submits to HNTB **by May 21, 2018** will be considered prior to the final submission of the Part 150 Study Update. If you agree with the land uses shown on Figure 1, please sign below and return to HNTB, 2900 S. Quincy

Street, Suite 600, Arlington, VA 22206 or scan and send to cpinegar@hntb.com. If not, please make any suggested edits to the graphic or explain any requested changes in writing. If you have any questions or require any additional information, please do not hesitate to contact me at 703-253-5843 or by email at the address above.

Best regards,

Caroline E. Pinegar

Caroline E. Pinegar, AICP
HNTB

Enclosure: **Figure 1: Draft Generalized Existing Land Use**

cc: Michael Bolton, President/CEO, Westover Airport
Dan Kost, Contract Community Planner, Westover ARB
Larry Smith, Principal Land Use Planner, PVPC

DRAFT


On behalf of the Town of Ludlow Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Douglas J. Stefancik (or designee)
Planning Department
Town of Ludlow

Date

DRAFT


Westover Air Reserve Base / Metropolitan Airport
 DRAFT Generalized Existing Land Use



LEGEND

- | | | |
|---|--|--|
| ■ Commercial/Industrial | ■ Transportation | ■ Local Historic District |
| ■ Open/Agricultural/Recreational | ■ Water | ⛪ Place of Worship |
| ■ Public/Quasi-Public | ■ WARB Installation Area | 🎓 School |
| ■ Residential | ■ WMDC Aviation Property | |
| ■ Previously Acquired Property under the Voluntary Acquisition Program | ■ County Boundary | |
| ■ Cemetery | ■ Town Boundary | |
| ■ Institutional | ○ National Register of Historic Places | |
| | ■ National Register Historic District | |

Figure 1



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

[This page is left intentionally blank]

DRAFT

Attachment 2:
Land Use Verification Responses

DRAFT

On behalf of the Town of Ludlow Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.

Douglas J. Stefancik *
Douglas J. Stefancik (or designee)
Planning Department
Town of Ludlow

May 7, 2018
Date

* Note #1 Marianna Lane is all Residential.
Note #2 483-485 Wolvcke St is Commercial/Industrial.

DRAFT

City of Chicopee
Department of Planning & Development

City Hall Annex • 274 Front Street • Chicopee, Massachusetts 01013
Tel (413) 594-1515 • Fax (413) 594-1514
www.chicopeema.gov



Jack S. Benjamin
Assistant Planner

Michelle Santerre
GIS Coordinator

Lee M. Pouliot
Director, AICP, ASLA

James Dawson
Development Manager

Kristen Pope
Senior Clerk

May 16, 2018

Caroline Pinegar, AICP
HNTB Corporation
2900 South Quincy Street, Suite 600
Arlington, VA 22206

Re: WMDC Title 14 CFR Part 150 Noise Compatibility Study at Westover Air Reserve Base/Metropolitan Airport (CEF)

Caroline,

Per request made by your letter dated May 3, 2018 staff in the City of Chicopee's Department of Planning & Development has reviewed the provided land use map for the areas surrounding Westover Air Reserve Base/Metropolitan Airport. Per your letter, we understand that the land use data reflected in the provided map was sourced from available MassGIS data.

The Department of Planning & Development encourages the use of standardized MassGIS data in the absence of municipally-produced data sets. Specifically, regarding land use data, the City has not created its own data set. The Department and City utilize the MassGIS data for existing land use data on a regular basis. We also understand from the provided land use map that the data is 'generalized' and not particularly site specific or based upon land use codes as are assigned by the City's Assessors Department. Planning Staff is comfortable with the generalized data portrayed on the map as we ourselves rely on this particular MassGIS dataset. Please see attached the requested verification document, as requested.


Should you have any questions regarding this response, please feel free to contact me at any time.

With Regards,


Lee M. Pouliot, AICP, ASLA
Director

Cc: Michelle Santerre, GIS Coordinator

Westover Air Reserve Base / Metropolitan Airport DRAFT Generalized Existing Land Use



LEGEND


- | | | |
|--|--|--|
| Commercial/Industrial | Transportation | Local Historic District |
| Open/Agricultural/Recreational | Water | Place of Worship |
| Public/Quasi-Public | WARB Installation Area | School |
| Residential | WMDC Aviation Property | |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary | |
| Cemetery | Town Boundary | |
| Institutional | National Register of Historic Places | |
| | National Register Historic District | |

Figure 1



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

On behalf of the City of Chicopee Planning Department, I verify that the land use information shown on Figure 1 provided by HNTB is accurate to the best of my knowledge.



Dee M. Pouliot, ASLA (or designee)
Planning Department
City of Chicopee

5/16/18

Date

DRAFT

Attachment 3:
Public Notice of Draft Document Availability
and Public Meeting Documents
(to be provided)

**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Appendix B Correspondence
July 5, 2018

Appendix B CORRESPONDENCE



**TRIBAL AND HISTORICAL RESOURCES
INFORMATION**



Stantec Consulting Services, Inc.
136 West Street, Suite 203
Northampton, MA 01060-3711

June 21, 2018
File: 195211001

Attention: Tribal Historic Preservation Officer
Narragansett Indian Longhouse
4425 South County Trail
Charlestown, RI 02813

Dear Historic Preservation Officer,

**Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106
National Historic Preservation Act Consultation**

The Westover Metropolitan Development Corporation (WMDC) proposes certain work at the Westover Metropolitan Airport; a joint-use facility owned by the United States Air Force (USAF) but provides for civilian aeronautical use through a joint-use agreement with the WMDC. The proposed activity is subject to the National Environmental Policy Act since it requires approval from the USAF; state-level funding is also involved through the MassDOT Aeronautics Division. The USAF approval of the proposed activity is considered a Federal action thus requiring consultation pursuant to the Section 106 of the National Historic Preservation Act. The WMDC is the applicant for this project. The Federal Aviation Administration will be a cooperating agency during the NEPA process.

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF), to modify civil air operations at CEF. This Civil Aviation Action will extend the hours of civil air operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with their mission as established in the 1974 WMDC enacting legislation which reads, in part, "it is the purpose of the Westover metropolitan development corporation created by this act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment."

The extension of civil air operations will be facilitated by the installation of certain communications equipment that will provide for pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Radio communications for the nighttime operations will shift from ATCT-controlled communications to a Common Traffic Advisory Frequency (CTAF) per the procedures outlined in the Aeronautical Information Manual (AIM) Chapter 4 Section 1-9 Traffic Advisory Practices at Airports Without Operating Control Towers developed by the Federal Aviation Administration (FAA). There is no disturbance of soil, vegetation or structures associated with the work.

The attached figure shows the location of the airport, as well as the proposed change in the critical noise contours (the 65 and 70 DNL contours) between the "no action" alternative and the proposed action in the short term (2023). Differences in the contours are considered to be minor.

June 21, 2018
Tribal Historic Preservation Officer
Page 2 of 2

Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106 National Historic Preservation Act Consultation

Please review this action for potential impacts to sensitive traditional, religious and/or cultural artifacts or properties, or other environmental resources protected under Section 106 of the National Historic Preservation Act.

Regards,

Stantec Consulting Services, Inc.




Randy Christensen M.S.
Senior Environmental Scientist/Project Manager

Phone: (413)584-4776
Fax: (413)584-3157
randy.christensen@stantec.com

Attachment: Site Locus, existing and proposed noise contours
c. Westover Air Reserve Base; Attn: Mr. Jack Moriarty
cr v:\1952\temp\westover 24-hour operations env study\lea materials\let_thpo narragansett_rpc_20180612.docx


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

**Vicinity Map
Figure 2-1**



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

**Airfield Layout
Figure 2-2**




Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




- LEGEND**
- | | |
|--|---|
| No Action Alternative DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

No Action Alternative Noise Contour Figure 3




Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2015, INITS RPT (2016), Aerial: USDA 2016, ESRI Data and NHTS Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



Proposed Action Alternative Noise Contour Figure 4

- LEGEND**
- Proposed Action Alternative DNL Noise Contour
 - Commercial/Industrial
 - Open/Agricultural/Recreational
 - Public/Quasi-Public
 - Residential
 - Previously Acquired Property under the Voluntary Acquisition Program
 - Cemetery
 - Institutional
 - Transportation
 - Water
 - Westover Air Reserve Base Installation Area
 - Westover Metropolitan Development Corporation Aviation Property
 - County Boundary
 - Town Boundary
 - Place of Worship
 - School
 - National Register of Historic Places



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2016, and T&S (2018). Aerial: USDA 2016, ESRI Data and NHTS Analysis



Stantec Consulting Services, Inc.
136 West Street, Suite 203
Northampton, MA 01060-3711

June 21, 2018
File: 195211001

Attention: Tribal Historic Preservation Officer
Stockbridge-Munsee Mohican Tribal Historic Preservation,
New York Office 65 1st Street
Troy, NY 12180

Dear Historic Preservation Officer,

**Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106
National Historic Preservation Act Consultation**

The Westover Metropolitan Development Corporation (WMDC) proposes certain work at the Westover Metropolitan Airport; a joint-use facility owned by the United States Air Force (USAF) but provides for civilian aeronautical use through a joint-use agreement with the WMDC. The proposed activity is subject to the National Environmental Policy Act since it requires approval from the USAF; state-level funding is also involved through the MassDOT Aeronautics Division. The USAF approval of the proposed activity is considered a Federal action thus requiring consultation pursuant to the Section 106 of the National Historic Preservation Act. The WMDC is the applicant for this project. The Federal Aviation Administration will be a cooperating agency during the NEPA process.

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF), to modify civil air operations at CEF. This Civil Aviation Action will extend the hours of civil air operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with their mission as established in the 1974 WMDC enacting legislation which reads, in part, "it is the purpose of the Westover metropolitan development corporation created by this act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment."

The extension of civil air operations will be facilitated by the installation of certain communications equipment that will provide for pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Radio communications for the nighttime operations will shift from ATCT-controlled communications to a Common Traffic Advisory Frequency (CTAF) per the procedures outlined in the Aeronautical Information Manual (AIM) Chapter 4 Section 1-9 Traffic Advisory Practices at Airports Without Operating Control Towers developed by the Federal Aviation Administration (FAA). There is no disturbance of soil, vegetation or structures associated with the work.

The attached figure shows the location of the airport, as well as the proposed change in the critical noise contours (the 65 and 70 DNL contours) between the "no action" alternative and the proposed action in the short term (2023). Differences in the contours are considered to be minor.

June 21, 2018
Tribal Historic Preservation Officer
Page 2 of 2

Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106 National Historic Preservation Act Consultation

Please review this action for potential impacts to sensitive traditional, religious and/or cultural artifacts or properties, or other environmental resources protected under Section 106 of the National Historic Preservation Act.

Regards,

Stantec Consulting Services, Inc.



Randy Christensen M.S.
Senior Environmental Scientist/Project Manager

Phone: (413)584-4776
Fax: (413)584-3157
randy.christensen@stantec.com

Attachment: Site Locus, existing and proposed noise contours
c. Westover Air Reserve Base; Attn: Mr. Jack Moriarty
cr v:\1952\temp\westover 24-hour operations env study\lea materials\let_thpo stockbridge-munsee mohican_rpc_20180612.docx



Stantec Consulting Services, Inc.
136 West Street, Suite 203
Northampton, MA 01060-3711

June 21, 2018
File: 195211001

Attention: Tribal Historic Preservation Officer
Wampanoag Tribe of Gay Head (Aquinnah)
20 Black Brook Road
Aquinnah, MA 02535

Dear Historic Preservation Officer,

**Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106
National Historic Preservation Act Consultation**

The Westover Metropolitan Development Corporation (WMDC) proposes certain work at the Westover Metropolitan Airport; a joint-use facility owned by the United States Air Force (USAF) but provides for civilian aeronautical use through a joint-use agreement with the WMDC. The proposed activity is subject to the National Environmental Policy Act since it requires approval from the USAF; state-level funding is also involved through the MassDOT Aeronautics Division. The USAF approval of the proposed activity is considered a Federal action thus requiring consultation pursuant to the Section 106 of the National Historic Preservation Act. The WMDC is the applicant for this project. The Federal Aviation Administration will be a cooperating agency during the NEPA process.

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF), to modify civil air operations at CEF. This Civil Aviation Action will extend the hours of civil air operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with their mission as established in the 1974 WMDC enacting legislation which reads, in part, "it is the purpose of the Westover metropolitan development corporation created by this act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment."

The extension of civil air operations will be facilitated by the installation of certain communications equipment that will provide for pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Radio communications for the nighttime operations will shift from ATCT-controlled communications to a Common Traffic Advisory Frequency (CTAF) per the procedures outlined in the Aeronautical Information Manual (AIM) Chapter 4 Section 1-9 Traffic Advisory Practices at Airports Without Operating Control Towers developed by the Federal Aviation Administration (FAA). There is no disturbance of soil, vegetation or structures associated with the work.

The attached figure shows the location of the airport, as well as the proposed change in the critical noise contours (the 65 and 70 DNL contours) between the "no action" alternative and the proposed action in the short term (2023). Differences in the contours are considered to be minor.

June 21, 2018
Tribal Historic Preservation Officer
Page 2 of 2

Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106 National Historic Preservation Act Consultation

Please review this action for potential impacts to sensitive traditional, religious and/or cultural artifacts or properties, or other environmental resources protected under Section 106 of the National Historic Preservation Act.

Regards,

Stantec Consulting Services, Inc.



Randy Christensen M.S.
Senior Environmental Scientist/Project Manager

Phone: (413)584-4776
Fax: (413)584-3157
randy.christensen@stantec.com

Attachment: Site Locus, existing and proposed noise contours
c. Westover Air Reserve Base; Attn: Mr. Jack Moriarty
cr v:\1952\temp\westover 24-hour operations env study\lea materials\let_thpo wampanoag - gay head_rpc_20180612.docx



Stantec Consulting Services, Inc.
136 West Street, Suite 203
Northampton, MA 01060-3711

June 21, 2018
File: 195211001

Attention: Tribal Historic Preservation Officer
Mashpee Wampanoag Tribe
483 Great Neck Road
South Mashpee, MA 02649

Dear Historic Preservation Officer,

**Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106
National Historic Preservation Act Consultation**

The Westover Metropolitan Development Corporation (WMDC) proposes certain work at the Westover Metropolitan Airport; a joint-use facility owned by the United States Air Force (USAF) but provides for civilian aeronautical use through a joint-use agreement with the WMDC. The proposed activity is subject to the National Environmental Policy Act since it requires approval from the USAF; state-level funding is also involved through the MassDOT Aeronautics Division. The USAF approval of the proposed activity is considered a Federal action thus requiring consultation pursuant to the Section 106 of the National Historic Preservation Act. The WMDC is the applicant for this project. The Federal Aviation Administration will be a cooperating agency during the NEPA process.

The proposed action includes a proposal by the Westover Metropolitan Development Corporation (WMDC), operator of the Westover Metropolitan Airport (CEF), to modify civil air operations at CEF. This Civil Aviation Action will extend the hours of civil air operations at CEF from the current 16 hours per day (7 a.m. to 11 p.m.) to 24 hours per day to facilitate the continued development of civil aviation operations in accordance with their mission as established in the 1974 WMDC enacting legislation which reads, in part, “it is the purpose of the Westover metropolitan development corporation created by this act to aid private enterprise in the speedy and orderly conversion and redevelopment of lands formerly used for certain activities at said base to nonmilitary uses, including, but not limited to, industrial, commercial, or manufacturing uses, in order to prevent blight, economic dislocation, and additional unemployment and to aid private enterprise fully to utilize opportunities to alleviate unemployment.”

The extension of civil air operations will be facilitated by the installation of certain communications equipment that will provide for pilot-controlled operation of navigation lights in the absence of Air Traffic Control Tower (ATCT) personnel. Radio communications for the nighttime operations will shift from ATCT-controlled communications to a Common Traffic Advisory Frequency (CTAF) per the procedures outlined in the Aeronautical Information Manual (AIM) Chapter 4 Section 1-9 Traffic Advisory Practices at Airports Without Operating Control Towers developed by the Federal Aviation Administration (FAA). There is no disturbance of soil, vegetation or structures associated with the work.

The attached figure shows the location of the airport, as well as the proposed change in the critical noise contours (the 65 and 70 DNL contours) between the “no action” alternative and the proposed action in the short term (2023). Differences in the contours are considered to be minor.

June 21, 2018
Tribal Historic Preservation Officer
Page 2 of 2

Reference: Westover Metropolitan Airport – Modification to Civil Air Operations – Section 106 National Historic Preservation Act Consultation

Please review this action for potential impacts to sensitive traditional, religious and/or cultural artifacts or properties, or other environmental resources protected under Section 106 of the National Historic Preservation Act.

Regards,

Stantec Consulting Services, Inc.



Randy Christensen M.S.
Senior Environmental Scientist/Project Manager

Phone: (413)584-4776
Fax: (413)584-3157
randy.christensen@stantec.com

Attachment: Site Locus, existing and proposed noise contours
c. Westover Air Reserve Base; Attn: Mr. Jack Moriarty
cr v:\1952\temp\westover 24-hour operations env study\lea materials\let_thpo wampanoag - mashpee_rpc_20180612.docx



Mashpee Wampanoag Tribe
Section 106 Review
Consultation Response Form

Project Docket Number:	Modification to Civil Air Operations
Consultant/Environmental Firm:	Stantec Consulting Services, Inc.
Address or Location Description:	Westover Metropolitan Airport
City, State:	Chicopee, MA
Point of Contact	Randy Christensen

Response: June 27, 2018

- We have no concerns related to the proposed project. MWT anticipates no adverse effects to our sites of cultural significance, by you or your client.
- The MWT considers this project in compliance with the MWT's section 106 review process with agreed upon mitigations measures.
- This site will require the on-site presence of a Tribal Cultural Resource Monitor during ground disturbing activities. Contact the Compliance Review Supervisor with construction schedule.
- This project has the potential to have "adverse effects" to historic or cultural resources important to our tribe. We recommend the following actions:

This consultation process is in compliance to the National Historic Preservation Act of 1966 and all relevant amendments including but not limited to section 106 and 36 CFR 800.

Condition: If unanticipated discoveries of archaeological resources or human remains are found during construction, **you must immediately stop construction and notify our office.**

Deputy THPO of Compliance Review
Tribal Historic Preservation Office

From: tashtesook@aol.com
To: [Christensen, Randall](#)
Subject: RE: Westover Airport Changes to Civil Air Operations - Sec 106 Consultation - Narragansett Tribe
Date: Monday, June 25, 2018 10:45:30 PM

Randall,

Please accept this email as proof that NITHPO has completed Section 106 review of the Westover Metropolitan Airport project. We have found no findings and have no further comments to make regarding the above mentioned project.

As such this email concludes our review of your project.

Sincerely,

John Brown, NITHPO

Sent from AOL Mobile Mail
Get the new AOL app: mail.mobile.aol.com

On Monday, June 25, 2018, Christensen, Randall <randy.christensen@stantec.com> wrote:

Good Morning John.

Thank you for our phone conversation last Friday regarding the below-noted project at the Westover Metropolitan Airport; I'm pleased I was able to provide you with sufficient information for you to make your project determination. As we discussed, an email response from you would be appreciated regarding our NHPA Part 106 discussion.

I remain available to address any further requests for information.

Randall P. Christensen M.S.

Associate, Senior Environmental Scientist

Direct: 413-387-4508
Mobile: 413-519-2587
Fax: 413-584-3157
randy.christensen@stantec.com

Stantec



The content of this email is the confidential property of Stantec and should not be copied, modified, retransmitted, or used for any purpose except with Stantec's written authorization. If you are not the intended recipient, please delete all copies and notify us immediately.

From: Christensen, Randall

Sent: Thursday, June 21, 2018 3:24 PM

To: 'tashtesook@aol.com' <tashtesook@aol.com>; 'dhnithpo@gmail.com' <dhnithpo@gmail.com>

Subject: Westover Airport Changes to Civil Air Operations - Sec 106 Consultation - Narragansett Tribe

Dear Tribal Historic Preservation Officer:

Please find attached our request for project review pursuant to Section 106 of the National Historic Preservation Act. The attachment contains details concerning a proposed change to Civil Air Operations at the Westover Metropolitan Airport; a joint-use facility with the United States Air Force and the Westover Air Reserve Base. The project entails a change in air operations and involves no disturbance of soils, vegetation or structures. No construction is involved. The change to civil air operations will cause a slight increase in the off-airport extent of critical noise contours over the "no action" alternative. No other impacts are envisioned from this proposal.

Please review the attached information and contact me with any questions. Thank you for your assistance with this project.

Randall P. Christensen M.S.

Associate, Senior Environmental Scientist

Direct: 413-387-4508

Mobile: 413-519-2587

Fax: 413-584-3157

randy.christensen@stantec.com

Stantec



The content of this email is the confidential property of Stantec and should not be copied, modified, retransmitted, or used for any purpose except with Stantec's written authorization. If you are not the intended recipient, please delete all copies and notify us immediately.

Massachusetts Cultural Resource Information System

MACRIS

MACRIS Search Results

Search Criteria: Town(s): Chicopee; Place: Westover; Resource Type(s): Area, Building, Burial Ground, Object, Structure;

Inv. No.	Property Name	Street	Town	Year
CHI.AA	Westover Air Reserve Base		Chicopee	
CHI.AG	Chicopee Memorial State Park		Chicopee	
CHI.743	Westover Armed Forces Reserve Center	Airman Way	Chicopee	1959
CHI.744	Westover Armed Forces Reserve Center Garage	Airman Way	Chicopee	1978
CHI.725	Westover Air Base - Building #1900	Ellipse Dr	Chicopee	1955
CHI.925	Westover Air Base - Flagpole	Ellipse Dr	Chicopee	1939
CHI.719	Westover Air Base - Building #1502 - Photo Lab	450 Ellipse Dr	Chicopee	1940
CHI.710	Westover Air Base - Bldg #5302 - Bldg #S-241	First Ave	Chicopee	1942
CHI.713	Westover Air Base - Field Officer's Quarters	53 Fredette St	Chicopee	1941
CHI.917	Shawinigan Drive Bridge over Fuller Brook	Fuller Rd	Chicopee	1956
CHI.252	Fuller, Orrin House	809 Fuller Rd	Chicopee	r 1830
CHI.711	Westover Air Base - Bldg #2503 - Pumping Station	Hangar Ave	Chicopee	1942
CHI.715	Westover Air Base - Bldg #1529 - Switching Station	Hangar Ave	Chicopee	1940
CHI.716	Westover Air Base - Building #1528 - Warehouse	Hangar Ave	Chicopee	1940
CHI.722	Westover Air Base - Building #1312 - Valve Shelter	Hangar Ave	Chicopee	1942
CHI.728	Westover Air Base - Building #2502 - Building P-29	Hangar Ave	Chicopee	1941
CHI.729	Westover Air Base - Building #2500 - Building P-77	Hangar Ave	Chicopee	1941
CHI.734	Westover Air Base - Building #7010 - Arms Storage	Hangar Ave	Chicopee	1941
CHI.736	Westover Air Base - Building #7012 - Arms Storage	Hangar Ave	Chicopee	1941
CHI.924	Westover Air Base - Bldg #1311 - Water Tower	Hangar Ave	Chicopee	1941
CHI.737	Westover Air Base - Building #7071 - Base Hangar 9	250 Hangar Ave	Chicopee	1941

Inv. No.	Property Name	Street	Town	Year
CHI.738	Westover Air Base - Building #7072 - Base Hangar 7	350 Hangar Ave	Chicopee	1941
CHI.723	Westover Air Base - Building #1310 - Warehouse	395 Hangar Ave	Chicopee	1941
CHI.739	Westover Air Base - Building #7073 - Base Hangar 5	450 Hangar Ave	Chicopee	1941
CHI.720	Westover Air Base - Building #1411 - Heating Plant	495 Hangar Ave	Chicopee	1941
CHI.740	Westover Air Base - Building #7075 - Base Hangar 3	550 Hangar Ave	Chicopee	1941
CHI.741	Westover Air Base - Building #7087 - Base Hangar 1	650 Hangar Ave	Chicopee	1941
CHI.717	Westover Air Base - Bldg #1520 - Fire - Guard Hse	651 Hangar Ave	Chicopee	1941
CHI.712	Westover Air Base - Building P-603	Industrial Hwy	Chicopee	1940
CHI.733	Westover Air Base - Building #6300 - Sentry House	Industrial Rd	Chicopee	1940
CHI.718	Westover Air Base - Building #1510 - Building P-41	250 Jenkins St	Chicopee	1942
CHI.735	Westover Air Base - Building #7011 - Arms Storage	Logistics Dr	Chicopee	1941
CHI.727	Westover Air Base - Building #7450 - The Mole Hole	255 Padgette St	Chicopee	1959
CHI.721	Westover Air Base - Building #1408 - Commissary	570 Patriot Ave	Chicopee	1941
CHI.730	Westover Air Base - Bldg #1601 - PX Gas Station	880 Patriots Ave	Chicopee	1942
CHI.714	Westover Air Base - Bldg #3150 - Little Kings Row	Seawolf Ave	Chicopee	1941
CHI.709	Westover Air Base - Bldg 5305 - Bldg S-244 - S-106	Second Ave	Chicopee	1942
CHI.731	Westover Air Base - Building #5309 - Metal Shop	Second Ave	Chicopee	1942
CHI.732	Westover Air Base - Building #5312 - Plumbing Shop	Second Ave	Chicopee	1942
CHI.742	Westover Air Base - Buildings #5306 and #669	Second Ave	Chicopee	1942
CHI.922	Westover Air Base - Imhoff Tanks	Second Ave	Chicopee	1941
CHI.432	Butterfield Farm	850 Sheridan St	Chicopee	c 1856
CHI.564	Butterfield Farm Barn	850 Sheridan St	Chicopee	c 1856
CHI.726	Westover Air Base - Building #1875	100 Starlifter Ave	Chicopee	1957
CHI.724	Westover Air Base - Building #1100 - Headquarters	100 Walker Ave	Chicopee	1942
CHI.921	Westover Air Base - Ellipse	Westover Air Base	Chicopee	1939
CHI.923	Westover Air Base - Crosswind Airplane Runway	Westover Air Base	Chicopee	1940

PROTECTED SPECIES INFORMATION



United States Department of the Interior



FISH AND WILDLIFE SERVICE
New England Ecological Services Field Office
70 Commercial Street, Suite 300
Concord, NH 03301-5094
Phone: (603) 223-2541 Fax: (603) 223-0104
<http://www.fws.gov/newengland>

In Reply Refer To:

June 20, 2018

Consultation Code: 05E1NE00-2018-SLI-2154

Event Code: 05E1NE00-2018-E-04987

Project Name: Westover Metropolitan Airport (CEF) Modification to General Aviation Operations

Subject: List of threatened and endangered species that may occur in your proposed project location, and/or may be affected by your proposed project

To Whom It May Concern:

The enclosed species list identifies threatened, endangered, proposed and candidate species, as well as proposed and final designated critical habitat, that may occur within the boundary of your proposed project and/or may be affected by your proposed project. The species list fulfills the requirements of the U.S. Fish and Wildlife Service (Service) under section 7(c) of the Endangered Species Act (Act) of 1973, as amended (16 U.S.C. 1531 *et seq.*).

New information based on updated surveys, changes in the abundance and distribution of species, changed habitat conditions, or other factors could change this list. Please feel free to contact us if you need more current information or assistance regarding the potential impacts to federally proposed, listed, and candidate species and federally designated and proposed critical habitat. Please note that under 50 CFR 402.12(e) of the regulations implementing section 7 of the Act, the accuracy of this species list should be verified after 90 days. This verification can be completed formally or informally as desired. The Service recommends that verification be completed by visiting the ECOS-IPaC website at regular intervals during project planning and implementation for updates to species lists and information. An updated list may be requested through the ECOS-IPaC system by completing the same process used to receive the enclosed list.

The purpose of the Act is to provide a means whereby threatened and endangered species and the ecosystems upon which they depend may be conserved. Under sections 7(a)(1) and 7(a)(2) of the Act and its implementing regulations (50 CFR 402 *et seq.*), Federal agencies are required to utilize their authorities to carry out programs for the conservation of threatened and endangered species and to determine whether projects may affect threatened and endangered species and/or designated critical habitat.

A Biological Assessment is required for construction projects (or other undertakings having similar physical impacts) that are major Federal actions significantly affecting the quality of the human environment as defined in the National Environmental Policy Act (42 U.S.C. 4332(2)(c)). For projects other than major construction activities, the Service suggests that a biological evaluation similar to a Biological Assessment be prepared to determine whether the project may affect listed or proposed species and/or designated or proposed critical habitat. Recommended contents of a Biological Assessment are described at 50 CFR 402.12.

If a Federal agency determines, based on the Biological Assessment or biological evaluation, that listed species and/or designated critical habitat may be affected by the proposed project, the agency is required to consult with the Service pursuant to 50 CFR 402. In addition, the Service recommends that candidate species, proposed species and proposed critical habitat be addressed within the consultation. More information on the regulations and procedures for section 7 consultation, including the role of permit or license applicants, can be found in the "Endangered Species Consultation Handbook" at:

<http://www.fws.gov/endangered/esa-library/pdf/TOC-GLOS.PDF>

Please be aware that bald and golden eagles are protected under the Bald and Golden Eagle Protection Act (16 U.S.C. 668 *et seq.*), and projects affecting these species may require development of an eagle conservation plan (http://www.fws.gov/windenergy/eagle_guidance.html). Additionally, wind energy projects should follow the wind energy guidelines (<http://www.fws.gov/windenergy/>) for minimizing impacts to migratory birds and bats.

Guidance for minimizing impacts to migratory birds for projects including communications towers (e.g., cellular, digital television, radio, and emergency broadcast) can be found at: <http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/towers.htm>; <http://www.towerkill.com>; and <http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/comtow.html>.

We appreciate your concern for threatened and endangered species. The Service encourages Federal agencies to include conservation of threatened and endangered species into their project planning to further the purposes of the Act. Please include the Consultation Tracking Number in the header of this letter with any request for consultation or correspondence about your project that you submit to our office.

Attachment(s):

- Official Species List
-

Official Species List

This list is provided pursuant to Section 7 of the Endangered Species Act, and fulfills the requirement for Federal agencies to "request of the Secretary of the Interior information whether any species which is listed or proposed to be listed may be present in the area of a proposed action".

This species list is provided by:

New England Ecological Services Field Office

70 Commercial Street, Suite 300

Concord, NH 03301-5094

(603) 223-2541

Project Summary

Consultation Code: 05E1NE00-2018-SLI-2154

Event Code: 05E1NE00-2018-E-04987

Project Name: Westover Metropolitan Airport (CEF) Modification to General Aviation Operations

Project Type: TRANSPORTATION

Project Description: Installation of pilot-controlled electronics allowing for non-tower assisted nighttime air operations at CEF. No soil disturbance, construction and/or demolition is proposed with the project.

Project Location:

Approximate location of the project can be viewed in Google Maps: <https://www.google.com/maps/place/42.19462987050227N72.53769176606535W>



Counties: Hampden, MA

Endangered Species Act Species

There is a total of 1 threatened, endangered, or candidate species on this species list.

Species on this list should be considered in an effects analysis for your project and could include species that exist in another geographic area. For example, certain fish may appear on the species list because a project could affect downstream species.

IPaC does not display listed species or critical habitats under the sole jurisdiction of NOAA Fisheries¹, as USFWS does not have the authority to speak on behalf of NOAA and the Department of Commerce.

See the "Critical habitats" section below for those critical habitats that lie wholly or partially within your project area under this office's jurisdiction. Please contact the designated FWS office if you have questions.

-
1. [NOAA Fisheries](#), also known as the National Marine Fisheries Service (NMFS), is an office of the National Oceanic and Atmospheric Administration within the Department of Commerce.

Mammals

NAME	STATUS
Northern Long-eared Bat <i>Myotis septentrionalis</i> No critical habitat has been designated for this species. Species profile: https://ecos.fws.gov/ecp/species/9045	Threatened


Critical habitats

THERE ARE NO CRITICAL HABITATS WITHIN YOUR PROJECT AREA UNDER THIS OFFICE'S JURISDICTION.

**DRAFT NEPA ENVIRONMENTAL ASSESSMENT
WESTOVER REGIONAL AIRPORT – MODIFICATIONS TO CIVIL AVIATION OPERATIONS**

Appendix C Noise Analysis – Technical Memo
July 5, 2018

Appendix C NOISE ANALYSIS – TECHNICAL MEMO





Ervin Deck, Senior Associate, Aviation Planning – Transportation
Randall Christensen, Associate, Senior Environmental Scientist
Stantec Consulting Services Inc.
482 Payne Road Scarborough Court
Scarborough, ME 04074-8929

May 25, 2018

Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF) Title 14 C.F.R. Part 150 and EA Studies – Noise Contour Development

1. Introduction

The Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF), home to the Massachusetts Air Force Reserve 439th Airlift Wing, previously operated Lockheed C-5A Galaxy aircraft and has upgraded to the C-5M Super Galaxy. A Title 14 Code of Federal Register (CFR) Part 150 Update (Part 150 Update) is being prepared to disclose the impacts of the C-5M Super Galaxy fleet upgrade. The Westover Metropolitan Development Corporation (WMDC) proposes to extend CEF operating hours to 24 hours per day and an Environmental Assessment (EA) is being prepared to assess the potential environmental impacts of this change in operating hours.

To assist with the Part 150 Update and EA, HNTB prepared noise exposure contours representative of existing conditions in 2018, and forecast conditions in 2019 and 2023 using the Aviation Environmental Design Tool (AEDT) Version 2d and NOISEMAP Version 7.363. This technical memorandum presents the data sources, methodologies, and assumptions applied to develop the noise contours, as well as the presentation of noise contours and their comparisons.

2. Data Sources, Methodologies, and Assumptions

The data sources applied in the noise contour development included information collected and presented in the 2013 Air Installation Compatible Use Zone (AICUZ) Studyⁱ (2013 AICUZ Study), the 2014 14 CFR Part 150 Noise Compatibility Study (2014 Part 150 Study), operations data from 2017 and 2018 as provided by the CEF Airport Traffic Control Tower (ATCT), coordination with the Federal Aviation Administration (FAA) and U.S. Air Forces (USAF), and various other sources.

2.1 Alternatives, Fleet Mixes and Operations

The Existing Condition (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low General Aviation (GA) Operations (2023) fleet mixes were developed based on information provided by the ATCT, and included potential new aircraft that would be introduced if the airport hours were extended from 16-hour to 24-hour. The fleet mixes were developed by Stantec for use by HNTB. The Part 150 Update applies the Existing Condition

(2018) and the Future No Action (2023) fleet mixes. The EA Study applies the Existing Condition (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low GA Operations (2023) fleet mixes. The following assumptions were included in each alternative/scenario:

- Existing Conditions represented the current state at CEF in 2018. The fleet mixes and operations represented the current aircraft types and associated operations.
- Short Term represented the first year (2019) when the airport operating hours would be extended from 16 hours per day to 24 hours per day. The fleet mixes and operations included potential new aircraft types and additional nighttime operations.
- Future No Action (2023) assumed the airport would remain open for 16 hours per day in 2023. The fleet mixes and operations included projected operations but no changes to fleet mix.
- Future Proposed Action (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The fleet mixes and operations included potential new aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 4 arrivals and 4 departures each night.
- Low GA Operations (2023) assumed the airport operating hours would be extended from 16 hours per day to 24 hours per day in 2023. The fleet mixes and operations included potential new aircraft types and additional nighttime operations. It was assumed that the nighttime flights would increase by an additional 2 arrivals and 2 departures each night.

Aircraft in the fleet mixes were converted to representative noise aircraft, and operations were converted to Average Annual Day (AAD) operations by dividing the annual operations by 365. **Tables A-1 to A-5 in Appendix A** show the fleet mixes, representative noise aircraft, and AAD operations. **Table 1** depicts a summary of the total annual and AAD operations.

Table 1
Total Aircraft Operations

Operations	Existing Condition (2018)	Short Term (2019)	Future No Action (2023)	Future Proposed Action (2023)	Low GA Operations (2023)
Annual	19,754	20,214	20,816	23,708	22,190
AAD	54.1	55.4	57.0	65.0	60.8

Sources: Stantec and HNTB analysis, 2018.

2.1.1 Noise Aircraft Substitution in AEDT and NOISEMAP

Consistent with FAA’s NEPA guidance, civilian operations at CEF were modeled in the latest version of AEDT (Version 2d) while military operations were modeled in the latest version of NOISEMAP (Version 7.363). Both models include a database of representative aircraft whose performance and noise parameters have been approved by the FAA. In addition, the FAA maintains a list of approved substitutions for certain aircraft types that may be substituted with

another noise aircraft with similar noise signature when an aircraft is not within the model database. However, there are some aircraft types without direct AEDT 2d aircraft types or substitutions. Under this circumstance, the FAA Office of Environment and Energy (AEE) Noise Division (AEE-100) must be consulted. CEF required this type of coordination as not all aircraft expected to use the Airport were included in the noise model or approved substitution list. An AEE coordination letter was sent on April 19th, 2018 and the FAA approved the substitutions on May 8th, 2018. All the recommended aircraft substitutions were approved except the F-22 Falcon, which was recommended to be modeled in NOISEMAP. **Appendix B** includes the AEE coordination letter and the FAA approval letter.

2.1.2 Day/Night Split

For noise modeling purposes, acoustic daytime is defined as 7:00 A.M. to 9:59 P.M., and acoustic nighttime is defined as 10:00 P.M. to 6:59 A.M. The noise model includes a nighttime penalty of 10 dB for all operations occurring during nighttime hours. **Table 2** compares the day/night split in the five scenarios. Since it was assumed that the airport operating hours would be extended into nighttime hours for the Short Term, Future Proposed Action and Low GA Operations alternatives, the percentage of nighttime operations would increase under these alternatives.

Table 2
AAD Day/Night Split Comparison

Alternatives	Existing Condition (2018)	Short Term (2019)	Future No Action (2023)	Future Proposed Action (2023)	Low GA Operations (2023)
Day	99.9%	97.7%	99.9%	87.5%	93.7%
Night	0.1%	2.3%	0.1%	12.5%	6.3%
Total	100.0%	100.0%	100.0%	100.0%	100.0%

Sources: Stantec and HNTB analysis, 2018.

2.1.3 Stage Length

Stage length is a noise modeling term used to refer to trip distance for an aircraft departure from origin to destination, and is a surrogate for aircraft weight. The trip distance influences the take-off weight (and therefore the thrust and performance) of the aircraft, as more fuel is required to fly longer distances and therefore adds weight to the aircraft. Where necessary, HNTB adjusted the stage lengths to adhere to the maximum stage lengths available in the noise models. **Table 3** shows the stage length comparison between the alternatives.

Table 3
Stage Length Comparison

Stage Length	Existing Condition (2018)	Short Term (2019)	Future No Action (2023)	Future Proposed Action (2023)	Low GA Operations (2023)
1 (0 – 500 nmi)	92.8%	92.2%	91.4%	86.7%	90.4%
2 (501 – 1,000 nmi)	4.9%	5.3%	6.3%	10.5%	7.0%
3 (1,001 – 1,500 nmi)	1.9%	2.1%	1.9%	2.1%	2.0%
4 (1,501 – 2,500 nmi)	0.4%	0.4%	0.4%	0.7%	0.5%
5 (2,501 – 3,500 nmi)	0.1%	0.1%	0.0%	0.1%	0.1%
Total	100.0%	100.0%	100.0%	100.0%	100.0%

Totals may not sum up due to rounding.

Sources: Stantec and HNTB analysis, 2018.

Table 3 shows the Proposed Action (2023) alternative is expected to have departures with higher percentage of distance between 501 and 1,000 nautical miles than the other alternatives. This is because more business jet operations are expected under the Proposed Action alternative and business jets tend to fly longer distances than piston aircraft.

2.1.4 Flight Profiles

AEDT and NOISEMAP include many standard flight profiles to represent how an aircraft normally flies in the vicinity of an airfield. The standard flight profiles were applied in both the EA and Part 150 Update wherever available. The USAF noise modeling team provided the standard arrival, departure and closed pattern flight profiles for C-5M. Based on the updated C-5M flight profiles, C-5A arrival, departure, and closed pattern flight profiles included in the 2013 AICUZ Study and 2014 Part 150 Study were then modified. In addition, the standard C-5M flight profiles were consistent with the C-5M flight profiles included in the Environmental Assessment of the Interim Relocation of two F-16 Squadrons studyⁱⁱ. All of the C-5M flight profiles were verified by a WARB C-5M pilot, Colonel Ian Coogan of the Massachusetts Air Force Reserve 439th Airlift Wing.

2.2 Runway Use

Runway use for both civil and military operations remained consistent with that presented in the 2014 Part 150 Study. It was assumed that the future runway use would be the same as the existing runway use. **Table 4** shows the runway use for civilian aircraft and **Table 5** shows the runway use for military aircraft. The civilian runway use was applied by aircraft types. The military runway use was applied by based C-5M, transient fixed wing aircraft, and transient helicopters.

Table 4
Existing and Future Runway Use for Civilian Aircraft

Operation Type	Aircraft Type	Runway ID	Day	Night
Arrival	SEP	5	19.6%	19.6%
		23	80.4%	80.4%
		15	-	-
		33	-	-
	MEP	5	19.6%	19.6%
		23	80.4%	80.4%
		15	-	-
		33	-	-
	MET	5	19.6%	19.6%
		23	80.4%	80.4%
		15	-	-
		33	-	-
JET	5	19.6%	19.6%	
	23	80.4%	80.4%	
	15			
	33			
Departure	SEP	5	80.1%	80.1%
		23	19.9%	19.9%
		15	-	-
		33	-	-
	MEP	5	80.1%	80.1%
		23	19.9%	19.9%
		15	-	-
		33	-	-
	MET	5	80.1%	80.1%
		23	19.9%	19.9%
		15	-	-
		33	-	-
JET	5	80.1%	80.1%	
	23	19.9%	19.9%	
	15	-	-	
	33	-	-	

SEP–Single Engine Piston; MEP–Multi-Engine Piston; MET–Multi-Engine Turboprop; JET–Jet; HEL–Helicopter

Source: 2014 Part 150 Study and 2013 AICUZ Study.

**Table 5
Existing and Future Runway Use for Military Aircraft**

Operation Group	Operation Type	Runway	Percentage		
			Day	Night	
Base C-5M	Arrival	05	40.0%	40.0%	
		23	60.0%	60.0%	
	Closed Pattern	05	22.0%	0.0%	
		23	64.0%	0.0%	
		15	3.0%	0.0%	
		33	11.0%	0.0%	
	Departure	05	22.0%	22.0%	
		23	64.0%	64.0%	
		15	3.0%	3.0%	
		33	11.0%	11.0%	
	Transient	Arrival	05	46.0%	27.4%
			23	47.7%	54.9%
15			0.0%	0.0%	
33			3.2%	9.2%	
Drop Zone			3.1%	8.5%	
Closed Pattern		Drop Zone	100.0%	0.0%	
Departure		05	38.8%	35.9%	
		23	58.0%	54.9%	
		15	0.0%	0.0%	
		33	3.2%	9.2%	
Helicopter	Arrival	23	66.0%	0.0%	
		Helipad	34.0%	0.0%	
	Closed Pattern	05	1.0%	0.0%	
		23	3.8%	0.0%	
		15	0.0%	0.0%	
		33	2.9%	0.0%	
		Drop Zone	23.1%	0.0%	
		SLING	69.2%	0.0%	
	Departure	Helipad	100.0%	0.0%	

Sources: 2014 Part 150 Study and HNTB Analysis, 2018.

2.3 Weather

Default weather parameters in the AEDT model should be applied, as per FAA guidance on the AEDT application to the National Environmental Policy Act (NEPA)ⁱⁱⁱ. However, the default CEF average temperature and pressure data were missing from AEDT. The FAA AEE suggested using the same data sources for all the weather parameters. Therefore, weather parameters collected from weather station 744910 – Westover AFB/Metropolitan Airport (between April 1989 and March 2018) were applied in the noise models. **Table 6** provides the average temperature and pressure at CEF^{iv}, together with other AEDT weather parameters of CEF.

Table 6
Weather Parameters

Parameter	Value
Temperature	50.0 (°F)
Pressure	1,006.6 (millibars)
Dew Point	38.8 (°F)
Humidity	65.1%
Headwind	5.7 (knots)

Source: NOAA, 2018.

2.4 Terrain

Terrain data is used to account for effects that variations in terrain have on noise propagation. The noise contours were modeled using 1/3 arc-second data from the Multi-Resolution Land Characteristics Consortium (MRLC) of the National Land Cover Database (NLCD)^v.

2.5 Flight Track Locations and Use

Aircraft flight tracks refer to the tracks depicting arrival and departure routes to and from individual runways at an airport. Depending on weather and the aircraft flight characteristics, actual aircraft flight paths are infrequently identical. However, flight paths with similar characteristics can be grouped together and be represented with common flight tracks, which are required by the noise model. Figures 1 and 2 in **Appendix C** illustrate the proposed flight tracks for arrival and departure operations flown by civilian fixed wing aircraft, and Figures 3 and 4 in Appendix C illustrate the proposed flight tracks for arrival and departure operations flown by helicopters.

2.6 Maintenance Run-Up Operations


Aircraft maintenance engine run-ups can also be modeled in AEDT and NOISEMAP, and depending on their frequency and orientation, they may influence the size and location of noise exposure contours. Aircraft maintenance engine run-up logs from 2017 were obtained as the basis for modeling the existing condition run-up noise impact. A total of 139 engine run-up operations were recorded in 2017. The 2017 run-up operations were categorized into two types: idle run and power run. It was assumed that C-5M aircraft would apply 65% of power during the idle runs, and would apply 85% of power during power runs. It was also assumed that the C-5M parking positions have not changed from the previous two studies, and the duration of the run-

ups would be the difference between entry and exit time. The future run-ups were assumed to increase at the same rate of the C-5M operation increase.

3. DNL Noise Contours and Comparison

DNL noise exposure was calculated using AEDT and NOISEMAP. **Figures 1 through 5** depict the 65 – 75 DNL noise contours in 5 dB increments for the Existing Conditions (2018), Short Term (2019), Future No Action (2023), Future Proposed Action (2023), and Low GA Operation (2023) alternatives. **Figure 6** compares the noise contours for all five alternatives. **Tables 7 through 11** depict the total areas by land use categories for the five alternatives.


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- | | |
|--|---|
| Existing Conditions DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

Existing Conditions Noise Contour Figure 1




Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2012, 10/16/2012 (2012), Aerial - USDA 2014, ESRI Data and MapX Analyst

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




- LEGEND**
- Short Term DNL Noise Contour
 - Commercial/Industrial
 - Open/Agricultural/Recreational
 - Public/Quasi-Public
 - Residential
 - Previously Acquired Property under the Voluntary Acquisition Program
 - Cemetery
 - Institutional
 - Transportation
 - Water
 - Westover Air Reserve Base Installation Area
 - Westover Metropolitan Development Corporation Aviation Property
 - County Boundary
 - Town Boundary
 - Place of Worship
 - School
 - National Register of Historic Places

**Short Term Noise Contour
Figure 2**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2015, INITS 817 (2016), Aerial/USDA 2016, ESRI Data and NHTS Analysis


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- | | |
|--|---|
| No Action Alternative DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

No Action Alternative Noise Contour Figure 3



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2015, INITS RPT (2016), Aerial/USDA 2016, ESRI Data and NHTS Analysis


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- | | |
|--|---|
| Proposed Action Alternative DNL Noise Contour | Transportation |
| Commercial/Industrial | Water |
| Open/Agricultural/Recreational | Westover Air Reserve Base Installation Area |
| Public/Quasi-Public | Westover Metropolitan Development Corporation Aviation Property |
| Residential | County Boundary |
| Previously Acquired Property under the Voluntary Acquisition Program | Town Boundary |
| Cemetery | Place of Worship |
| Institutional | School |
| | National Register of Historic Places |

Proposed Action Alternative Noise Contour Figure 4



Source: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2016, and T&S (2018). Aerial: USDA 2016, ESRI Data and NHTS Analysis


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


Low GA Operations DNL Noise Contour	Transportation
Commercial/Industrial	Water
Open/Agricultural/Recreational	Westover Air Reserve Base Installation Area
Public/Quasi-Public	Westover Metropolitan Development Corporation Aviation Property
Residential	County Boundary
Previously Acquired Property under the Voluntary Acquisition Program	Town Boundary
Cemetery	Place of Worship
Institutional	School
	National Register of Historic Places

Low GA Operations Noise Contour Figure 5



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2015, INITS RPT (2016), Aerial © USDA 2016, ESRI Data and NHTS Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

Existing Condition (2018)	Commercial/Industrial	Transportation
Short Term (2019)	Open/Agricultural/Recreational	Water
No Action (2023)	Public/Quasi-Public	Westover Air Reserve Base Installation Area
Proposed Action (2023)	Residential	WMDC Aviation Property
Low GA Operations (2023)	Previously Acquired Property under the Voluntary Acquisition Program	County Boundary
	Cemetery	Town Boundary
	Institutional	Place of Worship
		School
		National Register of Historic Places

65+ DNL Contour Comparison
Figure 6

Scale: 1" = 2,000'
0 500 1,000 2,000 Feet

Sources: Bureau of Geographic Information Systems, Massachusetts, Commonwealth of Massachusetts, Executive Office of Technology and Security Services, Westover Metropolitan Development Corporation 2010, NEMD 2012, 2015, Aerial - USDA 2016, 8-Net Data and NEM Analysis

Table 7
**Generalized Land Uses within the Existing Conditions (2018) 65 DNL Contour
(acres)**

Generalized Land Use	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
Airport Property	368.4	171.3	57.2	596.9
Industrial	1.7	-	-	1.7
Open/Agricultural	13.8	-	-	13.8
Recreational	-	-	-	-
Residential	-	-	-	-
Transportation/Utility	-	-	-	-
Voluntary Acquisition Property	-	-	-	-
Water	0.6	-	-	0.6
Wetland	-	-	-	-
Grand Total	384.5	171.3	57.2	613.0

Source: PVPC and MassDOT Land Use Data, Stantec and HNTB Analysis, 2018.

Table 8
Generalized Land Uses within the Short Term (2019) 65 DNL Contour (acres)

Generalized Land Use	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
Airport Property	375.1	166.9	66.0	608.0
Industrial	1.8	-	-	1.8
Open/Agricultural	15.6	-	-	15.6
Recreational	-	-	-	-
Residential	-	-	-	-
Transportation/Utility	-	-	-	-
Voluntary Acquisition Property	-	-	-	-
Water	0.7	-	-	0.7
Wetland	-	-	-	-
Grand Total	393.2	166.9	66.0	626.1

Source: PVPC and MassDOT Land Use Data, Stantec and HNTB Analysis, 2018.

Table 9
Generalized Land Uses within the No Action (2023) 65 DNL Contour (acres)

Generalized Land Use	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
Airport Property	386.8	163.7	76.2	626.7
Industrial	1.8	-	-	1.8
Open/Agricultural	20.9	-	-	20.9
Recreational	-	-	-	-
Residential	-	-	-	-
Transportation/Utility	-	-	-	-
Voluntary Acquisition Property	-	-	-	-
Water	3.3	-	-	3.3
Wetland	-	-	-	-
Grand Total	412.8	163.7	76.2	652.7

Source: PVPC and MassDOT Land Use Data, Stantec and HNTB Analysis, 2018.

Table 10
Generalized Land Uses within the Proposed Action (2023) 65 DNL Contour (acres)

Generalized Land Use	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
Airport Property	410.8	162.8	99.9	673.5
Industrial	2.1	-	-	2.1
Open/Agricultural	33.6	-	-	33.6
Recreational	0.3	-	-	-
Residential	-	-	-	-
Transportation/Utility	-	-	-	-
Voluntary Acquisition Property	-	-	-	-
Water	6.1	-	-	6.1
Wetland	-	-	-	-
Grand Total	452.9	162.8	99.9	715.3

Source: PVPC and MassDOT Land Use Data, Stantec and HNTB Analysis, 2018.

Table 11
**Generalized Land Uses within the Low GA Operations (2023) 65 DNL Contour
(acres)**

Generalized Land Use	65-70 DNL	70-75 DNL	75+ DNL	65+ DNL
Airport Property	397.4	161.8	90.1	649.3
Industrial	2.0	-	-	2.0
Open/Agricultural	26.9	-	-	26.9
Recreational	-	-	-	-
Residential	-	-	-	-
Transportation/Utility	-	-	-	-
Voluntary Acquisition Property	-	-	-	-
Water	3.9	-	-	3.9
Wetland	-	-	-	-
Grand Total	430.2	161.8	90.1	682.1

Source: PVPC and MassDOT Land Use Data, Stantec and HNTB Analysis, 2018.

The total area within the 65+ DNL noise contour of the Proposed Action (2023) alternative is 715.3 acres, which is 16.7% larger than the Existing Conditions (2018), and 9.6% larger than the No Action (2023) alternative. The larger contour is due to an increase in operations, especially nighttime operations under the Proposed Action. The total area within the 65+ DNL noise contour of the Low GA Operations (2023) alternative is 682.1 acres, which is 11.3% larger than the Existing Conditions (2018) and 4.5% larger than the No Action (2023) alternative. The total area within the 65+ DNL noise contour of the Short Term (2019) alternative is 626.1 acres, which is slightly larger (2.1%) than the Existing Conditions (2018) alternative.

The study shows no residential areas or noise sensitive sites are included in the 65+ DNL noise contour of any of the five alternatives. The 70+ DNL noise contour falls entirely within the airport boundary for all alternatives. Compared with the No Action (2023) alternative, the Proposed Action (2023) alternative 65+ DNL noise contour extends slightly further to the northeast beyond the north bank of Wade Pond and Stony Brook. For other areas, the Proposed Action (2023) and No Action (2023) noise contours are very similar. This is because the noise contours are dominated by the military noise signature in the future alternatives. Therefore, the increase of GA nighttime operations under the Proposed Action is expected to be a minor contributor to the overall noise exposure. The military noise signature is by far the largest contributor to the overall noise exposure for CEF and is present in all future alternatives.

4. Supplemental Noise Metrics

Two supplemental noise metrics were evaluated including the Percent Highly Annoyed and the Probability of Awakening. The methodologies followed the two technical bulletins published by the U.S. Department of Defense Noise Working Group (DNWG).

4.1 Percent of Highly Annoyed

The Percent of Highly Annoyed metric is based on DNL metrics and assesses the percentage of population expected to be 'highly annoyed' by aviation noise. A widely referenced research on this metric was performed by T.J. Schultz^{vi} in 1978, and the curve relating noise levels with community's response (annoyance) to the noise is usually referred to as the 'Schultz Curve'. In 1992, the U.S. Federal Interagency Committee on Noise (FICON) published a report indicating 'the percentage of the area population characterized as 'highly annoyed' by long-term exposure to noise' was its preferred measure of annoyance^{vii}. The report utilized a larger pool of sample data than the Schultz study and developed an updated curve known as the 'FICON Curve' or the 'Updated Schultz Curve'. In 2009, the DNWG published a technical bulletin recommending the 'FICON Curve' as the 'best available source of empirical dosage effect information to predict community response to transportation noise without any segregation by transportation source'^{viii}. **Figure 7** shows the Schultz and FICON curves.





Figure 7: Schultz and FICON Curves (source: DoD Technical Bulletin^{viii}).

Therefore, the 'FICON Curve' was applied in this study to estimate the population that would be highly annoyed. DNL values were converted to the percentage of highly annoyed based on the curve. **Figures 8 through 12** show the 10%, 20%, and 30% highly annoyed curves for each of the five alternatives. **Table 12** summarizes the areas that are on- or off-airport boundary under 10% annoyed by alternative. The areas under 20% and 30% would fall entirely within the airport boundary.


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| Existing Conditions (2018) Percentage of Highly Annoyed | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | Place of Worship |
| | School |
| | National Register of Historic Places |
| | Local Historic District |


**Existing Conditions (2018)
Percentage of Highly Annoyed Scenario
Figure 8**



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| Short Term Percentage of Highly Annoyed | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | Place of Worship |
| | School |
| | National Register of Historic Places |
| | Local Historic District |


Short Term Percentage of Highly Annoyed Scenario Figure 9



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC: 2015, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




LEGEND

- No Action Alternative Percentage of Highly Annoyed
- Commercial/Industrial
- Open/Agricultural/Recreational
- Public/Quasi-Public
- Residential
- Previously Acquired Property under the Voluntary Acquisition Program
- Cemetery

- Institutional
- Transportation
- Water
- WARB Installation Area
- WMDC Aviation Property
- County Boundary
- Town Boundary
- Place of Worship

- School
- National Register of Historic Places
- Local Historic District


No Action Alternative Percentage of Highly Annoyed Scenario Figure 10



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC: 2015, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| Proposed Action Alternative Percentage of Highly Annoyed | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | Place of Worship |
| | School |
| | National Register of Historic Places |
| | Local Historic District |


Proposed Action Alternative Percentage of Highly Annoyed Scenario Figure 11



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|--|--------------------------------------|
| Low GA Operations Percentage of Highly Annoyed | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | School |
| | National Register of Historic Places |
| | Local Historic District |
| | Place of Worship |

Low GA Operations Percentage of Highly Annoyed Scenario Figure 12



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2018, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

Table 12
Percentage of Highly Annoyed 10% and Above

Alternative	On-Airport Acres	Off-Airport Acres	Total Acres
Existing Conditions (2018)	760.6	84.5	845.1
Short Term (2019)	771.4	91.1	862.5
No Action (2023)	802.4	112.1	914.5
Proposed Action (2023)	857.4	155.1	1,012.5
Low GA Operations (2023)	831.9	132.6	964.5

Source: DoD Technical Bulletin, 2009; Stantec and HNTB Analysis, 2018.

The analysis shows the majority (approximately 85% - 90%) of the 10% contour falls within the airport boundary. The total area within 10% contour of the Proposed Action (2023) alternative is 1,012.5 acres, which is 19.8% larger than the Existing Conditions (2018), and 10.7% larger than the No Action (2023) alternative. The larger contour is due to an increase in operations, especially nighttime operations under the Proposed Action. The total area within the 10% contour of the Low GA Operations (2023) alternative is 964.5 acres, which is 14.1% larger than the Existing Conditions (2018) and 5.5% larger than the No Action (2023) alternative. The total area within the 10% contour of the Short Term (2019) alternative is 626.1 acres, which is slightly larger (2.1%) than the Existing Conditions (2018) alternative.

4.2 Probability of Awakening

The probability of awakening metric is usually applicable when nighttime operations are significant or of concern. The metric is based on the Sound Exposure Level (SEL) which measures the noise exposure for a single aircraft flyover. SEL may be considered an accumulation of the sound energy over the duration of an event. Therefore, it is used to assess the probability of awakening as it captures the total sound energy regardless of the total duration of the event. The Acoustical Society of America (ASA) and the American National Standards Institute (ANSI) published the ANSI/ASA S12.9-2008/Part 6, to project the probability of awakening as a result of the outdoor noise events^{ix}, which was also recommended by the DNWG^x. **Table 13** shows the probability of awakening at least once at night using the recommended number of events above 90 dB SEL based on the ANSI/ASA formula.

Table 13
**Probability of Awakening At Least Once from
 Multiple Events at SEL 90 dB**

NA90SEL	Windows Closed ¹	Windows Open ²
1	1%	2%
3	4%	6%
5	7%	10%
9	12%	18%
18	22%	33%
27	32%	45%


1: 'Windows Closed' assumes that there is a 25 dB noise level reduction (NLR) between the outdoors and indoors, e.g., 90 dB SEL outdoors is 65 dB SEL indoors.

2: 'Windows Open' assumes that there is a 15 dB NLR between the outdoors and indoors, e.g. 90 dB SEL outdoors is 75 dB SEL indoors.

Sources: DNWG Technical Bulletin, 2009.

The probability of awakening is evaluated for the Proposed Action (2023) alternatives which has the highest nighttime operations. The Existing Conditions (2018), Short Term (2019), and No Action (2023) are expected to have minimal to no nighttime operations and therefore were not evaluated using this metric. **Figure 13** shows the 5% and 10% contours of the probability of awakening at least once for the Proposed Action (2023). Due to the low number of nighttime operations, the 5% and 10% contours are expected to fall well within the airport property and no population would be included in the contours. Since the Proposed Action (2023) has the highest number of nighttime operations, the 5% and 10% contours for other alternatives are expected to be even smaller.


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND

- | | |
|---|--------------------------------------|
| Proposed Action (2023) Alternative Probability of Awakening at least once | Institutional |
| Commercial/Industrial | Transportation |
| Open/Agricultural/Recreational | Water |
| Public/Quasi-Public | WARB Installation Area |
| Residential | WMDC Aviation Property |
| Previously Acquired Property under the Voluntary Acquisition Program | County Boundary |
| Cemetery | Town Boundary |
| | Place of Worship |
| | School |
| | National Register of Historic Places |
| | Local Historic District |

Proposed Action (2023) Alternative Probability of Awakening Figure 13



Sources: Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services, WMDC 2019, HNTB GIS (2018), Aerial - USDA 2016, ESRI Data and HNTB Analysis

USDA-FSA-APFO

This technical memorandum presents the data sources, methodologies, and assumptions applied to develop the noise contours and supplemental metrics, as well as the presentation of noise contours and supplemental metrics, as well as their comparisons. If you have any questions or comments, please do not hesitate to send me an email yxu@hntb.com or call me at 703-253-5829.

Best Regards,

A handwritten signature in black ink, appearing to read 'Yue Xu', with a stylized flourish at the end.

Yue Xu, Ph.D., P.E.
Aviation/Environmental Planner
HNTB Corporation

Cc: Kim Hughes, HNTB
Caroline Pinegar, HNTB

ⁱ Air Installation Compatible Use Zone (AICUZ) Study, Westover Air Reserve Base, Massachusetts, United States Air Force, February 2013.

ⁱⁱ Interim Relocation of Two F-16 Squadrons – Environmental Assessment, Draft, U.S. Air Force, April 2017.

ⁱⁱⁱ Guidance on Using the Aviation Environmental Design Tool (AEDT) to Conduct Environmental Modeling for FAA Actions Subject to NEPA, FAA, revised Oct 27, 2017.

^{iv} Global Summary of the Day, Climate Data Online, National Centers for Environmental Information, National Oceanic and Atmospheric Administration, <https://www.ncdc.noaa.gov/cdo-web/datasets>, accessed April 2018.

^v Multi-Resolution Land Characteristics Consortium (MRLC), National Land Cover Database, U.S. Geological Survey, U.S. Department of Interior, <https://www.mrlc.gov/about.php>, accessed April 2018.

^{vi} Synthesis of Social Surveys on Noise Annoyance, Schultz, T.J., Journal of Acoustical Society of America, Volume 64, P377-405, 1978.

^{vii} Federal Interagency Committee on Noise (FICON). Federal Agency Review of Selected Airport Noise Analysis Issues, Report for the Department of Defense, Washington, DC, 1992.

^{viii} Noise Working Group Technical Bulletin, Community Annoyance Caused by Noise from Military Aircraft Operations, Department of Defense, December 2009.

^{ix} Quantities and Procedures for Description and Measurement of Environmental Sound - Part 6: Methods for Estimating of Awakenings Associated with Outdoor Noise Events Heard in Homes, ANSI/ASA S12.9-2008/Part 6, the Acoustical Society of America (ASA) and the American National Standards Institute (ANSI), 2008.

^x Noise Working Group Technical Bulletin, Using Supplemental Noise Metrics and Analysis Tools, Department of Defense, December 2009.

Appendix A – Detailed AEDT Aircraft and Operations

Table A-1
Existing Condition (2018) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	* Super Galaxy	C5-M	2.04	0.03	2.04	0.01	17.10	-	21.21
Military	JET	Boeing F-15 Eagle	F15A or F15E	0.28	-	0.28	-	-	-	0.56
Military	JET	Boeing Globemaster 3	C17	0.29	0.00	0.29	0.00	-	-	0.59
Military	JET	Boeing KC-135 Stratotanker	F15E	0.47	-	0.47	-	-	-	0.95
Military	JET	Boeing Raptor F22	F22	0.01	-	0.01	-	-	-	0.01
Military	JET	Boeing Sentry TF33/E3C	E3A	0.01	-	0.01	-	-	-	0.02
Military	JET	Extender	KC10A	0.28	-	0.28	-	-	-	0.55
Military	HEL	Boeing CH-47 Chinook	CH47D	2.12	-	2.12	-	2.19	-	6.43
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.68	-	4.68	-	2.19	-	11.56
Military	MET	Lockheed 130 Hercules	C130H&N&P	0.31	0.00	0.31	0.00	0.82	-	1.45
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.06
Civil	JET	Airbus A319	A319-131	0.02	-	0.02	-	-	-	0.03
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.05	-	0.05	-	-	-	0.10
Civil	JET	Boeing 737-400	737400	0.12	-	0.12	-	-	-	0.24
Civil	JET	Boeing 737-700	737700	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing 737-800	737800	0.04	-	0.04	-	-	-	0.09
Civil	JET	Boeing 757-200	757PW or 757RR	0.01	-	0.01	-	-	-	0.02
Civil	JET	Boeing P-8 Poseidon	737800	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier (Canadair) Challenger 300	CL600	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier Challenger 300	CL600	0.03	-	0.03	-	-	-	0.06
Civil	JET	Bombardier Challenger 600/601/604	CL600	0.10	-	0.10	-	-	-	0.21
Civil	JET	Bombardier CRJ-200	CL600	0.02	-	0.02	-	-	-	0.04

Table A-1
Existing Condition (2018) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	-	0.05	-	-	-	0.09
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	-	0.02	-	-	-	0.04
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	-	0.06	-	-	-	0.12
Civil	JET	Cessna 500/Citation I	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation CJ2	CNA500	0.07	-	0.07	-	-	-	0.13
Civil	JET	Cessna Citation CJ3	CNA500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	-	0.04	-	-	-	0.07
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation Sovereign	CNA680	0.06	-	0.06	-	-	-	0.13
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.08	-	0.08	-	-	-	0.17
Civil	JET	Cessna Citation X	CNA750	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.10	-	0.10	-	-	-	0.20
Civil	JET	Cessna Excel/XLS	CNA560XL	0.13	-	0.13	-	-	-	0.27
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Dassault Falcon 2000	CNA750	0.13	-	0.13	-	-	-	0.27
Civil	JET	Dassault Falcon 900	CNA750	0.02	-	0.02	-	-	-	0.04
Civil	JET	Dassault Falcon F7X	CNA750 or GIV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	-	0.12	-	-	-	0.23
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 190	EMB190	0.01	-	0.01	-	-	-	0.01

Table A-1
Existing Condition (2018) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	CNA55B	0.09	-	0.09	-	-	-	0.18
Civil	JET	Gulfstream	GV	0.02	-	0.02	-	-	-	0.05
Civil	JET	Gulfstream G280	IA1125	0.01	-	0.01	-	-	-	0.01
Civil	JET	Gulfstream IV/G400	GIV	0.29	-	0.29	-	-	-	0.58
Civil	JET	Gulfstream V/G500	GV	0.27	-	0.27	-	-	-	0.54
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	JET	Raytheon/Beech Beechjet 400/T-1	MU3001	0.05	-	0.05	-	-	-	0.11
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech 58	BEC58P	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech 76 Duchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Beech Baron 55	BEC58P	0.02	-	0.02	-	-	-	0.03
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus A400M Atlas	C-130E	0.01	-	0.01	-	-	-	0.02
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Beech 200 Super King	DHC6	0.88	-	0.88	-	-	-	1.76

Table A-1
Existing Condition (2018) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MET	Beech King Air 90	DHC6	0.03	-	0.03	-	-	-	0.05
Civil	MET	Beech Super King Air 350	DHC6	0.38	-	0.38	-	-	-	0.76
Civil	MET	CASA CN-235	SF340	0.05	-	0.05	-	-	-	0.10
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Raytheon 300 Super King Air	DHC6	0.07	-	0.07	-	-	-	0.13
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American AA-5 Traveler	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza 33	GASEPV	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Beech Bonanza 35	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza 36	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna 177 Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna 206 Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna 210 Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Cessna Skyhawk 172/Cutlass	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Skylane 182	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Diamond Star DA40	COMSEP	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05

Table A-1

Existing Condition (2018) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Pilatus PC-12	CNA208	0.43	-	0.43	-	-	-	0.85
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Raytheon Texan 2	GASEPF	0.01	-	0.01	-	-	-	0.02
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Total				15.89	0.03	15.89	0.01	22.30	-	54.12

Table A-2
No Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	* Super Galaxy	C5A	2.08	0.03	2.08	0.01	17.81	-	22.01
Military	JET	Boeing F-15 Eagle	F15A or F15E	0.30	-	0.30	-	-	-	0.60
Military	JET	Boeing Globemaster	C17	0.30	0.00	0.30	0.00	-	-	0.61
Military	JET	Boeing KC-135 Stratotanker	KC-135R	0.49	-	0.49	-	-	-	0.99
Military	JET	Boeing Raptor F22	F22	0.01	-	0.01	-	-	-	0.02
Military	JET	Boeing Sentry TF33/E3C	E3A	0.02	-	0.02	-	-	-	0.03
Military	JET	Extender	KC10A	0.29	-	0.29	-	-	-	0.58
Military	HEL	Boeing CH-47 Chinook	CH47D	2.16	-	2.16	-	2.19	-	6.52
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.71	-	4.71	-	2.19	-	11.62
Military	MET	Lockheed Hercules	C130HP	0.33	0.00	0.33	0.00	1.10	-	1.76
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.07
Civil	JET	Airbus	A319-131	0.02	-	0.02	-	-	-	0.03
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing	737400	0.14	-	0.14	-	-	-	0.27
Civil	JET	Boeing	737700	0.04	-	0.04	-	-	-	0.08
Civil	JET	Boeing	737800	0.51	-	0.51	-	-	-	1.01
Civil	JET	Boeing	757PW or 757RR	0.02	-	0.02	-	-	-	0.03
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.07	-	0.07	-	-	-	0.14
Civil	JET	Boeing P-8 Poseidon	737800	0.10	-	0.10	-	-	-	0.19
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier Challenger	CL600	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier Challenger	CL600	0.03	-	0.03	-	-	-	0.06
Civil	JET	Bombardier Challenger	CL600	0.10	-	0.10	-	-	-	0.21
Civil	JET	Bombardier CRJ-200	CL600	0.02	-	0.02	-	-	-	0.04

Table A-2
No Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Bombardier Global 7000	BD-700-1A10 or BD-700-1A11	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	-	0.05	-	-	-	0.09
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	-	0.02	-	-	-	0.04
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	-	0.06	-	-	-	0.12
Civil	JET	Cessna 500/Citation I	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation CJ2	CNA500	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna Citation CJ3	CNA500	0.05	-	0.05	-	-	-	0.11
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	-	0.04	-	-	-	0.08
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation Sovereign	CNA680	0.07	-	0.07	-	-	-	0.14
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.10	-	0.10	-	-	-	0.19
Civil	JET	Cessna Citation X	CNA750	0.08	-	0.08	-	-	-	0.16
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.11	-	0.11	-	-	-	0.22
Civil	JET	Cessna Excel/XLS	CNA560XL	0.14	-	0.14	-	-	-	0.27
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	-	0.12	-	-	-	0.23
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 190	EMB190	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01

Table A-2
No Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Embraer Phenom 300	CNA55B	0.07	-	0.07	-	-	-	0.14
Civil	JET	Falcon 2000	CNA750	0.14	-	0.14	-	-	-	0.27
Civil	JET	Falcon 7X	CNA750 or GIV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Falcon 900LX	CNA750	0.02	-	0.02	-	-	-	0.04
Civil	JET	Gulfstream 280	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Gulfstream 550	GV	0.27	-	0.27	-	-	-	0.55
Civil	JET	Gulfstream 650	GV	0.03	-	0.03	-	-	-	0.05
Civil	JET	Gulfstream IV/G400	GIV	0.29	-	0.29	-	-	-	0.58
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	JET	Pilatus PC-24	CNA55B	0.07	-	0.07	-	-	-	0.14
Civil	JET	Raytheon Beechjet	MU3001	0.07	-	0.07	-	-	-	0.14
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech 58	BEC58P	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech Baron	BEC58P	0.03	-	0.03	-	-	-	0.05
Civil	MEP	Beech Dutchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus	C-130E	0.01	-	0.01	-	-	-	0.02

Table A-2
No Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Beech King Air 90	DHC6	0.03	-	0.03	-	-	-	0.05
Civil	MET	CASA CN-235	SF340	0.05	-	0.05	-	-	-	0.10
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Raytheon Beech King Air	DHC6	0.38	-	0.38	-	-	-	0.77
Civil	MET	Raytheon Beech King Air	DHC6	0.89	-	0.89	-	-	-	1.78
Civil	MET	Raytheon Super King Air	DHC6	0.08	-	0.08	-	-	-	0.16
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza	GASEPV	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Cessna Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Skyhawk	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Skylane	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cessna Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Diamond Star DA40	GASEPV	0.00	-	0.00	-	-	-	0.01

Table A-2

No Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Pilatus PC-12	CNA208	0.44	-	0.44	-	-	-	0.88
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Raytheon Texan 2	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Total				16.85	0.03	16.85	0.01	23.29	-	57.03

Table A-3

Proposed Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	Boeing F-15 Eagle	GV	0.30	-	0.30	-	-	-	0.60
Military	JET	Boeing Globemaster	CL600	0.30	0.01	0.30	0.01	-	-	0.62
Military	JET	Boeing KC-135 Stratotanker	SF340	0.49	-	0.49	-	-	-	0.99
Military	JET	Boeing Raptor F22	GV	0.01	-	0.01	-	-	-	0.02
Military	JET	Boeing Sentry TF33/E3C	GIV	0.02	-	0.02	-	-	-	0.03
Military	JET	Extender	CNA441	0.29	-	0.29	-	-	-	0.58
Military	JET	Super Galaxy	CNA750	2.08	0.03	2.08	0.03	17.81	-	22.04
Military	HEL	Boeing CH-47 Chinook	C-130E	2.16	-	2.16	-	2.19	-	6.52
Military	HEL	Sikorsky SH-60 Seahawk	DHC6	4.71	-	4.71	-	2.19	-	11.62
Military	MET	Lockheed Hercules	737800	0.33	0.01	0.33	0.01	1.10	-	1.78
Military	SEP	Lockheed P-3C Orion	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	JET	Airbus	F15A or F15E	-	0.04	-	0.04	-	-	0.09
Civil	JET	Airbus	C17	0.02	0.04	0.02	0.04	-	-	0.12
Civil	JET	Airbus	KC-135R	-	0.04	-	0.04	-	-	0.09
Civil	JET	BAe HS 125/700-800/Hawker 800	BEC58P	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	PA30	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing	CH47D	0.14	-	0.14	-	-	-	0.27
Civil	JET	Boeing	S70	0.04	-	0.04	-	-	-	0.08
Civil	JET	Boeing	C130HP	-	0.04	-	0.04	-	-	0.09
Civil	JET	Boeing	P3A or P3C	0.51	-	0.51	-	-	-	1.01
Civil	JET	Boeing	A319-131	-	0.04	-	0.04	-	-	0.09
Civil	JET	Boeing	A319-131	0.02	-	0.02	-	-	-	0.03
Civil	JET	Boeing (Douglas) DC 10-10/30/40	CNA55B	0.07	-	0.07	-	-	-	0.14
Civil	JET	Boeing 767-300	A321-232	-	0.04	-	0.04	-	-	0.09
Civil	JET	Boeing P-8 Poseidon	GASEPV	0.10	-	0.10	-	-	-	0.19
Civil	JET	Bombardier BD-700 Global 5000	BEC58P	0.01	0.09	0.01	0.09	-	-	0.19

Table A-3

Proposed Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Bombardier Challenger	ECLIPSE500	0.06	0.04	0.06	0.04	-	-	0.20
Civil	JET	Bombardier Challenger	CNA55B	0.03	0.03	0.03	0.03	-	-	0.13
Civil	JET	Bombardier Challenger	EMB145	0.10	0.13	0.10	0.13	-	-	0.47
Civil	JET	Bombardier CRJ-200	EMB145	0.02	0.01	0.02	0.01	-	-	0.05
Civil	JET	Bombardier Global 7000	BEC58P	0.01	0.09	0.01	0.09	-	-	0.19
Civil	JET	Bombardier Learjet 31/A/B	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	CNA441	0.01	0.01	0.01	0.01	-	-	0.03
Civil	JET	Bombardier Learjet 45	DHC6	0.05	0.01	0.05	0.01	-	-	0.10
Civil	JET	Bombardier Learjet 55	DHC6	0.02	0.01	0.02	0.01	-	-	0.06
Civil	JET	Bombardier Learjet 60	DHC6	0.06	0.02	0.06	0.02	-	-	0.16
Civil	JET	Cessna 500/Citation I	CNA525C	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation CJ2	LEAR35	0.07	0.03	0.07	0.03	-	-	0.19
Civil	JET	Cessna Citation CJ3	LEAR35	0.05	0.02	0.05	0.02	-	-	0.15
Civil	JET	Cessna Citation CJ4	LEAR35	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation II/Bravo	CNA680	0.04	0.01	0.04	0.01	-	-	0.10
Civil	JET	Cessna Citation Latitude	CIT3	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation Sovereign	CNA560XL	0.07	0.01	0.07	0.01	-	-	0.16
Civil	JET	Cessna Citation V/Ultra/Encore	CNA680	0.10	0.02	0.10	0.02	-	-	0.24
Civil	JET	Cessna Citation X	FAL20	0.08	0.02	0.08	0.02	-	-	0.21
Civil	JET	Cessna CitationJet/CJ1	CNA55B	0.11	0.04	0.11	0.04	-	-	0.31
Civil	JET	Cessna Excel/XLS	CNA560U or CNA55B or CNA560E	0.14	0.02	0.14	0.02	-	-	0.32
Civil	JET	Cessna III/VI/VII	CNA500	0.02	-	0.02	-	-	-	0.03
Civil	JET	Dassault Falcon/Mystère 20	LEAR35	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	SABR80	0.12	-	0.12	-	-	-	0.23
Civil	JET	Eclipse 500	GV	0.04	-	0.04	-	-	-	0.09
Civil	JET	Eclipse 550	IA1125	0.01	-	0.01	-	-	-	0.01

Table A-3

Proposed Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Embraer 135 LR/ Legacy 600	CNA750 or GIV	0.01	0.11	0.01	0.11	-	-	0.23
Civil	JET	Embraer 190	CNA750	0.01	0.11	0.01	0.11	-	-	0.24
Civil	JET	Embraer ERJ-145	CNA750	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer Phenom 100	CNA750	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	IA1125	0.07	0.19	0.07	0.19	-	-	0.52
Civil	JET	Falcon 2000	GIV	0.14	0.19	0.14	0.19	-	-	0.66
Civil	JET	Falcon 5X	T-38A	-	0.22	-	0.22	-	-	0.44
Civil	JET	Falcon 7X	CNA55B	0.01	0.22	0.01	0.22	-	-	0.46
Civil	JET	Falcon 8X	MU3001	-	0.18	-	0.18	-	-	0.36
Civil	JET	Falcon 900LX	IA1125	0.02	0.18	0.02	0.18	-	-	0.39
Civil	JET	Gulfstream 150	H500D or SC300C	-	0.20	-	0.20	-	-	0.39
Civil	JET	Gulfstream 280	S76	0.01	0.20	0.01	0.20	-	-	0.42
Civil	JET	Gulfstream 500	BEC58P	-	0.11	-	0.11	-	-	0.22
Civil	JET	Gulfstream 550	BEC58P	0.27	0.20	0.27	0.20	-	-	0.94
Civil	JET	Gulfstream 650	BEC58P	0.03	0.20	0.03	0.20	-	-	0.45
Civil	JET	Gulfstream IV/G400	BEC58P	0.29	-	0.29	-	-	-	0.58
Civil	JET	IAI Astra 1125	KC10A	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	CNA441	0.01	0.01	0.01	0.01	-	-	0.04
Civil	JET	North American Rockwell Sabre 40/60	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	JET	Pilatus PC-24	GASEPV	0.07	0.34	0.07	0.34	-	-	0.82
Civil	JET	Raytheon Beechjet	737800	0.07	-	0.07	-	-	-	0.14
Civil	HEL	Hughes 269	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	GASEPF or PA28	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech 58	757PW or 757RR	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech Baron	737800	0.03	-	0.03	-	-	-	0.05

Table A-3

Proposed Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MEP	Beech Dutchess	DC1010 or DC1030 or DC1040	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Cessna 310	LEAR35 or CNA750	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	CNA500	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	CNA182	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-30	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-34 Seneca	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus	F22	0.01	-	0.01	-	-	-	0.02
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Beech King Air 90	767300	0.03	-	0.03	-	-	-	0.05
Civil	MET	CASA CN-235	EMB190	0.05	-	0.05	-	-	-	0.10
Civil	MET	Cessna Conquest	CNA500	0.01	-	0.01	-	-	-	0.02
Civil	MET	Piaggio P-180 Avanti	CNA208	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	COMSEP	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	GASEPV	0.02	-	0.02	-	-	-	0.03
Civil	MET	Raytheon Beech King Air	C5A	0.38	-	0.38	-	-	-	0.77
Civil	MET	Raytheon Beech King Air	LEAR35	0.89	-	0.89	-	-	-	1.78
Civil	MET	Raytheon Super King Air	LEAR35	0.08	-	0.08	-	-	-	0.16
Civil	MET	Swearingen Merlin 4/4A Metro2	CNA208	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American	E3A	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza	737400	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	737700	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	737700	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	GV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal	CL600	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna Cardinal RG	CNA750	0.01	-	0.01	-	-	-	0.01

Table A-3

Proposed Action (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Cessna Centurion	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Skyhawk	CL600	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Skylane	CL600	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cessna Stationair	BD-700-1A10 or BD-700-1A11	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cirrus SR 22	GASEPV	0.19	-	0.19	-	-	-	0.38
Civil	SEP	Cirrus SR-20	GASEPV	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR-22 Turbo	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Diamond Star DA40	CNA510	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPF	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Piper Aztec	GASEPV	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Cherokee Six	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	COMSEP	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Pilatus PC-12	GASEPV	0.44	0.41	0.44	0.41	-	-	1.70
Civil	SET	Piper Malibu Meridian	CNA172	0.01	-	0.01	-	-	-	0.03
Civil	SET	Raytheon Texan 2	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	SET	Socata TBM-850	GASEPV	0.02	-	0.02	-	-	-	0.04
Total				16.85	3.98	16.85	3.98	23.29	-	64.95

Table A-4
Short Term (2019) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	* Super Galaxy	C5A	2.04	0.03	2.04	0.03	17.10	-	21.23
Military	JET	Boeing F-15 Eagle	F15A or F15E	0.28	-	0.28	-	-	-	0.56
Military	JET	Boeing Globemaster 3	C17	0.29	0.00	0.29	0.00	-	-	0.59
Military	JET	Boeing KC-135 Stratotanker	KC-135R	0.47	-	0.47	-	-	-	0.95
Military	JET	Boeing Raptor F22	F22	0.01	-	0.01	-	-	-	0.01
Military	JET	Boeing Sentry TF33/E3C	E3A	0.01	-	0.01	-	-	-	0.02
Military	JET	Extender	KC10A	0.28	-	0.28	-	-	-	0.55
Military	HEL	Boeing CH-47 Chinook	CH47D	2.12	-	2.12	-	2.19	-	6.43
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.68	-	4.68	-	2.19	-	11.56
Military	MET	Lockheed 130 Hercules	C130HP	0.31	0.00	0.31	0.00	0.82	-	1.45
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.06
Civil	JET	Airbus A319	A319-131	0.02	0.00	0.02	0.00	-	-	0.04
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	0.02	0.21	0.02	-	-	0.47
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	0.01	0.04	0.01	-	-	0.08
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.05	-	0.05	-	-	-	0.10
Civil	JET	Boeing 737-400	737400	0.12	0.03	0.12	0.03	-	-	0.30
Civil	JET	Boeing 737-700	737700	0.04	0.00	0.04	0.00	-	-	0.08
Civil	JET	Boeing 737-800	737800	0.04	0.00	0.04	0.00	-	-	0.09
Civil	JET	Boeing 757-200	757PW or 757RR	0.01	-	0.01	-	-	-	0.02
Civil	JET	Boeing P-8 Poseidon	737800	0.06	-	0.06	-	-	-	0.12
Civil	JET	Bombardier (Canadair) Challenger 300	CL600	0.06	0.01	0.06	0.01	-	-	0.13
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	-	0.01	-	-	-	0.01
Civil	JET	Bombardier Challenger 300	CL600	0.03	0.00	0.03	0.00	-	-	0.07
Civil	JET	Bombardier Challenger 600/601/604	CL600	0.10	0.01	0.10	0.01	-	-	0.23
Civil	JET	Bombardier CRJ-200	CL600	0.02	-	0.02	-	-	-	0.04

Table A-4
Short Term (2019) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	-	0.01	-	-	-	0.02
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	0.00	0.05	0.00	-	-	0.10
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	-	0.02	-	-	-	0.04
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	0.01	0.06	0.01	-	-	0.13
Civil	JET	Cessna 500/Citation I	CNA500	0.01	0.01	0.01	0.01	-	-	0.02
Civil	JET	Cessna Citation CJ2	CNA500	0.07	0.01	0.07	0.01	-	-	0.15
Civil	JET	Cessna Citation CJ3	CNA500	0.04	0.01	0.04	0.01	-	-	0.10
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	0.01	0.02	0.01	-	-	0.04
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	0.00	0.04	0.00	-	-	0.08
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation Sovereign	CNA680	0.06	0.01	0.06	0.01	-	-	0.14
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.08	0.02	0.08	0.02	-	-	0.20
Civil	JET	Cessna Citation X	CNA750	0.07	0.01	0.07	0.01	-	-	0.15
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.10	0.02	0.10	0.02	-	-	0.23
Civil	JET	Cessna Excel/XLS	CNA560XL	0.13	0.02	0.13	0.02	-	-	0.31
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Dassault Falcon 2000	CNA750	0.13	0.02	0.13	0.02	-	-	0.30
Civil	JET	Dassault Falcon 900	CNA750	0.02	-	0.02	-	-	-	0.04
Civil	JET	Dassault Falcon F7X	CNA750 or GIV	0.01	-	0.01	-	-	-	0.02
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	0.02	0.12	0.02	-	-	0.26
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 190	EMB190	0.01	-	0.01	-	-	-	0.01

Table A-4
Short Term (2019) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	CNA55B	0.09	0.01	0.09	0.01	-	-	0.20
Civil	JET	Gulfstream	GV	0.02	-	0.02	-	-	-	0.05
Civil	JET	Gulfstream G280	IA1125	0.01	-	0.01	-	-	-	0.01
Civil	JET	Gulfstream IV/G400	GIV	0.29	0.03	0.29	0.03	-	-	0.64
Civil	JET	Gulfstream V/G500	GV	0.27	0.03	0.27	0.03	-	-	0.60
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	JET	Raytheon/Beech Beechjet 400/T-1	MU3001	0.05	0.00	0.05	0.00	-	-	0.12
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Beech 58	BEC58P	0.09	0.00	0.09	0.00	-	-	0.19
Civil	MEP	Beech 76 Duchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Beech Baron 55	BEC58P	0.02	-	0.02	-	-	-	0.03
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus A400M Atlas	C-130E	0.01	-	0.01	-	-	-	0.02
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Beech 200 Super King	DHC6	0.88	0.14	0.88	0.14	-	-	2.04

Table A-4
Short Term (2019) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MET	Beech King Air 90	DHC6	0.03	0.01	0.03	0.01	-	-	0.07
Civil	MET	Beech Super King Air 350	DHC6	0.38	0.11	0.38	0.11	-	-	0.98
Civil	MET	CASA CN-235	SF340	0.05	0.00	0.05	0.00	-	-	0.10
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Raytheon 300 Super King Air	DHC6	0.07	0.01	0.07	0.01	-	-	0.14
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American AA-5 Traveler	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza 33	GASEPV	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Beech Bonanza 35	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza 36	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna 177 Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna 206 Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna 210 Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Cessna Skyhawk 172/Cutlass	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Skylane 182	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Diamond Star DA40	COMSEP	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05

Table A-4
Short Term (2019) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Pilatus PC-12	CNA208	0.43	0.07	0.43	0.07	-	-	0.99
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Raytheon Texan 2	GASEPF	0.01	-	0.01	-	-	-	0.02
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Total				15.89	0.65	15.89	0.65	22.30	-	55.38

Table A-5
Low GA Operations (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Military	JET	Boeing F-15 Eagle	F15A or F15E	0.30	-	0.30	-	-	-	0.60
Military	JET	Boeing Globemaster	C17	0.30	0.01	0.30	0.01	-	-	0.61
Military	JET	Boeing KC-135 Stratotanker	KC-135R	0.49	-	0.49	-	-	-	0.99
Military	JET	Boeing Raptor F22	F15E29	0.01	-	0.01	-	-	-	0.02
Military	JET	Boeing Sentry TF33/E3C	E3A	0.02	-	0.02	-	-	-	0.03
Military	JET	Extender	KC10A	0.29	-	0.29	-	-	-	0.58
Military	JET	Super Galaxy	C5A	2.08	0.03	2.08	0.03	17.81	-	22.04
Military	HEL	Boeing CH-47 Chinook	CH47D	2.16	-	2.16	-	2.19	-	6.52
Military	HEL	Sikorsky SH-60 Seahawk	S70	4.71	-	4.71	-	2.19	-	11.62
Military	MET	Lockheed Hercules	C130HP	0.33	0.01	0.33	0.01	1.10	-	1.76
Military	SEP	Lockheed P-3C Orion	P3A or P3C	0.03	-	0.03	-	-	-	0.07
Civil	JET	Airbus	A319-131	-	0.02	-	0.02	-	-	0.04
Civil	JET	Airbus	A319-131	0.02	0.02	0.02	0.02	-	-	0.08
Civil	JET	Airbus	A321-232	-	0.02	-	0.02	-	-	0.04
Civil	JET	BAe HS 125/700-800/Hawker 800	LEAR35	0.21	-	0.21	-	-	-	0.43
Civil	JET	BAe/Raytheon HS 125-1000/Hawker 1000	LEAR35	0.04	-	0.04	-	-	-	0.07
Civil	JET	Boeing	737400	0.14	-	0.14	-	-	-	0.27
Civil	JET	Boeing	737700	0.04	-	0.04	-	-	-	0.08
Civil	JET	Boeing	737700	-	0.02	-	0.02	-	-	0.04
Civil	JET	Boeing	737800	0.51	-	0.51	-	-	-	1.01
Civil	JET	Boeing	737800	-	0.02	-	0.02	-	-	0.04
Civil	JET	Boeing	757PW or 757RR	0.02	-	0.02	-	-	-	0.03
Civil	JET	Boeing (Douglas) DC 10-10/30/40	DC1010 or DC1030 or DC1040	0.07	-	0.07	-	-	-	0.14
Civil	JET	Boeing 767-300	767300	-	0.02	-	0.02	-	-	0.04
Civil	JET	Boeing P-8 Poseidon	737800	0.10	-	0.10	-	-	-	0.19

Table A-5
Low GA Operations (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Bombardier BD-700 Global 5000	GV	0.01	0.04	0.01	0.04	-	-	0.09
Civil	JET	Bombardier Challenger	CL600	0.06	0.02	0.06	0.02	-	-	0.16
Civil	JET	Bombardier Challenger	CL600	0.03	0.02	0.03	0.02	-	-	0.09
Civil	JET	Bombardier Challenger	CL600	0.10	0.05	0.10	0.05	-	-	0.32
Civil	JET	Bombardier CRJ-200	CL600	0.02	0.00	0.02	0.01	-	-	0.05
Civil	JET	Bombardier Global 7000	BD-700-1A10 or BD-700-1A11	0.01	0.04	0.01	0.04	-	-	0.10
Civil	JET	Bombardier Learjet 31/A/B	LEAR35	0.01	-	0.01	-	-	-	0.03
Civil	JET	Bombardier Learjet 35/36	LEAR35	0.01	0.00	0.01	0.01	-	-	0.02
Civil	JET	Bombardier Learjet 45	LEAR35	0.05	0.00	0.05	0.01	-	-	0.10
Civil	JET	Bombardier Learjet 55	LEAR35	0.02	0.01	0.02	0.01	-	-	0.05
Civil	JET	Bombardier Learjet 60	LEAR35 or CNA750	0.06	0.01	0.06	0.02	-	-	0.15
Civil	JET	Cessna 500/Citation I	CNA500	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation CJ2	CNA500	0.07	0.01	0.07	0.01	-	-	0.16
Civil	JET	Cessna Citation CJ3	CNA500	0.05	0.01	0.05	0.01	-	-	0.13
Civil	JET	Cessna Citation CJ4	CNA525C	0.02	-	0.02	-	-	-	0.03
Civil	JET	Cessna Citation II/Bravo	CNA55B	0.04	0.01	0.04	0.01	-	-	0.09
Civil	JET	Cessna Citation Latitude	CNA680	0.01	-	0.01	-	-	-	0.01
Civil	JET	Cessna Citation Sovereign	CNA680	0.07	0.01	0.07	0.01	-	-	0.15
Civil	JET	Cessna Citation V/Ultra/Encore	CNA560U or CNA55B or CNA560E	0.10	0.01	0.10	0.01	-	-	0.21
Civil	JET	Cessna Citation X	CNA750	0.08	0.01	0.08	0.01	-	-	0.19
Civil	JET	Cessna CitationJet/CJ1	CNA500	0.11	0.02	0.11	0.02	-	-	0.26
Civil	JET	Cessna Excel/XLS	CNA560XL	0.14	0.01	0.14	0.01	-	-	0.30
Civil	JET	Cessna III/VI/VII	CIT3	0.02	-	0.02	-	-	-	0.03
Civil	JET	Dassault Falcon/Mystère 20	FAL20	0.01	-	0.01	-	-	-	0.01
Civil	JET	Dassault Falcon/Mystère 50	CNA750	0.12	-	0.12	-	-	-	0.23
Civil	JET	Eclipse 500	ECLIPSE500	0.04	-	0.04	-	-	-	0.09

Table A-5
Low GA Operations (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	JET	Eclipse 550	CNA55B	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 135 LR	EMB145	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer 190	EMB190	0.01	0.05	0.01	0.05	-	-	0.12
Civil	JET	Embraer ERJ-145	EMB145	0.01	-	0.01	-	-	-	0.02
Civil	JET	Embraer Legacy 600	EMB145	-	0.05	-	0.05	-	-	0.10
Civil	JET	Embraer Phenom 100	CNA510	0.01	-	0.01	-	-	-	0.01
Civil	JET	Embraer Phenom 300	CNA55B	0.07	0.08	0.07	0.08	-	-	0.30
Civil	JET	Falcon 2000	CNA750	0.14	0.08	0.14	0.08	-	-	0.44
Civil	JET	Falcon 5X	CNA750	-	0.10	-	0.10	-	-	0.21
Civil	JET	Falcon 7X	CNA750 or GIV	0.01	0.11	0.01	0.11	-	-	0.24
Civil	JET	Falcon 8X	GIV	-	0.08	-	0.08	-	-	0.16
Civil	JET	Falcon 900LX	CNA750	0.02	0.09	0.02	0.09	-	-	0.22
Civil	JET	Gulfstream 150	IA1125	-	0.09	-	0.09	-	-	0.19
Civil	JET	Gulfstream 280	IA1125	0.01	0.09	0.01	0.09	-	-	0.21
Civil	JET	Gulfstream 500	GV	-	0.05	-	0.05	-	-	0.11
Civil	JET	Gulfstream 550	GV	0.27	0.08	0.27	0.08	-	-	0.71
Civil	JET	Gulfstream 650	GV	0.03	0.08	0.03	0.08	-	-	0.22
Civil	JET	Gulfstream IV/G400	GIV	0.29	-	0.29	-	-	-	0.58
Civil	JET	IAI Astra 1125	IA1125	0.01	-	0.01	-	-	-	0.02
Civil	JET	Learjet 40; Gates Learjet	LEAR35	0.01	0.00	0.01	0.01	-	-	0.04
Civil	JET	North American Rockwell Sabre 40/60	SABR80	0.01	-	0.01	-	-	-	0.02
Civil	JET	Northrop T-38 Talon	T-38A	0.01	-	0.01	-	-	-	0.02
Civil	JET	Pilatus PC-24	CNA55B	0.07	0.16	0.07	0.16	-	-	0.47
Civil	JET	Raytheon Beechjet	MU3001	0.07	-	0.07	-	-	-	0.14
Civil	HEL	Hughes 269	H500D or SC300C	0.01	-	0.01	-	-	-	0.02
Civil	HEL	Sikorsky S-76	S76	0.01	-	0.01	-	-	-	0.02

Table A-5
Low GA Operations (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	MEP	Beech 58	BEC58P	0.09	-	0.09	-	-	-	0.18
Civil	MEP	Beech Baron	BEC58P	0.03	-	0.03	-	-	-	0.05
Civil	MEP	Beech Dutchess	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	MEP	Cessna 310	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Cessna 340	BEC58P	0.01	-	0.01	-	-	-	0.01
Civil	MEP	Cessna Golden Eagle 421	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MEP	PA31 - Piper Navajo PA-31	BEC58P	0.02	-	0.02	-	-	-	0.04
Civil	MEP	Piper PA-30	PA30	0.01	-	0.01	-	-	-	0.02
Civil	MEP	Piper PA-34 Seneca	BEC58P	0.01	-	0.01	-	-	-	0.02
Civil	MET	Airbus	C-130E	0.01	-	0.01	-	-	-	0.02
Civil	MET	BAe-3100 Jetstream	DHC6	0.01	-	0.01	-	-	-	0.01
Civil	MET	Beech King Air 90	DHC6	0.03	-	0.03	-	-	-	0.05
Civil	MET	CASA CN-235	SF340	0.05	-	0.05	-	-	-	0.10
Civil	MET	Cessna Conquest	CNA441	0.01	-	0.01	-	-	-	0.02
Civil	MET	Piaggio P-180 Avanti	DHC6	0.01	-	0.01	-	-	-	0.03
Civil	MET	Piper Cheyenne 1	CNA441	0.01	-	0.01	-	-	-	0.01
Civil	MET	Piper Cheyenne 2	CNA441	0.02	-	0.02	-	-	-	0.03
Civil	MET	Raytheon Beech King Air	DHC6	0.38	-	0.38	-	-	-	0.77
Civil	MET	Raytheon Beech King Air	DHC6	0.89	-	0.89	-	-	-	1.78
Civil	MET	Raytheon Super King Air	DHC6	0.08	-	0.08	-	-	-	0.16
Civil	MET	Swearingen Merlin 4/4A Metro2	DHC6	0.01	-	0.01	-	-	-	0.02
Civil	SEP	American	GASEPF	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Beech Bonanza	GASEPV	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.04
Civil	SEP	Beech Bonanza	CNA208	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cessna 150	CNA172	0.01	-	0.01	-	-	-	0.02

Table A-5
Low GA Operations (2023) Average Annual Day Fleet Mix

Civil / Military	Category	Aircraft Name	AEDT/NOISEMAP Aircraft	AAD Arrivals		AAD Departures		AAD Closed Pattern		AAD Total
				Day	Night	Day	Night	Day	Night	
Civil	SEP	Cessna Cardinal	CNA172	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Cessna Cardinal RG	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Cessna Centurion	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cessna Skyhawk	CNA172	0.03	-	0.03	-	-	-	0.07
Civil	SEP	Cessna Skylane	CNA182	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Cessna Stationair	CNA206	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Cirrus SR 22	COMSEP	0.19	-	0.19	-	-	-	0.38
Civil	SEP	Cirrus SR-20	COMSEP	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Cirrus SR-22 Turbo	COMSEP	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Diamond Star DA40	GASEPV	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.01	-	0.01	-	-	-	0.01
Civil	SEP	Mooney M-20C Ranger	GASEPV	0.03	-	0.03	-	-	-	0.05
Civil	SEP	Piper Aztec	BEC58P	0.00	-	0.00	-	-	-	0.01
Civil	SEP	Piper Cherokee	GASEPF or PA28	0.02	-	0.02	-	-	-	0.03
Civil	SEP	Piper Cherokee Six	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SEP	Piper Malibu	GASEPV	0.04	-	0.04	-	-	-	0.09
Civil	SEP	Turbo Mooney M20K	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Pilatus PC-12	CNA208	0.44	0.21	0.44	0.21	-	-	1.29
Civil	SET	Piper Malibu Meridian	CNA441	0.01	-	0.01	-	-	-	0.03
Civil	SET	Raytheon Texan 2	GASEPV	0.01	-	0.01	-	-	-	0.02
Civil	SET	Socata TBM-850	CNA441	0.02	-	0.02	-	-	-	0.04
Total				16.85	1.89	16.85	1.92	23.29	-	60.79

Appendix B - AEE Coordination

MEMORANDUM



To
Richard Doucette
Environmental Program Manager
New England Region
Federal Aviation Administration
12 New England Executive Park
Burlington, MA 01803

From
Yue Xu, HNTB

Cc
Gordon Hutchinson, WMDC
Ervin Deck, Stantec
Randall Christensen, Stantec
Kim Hughes, HNTB

Subject
Request for Non-standard Substitution
Aircraft and Weather Parameters for
Westover Air Reserve/Metropolitan Airport
Noise Exposure Map Update and EA

Date
April 19, 2018

The Westover Metropolitan Development Corporation (WMDC) has initiated a Part 150 Update and an Environmental Assessment (EA) for Westover Air Reserve Base (WARB)/Metropolitan Airport (CEF), with the assistance of Stantec Consulting Services and HNTB Corporation. The WMDC oversees civilian operations at CEF which is currently open 16 hours per day. The Airport is also home to the Massachusetts Air Force Reserve 439th Airlift Wing, which previously operated Lockheed C-5A Galaxy aircraft and has upgraded to the C-5M Super Galaxy. The Part 150 Update is being prepared to assess the impacts of the C-5M Super Galaxy fleet upgrade. The WMDC has proposed to extend CEF operating hours to 24 hours per day and the EA is being prepared to assess the potential environmental impacts of this proposed change in operating hours.

HNTB is preparing noise exposure contours representative of existing conditions in 2018 and forecast conditions in 2023 using the Aviation Environmental Design Tool (AEDT) 2d and NOISEMAP Version 7.363 for both the Part 150 Update and EA. Four aircraft identified in the existing and forecast fleet mixes do not have direct AEDT type or pre-approved AEDT substitutions, as shown in **Table 1**. This request is in accordance with the required protocol to obtain approval of non-standard aircraft substitution related to AEDT¹.

¹ *Guidance on Using the Aviation Environmental Design Tool (AEDT) to Conduct Environmental Modeling for FAA Actions Subject to NEPA*, FAA, October 27, 2017.

Table 1
Non-standard AEDT Aircraft Substitution for Westover Part 150/EA

Aircraft Code	Aircraft Description	AEDT Model / Substitution Model	Recommended EQUIP_ID	ANP_ID	BADA_ID
BE35	Beech Bonanza 35	Raytheon Beech Bonanza 36	1276	CNA208	TBM8
DA40	Diamond Star DA40	EADS Socata TB-10 Tobago	1904	GASEPV	TB21
F22	Boeing Raptor F22	Boeing F-15E Strike Eagle	4235	F15E29	FGTN
S22T	Cirrus SR-22 Turbo	Cirrus SR22	1325	COMSEP	SR22

Sources: Westover Air Traffic Control Tower and HNTB analysis, 2018.

BE35 – Beech Bonanza 35

The Beech Bonanza 35 is a single-engine general aviation aircraft powered by a Continental E-185-1 engine (185 hp) with an MTOW of 3,400 lbs. HNTB recommends using the Raytheon Beech Bonanza 36 (AEDT Equipment ID = 1276, ANP Code = CNA208, and BADA ID = TBM8) as a substitute. The Raytheon Beech Bonanza 36 is a single-engine aircraft powered by a Continental IO-550-B engine (300 hp) with an MTOW of 3,650 lbs.

DA40 - Diamond Star DA40

The Diamond Star DA40 is a low-wing, single-engine piston aircraft with an MTOW of 2,535 lbs. It is powered by a Lycoming IO-360-M1A engine producing 180 hp. The Diamond DA40 has a two or three-blade, constant speed variable pitch propeller. HNTB recommends using the EADS Socata TB-10 Tobago (AEDT Equipment ID = 1904, ANP Code = GASEPV, and BADA ID = TB21) as a substitute. The ADS Socata TB-10 Tobago has a MTOW of 2,530 lbs. and is powered by a Lycoming O-360-A1AD engine producing 180 hp. The ADS Socata TB-10 Tobago and Diamond Star DA40 have similar engines and MTOWs.

F22 – Boeing Raptor F22

The Boeing Raptor F22 is a twin-engine fighter aircraft powered by two Pratt & Whitney F119-PW-100 turbofans and has an MTOW of 83,500 lbs. HNTB recommends using the Boeing F-15E Strike Eagle (AEDT Equipment ID = 4235, ANP Code = F15E29, and BADA ID = FGTN) as a substitute. The Boeing F-15E Strike Eagle is a twin-engine fighter aircraft powered by two Pratt & Whitney F100-PW-229 turbofans and has an MTOW of 81,000 lbs. The Boeing Raptor F22 and Boeing F-15 Eagle have similar engines and MTOWs.

S22T - Cirrus SR22 Turbo

The Cirrus SR22 Turbo is a turbocharged version of the Cirrus SR-22. It has an MTOW of 3,600 lbs and is powered by a Tornado Alley turbonormalizing upgrade kit (310 hp) or a ground-boosted Continental TSIO-550K engine producing (315 hp). HNTB recommends using the Cirrus SR22 (AEDT Equipment ID = 1325, ANP Code = COMSEP, and BADA ID = SR22) as a substitute. Considering the relatively low altitude of Westover Airport (245ft), it is doubtful that the turbocharged version of the Cirrus SR22 produces considerably different noise signature than the standard version.

HNTB also proposes to apply the 30-year average temperature and pressure at CEF² as the AEDT default temperature and pressure are missing for CEF, as shown in **Table 2**. HNTB collected temperature and pressure data of the weather station 744910 – Westover AFB/Metropolitan Airport (between April 1989 and March 2018). The calculated average temperature and pressure, together with other AEDT default weather parameters, are recommended to be applied in the study.

Table 2
Temperature and Pressure

Parameter	AEDT Default	Recommended Value
Temperature	0	50.0 (°F)
Pressure	0	1,006.6 (millibars)

Sources: FAA AEDT 2d and NOAA, 2018.

We are requesting the approval or recommendation of five non-standard AEDT aircraft substitutions and 30-year average temperature and pressure for use in the Westover Part 150 and EA noise analysis. Should you have any additional questions, please do not hesitate to contact me. Thank you in advance for your consideration of this request.

Best regards,



Yue Xu, Ph.D., P.E.
Aviation/Environmental Planner
HNTB Corporation

² Global Summary of the Day, Climate Data Online, National Centers for Environmental Information, National Oceanic and Atmospheric Administration, <https://www.ncdc.noaa.gov/cdo-web/datasets>, accessed April 2018.



U.S. Department
of Transportation
**Federal Aviation
Administration**

Office of Environment and Energy

800 Independence Ave., S.W.
Washington, D.C. 20591

5/8/2018

Richard Doucette
Airports Division
Federal Aviation Administration,
New England Region
1200 District Avenue
Burlington, MA 01803

Dear Richard,

The Office of Environment and Energy (AEE) has received the memo dated April 19th 2018, referencing the Environmental Assessment at Westover Air Reserve Base/Metropolitan Airport (WARB/CEF) for the user defined AEDT aircraft substitutions and user entered atmospheric conditions listed below:

Aircraft Code	Aircraft Description	AEDT Model / Substitution Model	Recommended EQUIP_ID	ANP_ID	BADA_ID	AEE Requirement
BE35	Beech Bonanza 35	Raytheon Beech Bonanza 36	1276	CNA208	TBM8	Concur
DA40	Diamond Star DA40	EADS Socata TB-10 Tobago	1904	GASEPV	TB21	Concur
F22	Boeing Raptor F22	Boeing F-15E Strike Eagle	4235	F15E29	FGTN	Model with DOD NoiseMap
S22T	Cirrus SR-22 Turbo	Cirrus SR22	1325	COMSEP	SR22	Concur

AEE grants approval for all of the recommended substitutions **except** for the Boeing Raptor F22. Due to the unique noise and performance characteristics of fifth generation, military fighter aircraft AEE is unable to approve AEDT substitution requests for these aircraft. Noise modeling for F22 operations should therefore be conducted using the DOD NoiseMap model. The NoiseMap noise results should then be combined with the civil aircraft AEDT noise results, using tools available in AEDT.

Parameter	AEDT Default	Recommended Value	AEE Recommendation
Temperature (°F)	NA	50.0	Concur
Pressure (millibars)	NA	1,006.6	Concur
Sea Level Pressure (millibars)	1016.52		Update with NOAA data
Relative humidity (%)	65.33		Update with NOAA data
Dew Point (°F)	38.74		Update with NOAA data
[Average] Wind Speed (knots)	6.62		Update with NOAA data

AEE concurs with the use of the NOAA Global Summary of the Day, Climate Data Online, National Centers for Environmental Information Data for use in providing updated atmospheric data. Due to the lack of available temperature and pressure information in the AEDT standard database, AEE recommends that to ensure data consistency that all of the required parameters be updated to use the same NOAA data source.

Please understand that this approval is limited to this particular Environmental Assessment at Westover Air Reserve Base/Metropolitan Airport and that other non-standard AEDT inputs for additional projects at this or any other site will require separate approval.

Sincerely,

Rebecca Cointin
 Manager
 AEE-100/Noise Division

cc: Airports Contact (Jim Byers APP-400)



U.S. Department
of Transportation
**Federal Aviation
Administration**

Office of Environment and Energy

800 Independence Ave., S.W.
Washington, D.C. 20591

5/8/2018

Richard Doucette
Airports Division
Federal Aviation Administration,
New England Region
1200 District Avenue
Burlington, MA 01803

Dear Richard,

The Office of Environment and Energy (AEE) has received the memo dated April 19th 2018, referencing the 14 CFR Part 150 for Westover Air Reserve Base/Metropolitan Airport (WARB/CEF) for the user defined AEDT aircraft substitutions and user entered atmospheric conditions listed below:

Aircraft Code	Aircraft Description	AEDT Model / Substitution Model	Recommended EQUIP_ID	ANP_ID	BADA_ID	AEE Requirement
BE35	Beech Bonanza 35	Raytheon Beech Bonanza 36	1276	CNA208	TBM8	Concur
DA40	Diamond Star DA40	EADS Socata TB-10 Tobago	1904	GASEPV	TB21	Concur
F22	Boeing Raptor F22	Boeing F-15E Strike Eagle	4235	F15E29	FGTN	Model with DOD NoiseMap
S22T	Cirrus SR-22 Turbo	Cirrus SR22	1325	COMSEP	SR22	Concur

AEE grants approval for all of the recommended substitutions **except** for the Boeing Raptor F22. Due to the unique noise and performance characteristics of fifth generation, military fighter aircraft AEE is unable to approve AEDT substitution requests for these aircraft. Noise modeling for F22 operations should therefore be conducted using the DOD NoiseMap model. The NoiseMap noise results should then be combined with the civil aircraft AEDT noise results, using tools available in AEDT.

Parameter	AEDT Default	Recommended Value	AEE Recommendation
Temperature (°F)	NA	50.0	Concur
Pressure (millibars)	NA	1,006.6	Concur
Sea Level Pressure (millibars)	1016.52		Update with NOAA data
Relative humidity (%)	65.33		Update with NOAA data
Dew Point (°F)	38.74		Update with NOAA data
[Average] Wind Speed (knots)	6.62		Update with NOAA data

AEE concurs with the use of the NOAA Global Summary of the Day, Climate Data Online, National Centers for Environmental Information Data for use in providing updated atmospheric data. Due to the lack of available temperature and pressure information in the AEDT standard database, AEE recommends that to ensure data consistency that all of the required parameters be updated to use the same NOAA data source.

Please understand that this approval is limited to this particular 14 CFR Part 150 evaluation at Westover Air Reserve Base/Metropolitan Airport and that other non-standard AEDT inputs for additional projects at this or any other site will require separate approval.

Sincerely,




Rebecca Cointin
 Manager
 AEE-100/Noise Division

cc: Airports Contact (Jim Byers APP-400)

Appendix C – Flight Tracks and Profiles

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




Military flight tracks not shown; all remain consistent with the AICUZ.

USDA FSA APFO

LEGEND


- Civilian Arrival Flight Track
- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

Flight Tracks – Civilian Fixed Wing Arrival Figure C-1



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis

Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




Military flight tracks not shown; all remain consistent with the AICUZ.

USDA FSA APFO

LEGEND


- Civilian Departure Flight Track
- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

Flight Tracks – Civilian Fixed Wing Departure Figure C-2



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update



LEGEND


- Helicopter Arrival Flight Track
- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary

Flight Tracks – Civilian Helicopter Arrival
Figure C-3



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis


Westover Air Reserve Base / Metropolitan Airport NEM/NCP Update




LEGEND

- Helicopter Departure Flight Track
- Westover Air Reserve Base Installation Area
- Westover Metropolitan Development Corporation Aviation Property
- County Boundary
- Town Boundary


Flight Tracks – Civilian Helicopter Departure Figure C-4



Sources: Bureau of Geographic Information (MassGIS),
Commonwealth of Massachusetts,
Executive Office of Technology and Security Services,
WMDC 2018, HNTB GIS (2018),
Aerial - USDA 2016, ESRI Data and HNTB Analysis




Flight Profile C5A01
AFCEE - Arrival ~ 1




Scale in Feet 1:281,000 (1 inch = 23,400 feet)





Flight Profile C5A02
AFCEE - Arrival ~ 2




Scale in Feet 1:268,000 (1 inch = 22,300 feet)



Flight Profile C5A03


Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135



Flight Profile C5A03
AFCEE - Arrival ~ 3




Scale in Feet 1:205,000 (1 inch = 17,100 feet)



Flight Profile C5A04


Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135




Flight Profile C5A04
AFCEE - Arrival ~ 4




Scale in Feet 1:207,000 (1 inch = 17,300 feet)






Flight Profile C5A08				
Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135

Flight Profile C5A08
AFCEE - Arrival ~ 5



Scale in Feet 1:262,000 (1 inch = 21,900 feet)






Flight Profile C5A09


Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135

Flight Profile C5A09
AFCEE - Arrival ~ 6



Scale in Feet 1:221,000 (1 inch = 18,500 feet)







Flight Profile C5A10				
Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135

Flight Profile C5A10
AFCEE - Arrival ~ 7



Scale in Feet 1:237,000 (1 inch = 19,700 feet)





69,000 ft
2,310 ft AGL
75 % N1 Approach
180 kts

145,261 ft
3,310 ft AGL
65 % N1 Variable
215 kts

133,261 ft
2,310 ft AGL
65 % N1 Variable
210 kts

30,000 ft
1,810 ft AGL
75 % N1 Approach
135 kts

205,000 ft
4,310 ft AGL
65 % N1 Variable
250 kts


CCW 310°
CW 210°
2HP
3HP

6,000 ft
390 ft AGL
75 % N1 Approach
135 kts

0 ft
50 ft AGL
75 % N1 Approach
135 kts


9,000 ft
570 ft AGL
75 % N1 Approach
135 kts







Flight Profile C5A12				
Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135

Flight Profile C5A12
AFCEE - Arrival ~ 9



Scale in Feet 1:265,000 (1 inch = 22,100 feet)






Flight Profile C5A14

Point	Distance ft	Height ft	Power % N1	Speed kts
a	316,400	7,310 AGL	65 Variable	250
b	277,900	5,310 AGL	65 Variable	250
c	205,000	4,310 AGL	65 Variable	250
d	145,261	3,310 AGL	65 Variable	215
e	133,261	2,310 AGL	65 Variable	210
f	69,000	2,310 AGL	75 Approach	180
g	30,000	1,810 AGL	75 Approach	135
h	9,000	570 AGL	75 Approach	135
i	6,000	390 AGL	75 Approach	135
j	0	50 AGL	75 Approach	135

Flight Profile C5A14
AFCEE - Arrival ~ 10

Scale in Feet 1:224,000 (1 inch = 18,700 feet)




Flight Profile C5-05A
Closed Pattern ~ 1




Scale in Feet 1:188,000 (1 inch = 15,600 feet)






Flight Profile C5-05B
Closed Pattern ~ 2



Scale in Feet 1:129,000 (1 inch = 10,700 feet)





Flight Profile C5-05C


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	129
c	16,638	419 AGL	95 Takeoff	140
d	47,286	2,759 AGL	60 Cruise	230
e	91,851	2,759 AGL	60 Cruise	230
f	110,348	2,259 AGL	60 Cruise	230
g	138,871	2,259 AGL	60 Cruise	230
h	177,590	639 AGL	68 Approach	138
i	189,594	59 AGL	68 Approach	123

Flight Profile C5-05C
Closed Pattern ~ 3



Scale in Feet 1:120,000 (1 inch = 10,000 feet)






Flight Profile C5-05D


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	123
c	16,864	1,759 AGL	95 Takeoff	134
d	64,778	3,759 AGL	60 Cruise	210
e	128,665	3,759 AGL	60 Cruise	213
f	158,796	2,759 AGL	68 Approach	168
g	166,110	2,759 AGL	68 Approach	162
h	198,900	1,659 AGL	68 Approach	139
i	220,388	359 AGL	68 Approach	125
j	228,691	59 AGL	68 Approach	123

Flight Profile C5-05D
Closed Pattern ~ 4




Scale in Feet 1:144,000 (1 inch = 12,000 feet)







Flight Profile C5-05F
Closed Pattern ~ 5




Scale in Feet 1:159,000 (1 inch = 13,300 feet)






Flight Profile C5-05G
Closed Pattern ~ 6




Scale in Feet 1:141,000 (1 inch = 11,800 feet)







Flight Profile C5-05K				
Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	50 AGL	68 Approach	123
b	1,000	0 AGL	95 Takeoff	123
c	6,500	50 AGL	95 Takeoff	130
d	15,394	649 AGL	95 Takeoff	140
e	25,167	1,199 AGL	95 Takeoff	142
f	31,176	1,779 AGL	60 Cruise	175
g	50,941	1,759 AGL	60 Cruise	172
h	61,417	659 AGL	68 Approach	150
i	71,885	59 AGL	68 Approach	123

Flight Profile C5-05K
Closed Pattern ~ 7



Scale in Feet 1:43,100 (1 inch = 3,590 feet)





Flight Profile C5-15A


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	12,826	999 AGL	95 Takeoff	130
d	26,368	2,519 AGL	95 Takeoff	190
e	35,806	9,259 AGL	60 Cruise	230
f	70,335	9,259 AGL	60 Cruise	230
g	158,229	9,259 AGL	60 Cruise	230
h	217,689	9,259 AGL	68 Approach	135
i	291,712	699 AGL	68 Approach	151
j	302,200	59 AGL	68 Approach	123

Flight Profile C5-15A
Closed Pattern ~ 8




Scale in Feet 1:169,000 (1 inch = 14,100 feet)






Flight Profile C5-15B
Closed Pattern ~ 9



Scale in Feet 1:111,000 (1 inch = 9,230 feet)





89,987 ft
2,259 ft AGL
60 % N1 Cruise
230 kts

122,902 ft
2,259 ft AGL
60 % N1 Cruise
230 kts

172,035 ft
659 ft AGL
68 % N1 Approach
140 kts

44,114 ft
2,259 ft AGL
60 % N1 Cruise
230 kts

162,333 ft
959 ft AGL
60 % N1 Cruise
230 kts


0 ft
0 ft AGL
95 % N1 Takeoff
0 kts


10,867 ft
1,429 ft AGL
95 % N1 Takeoff
147 kts

184,817 ft
59 ft AGL
68 % N1 Approach
123 kts

5,000 ft
0 ft AGL
95 % N1 Takeoff
130 kts

2HP
815
CW SLING
12800






Flight Profile C5-15D


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	35,415	1,759 AGL	95 Takeoff	145
d	116,216	3,759 AGL	60 Cruise	210
e	150,277	2,959 AGL	68 Approach	155
f	173,092	2,609 AGL	68 Approach	150
g	208,097	2,059 AGL	68 Approach	150
h	219,107	709 AGL	68 Approach	150
i	236,450	59 AGL	68 Approach	123

Flight Profile C5-15D
Closed Pattern ~ 11



Scale in Feet 1:169,000 (1 inch = 14,100 feet)







Flight Profile C5-15E


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	35,415	1,759 AGL	95 Takeoff	145
d	113,891	3,759 AGL	60 Cruise	210
e	142,573	2,359 AGL	68 Approach	170
f	166,416	2,359 AGL	68 Approach	170
g	195,990	2,059 AGL	68 Approach	170
h	227,705	59 AGL	68 Approach	123

Flight Profile C5-15E
Closed Pattern ~ 12



Scale in Feet 1:167,000 (1 inch = 13,900 feet)





40,261 ft
1,759 ft AGL
68 % N1 Approach
158 kts

51,889 ft
689 ft AGL
68 % N1 Approach
138 kts

65,269 ft
59 ft AGL
68 % N1 Approach
122 kts

23,536 ft
1,759 ft AGL
60 % N1 Cruise
164 kts

2,835 ft
0 ft AGL
95 % N1 Takeoff
122 kts

14,175 ft
1,279 ft AGL
95 % N1 Takeoff
151 kts

7,744 ft
459 ft AGL
95 % N1 Takeoff
134 kts


0 ft
50 ft AGL
68 % N1 Approach
122 kts

CCW_SLING
CW_SLING


14DZ

32DZ
32DZ 2

23




Flight Profile C5-23A
Closed Pattern ~ 14



Scale in Feet 1:160,000 (1 inch = 13,300 feet)






Flight Profile C5-23B



Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	128
c	15,836	1,759 AGL	95 Takeoff	144
d	24,289	3,519 AGL	95 Takeoff	210
e	61,058	5,259 AGL	60 Cruise	230
f	106,204	5,259 AGL	60 Cruise	230
g	153,412	5,259 AGL	60 Cruise	230
h	182,550	5,259 AGL	68 Approach	135
i	201,365	629 AGL	68 Approach	134
j	214,032	59 AGL	68 Approach	123



Flight Profile C5-23B
Closed Pattern ~ 15




Scale in Feet 1:113,000 (1 inch = 9,400 feet)












Flight Profile C5-23E
Closed Pattern ~ 18



Scale in Feet 1:160,000 (1 inch = 13,300 feet)






Flight Profile C5-23F				
Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	121
c	11,974	959 AGL	95 Takeoff	132
d	47,130	3,759 AGL	60 Cruise	210
e	128,868	3,759 AGL	60 Cruise	210
f	155,433	3,759 AGL	60 Cruise	210
g	168,985	2,759 AGL	68 Approach	170
h	211,394	2,759 AGL	68 Approach	170
i	230,718	959 AGL	68 Approach	150
j	246,119	959 AGL	68 Approach	150
k	262,054	759 AGL	68 Approach	140
l	268,271	59 AGL	68 Approach	123



Flight Profile C5-23F
Closed Pattern ~ 19

Scale in Feet 1:160,000 (1 inch = 13,300 feet)





Flight Profile C5-23K


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	50 AGL	68 Approach	123
b	1,000	0 AGL	95 Takeoff	123
c	3,602	0 AGL	95 Takeoff	136
d	11,693	769 AGL	95 Takeoff	145
e	20,992	1,274 AGL	95 Takeoff	172
f	32,037	1,759 AGL	60 Cruise	170
g	42,347	1,759 AGL	75 Cruise	172
h	51,361	829 AGL	68 Approach	150
i	64,593	59 AGL	68 Approach	123

Flight Profile C5-23K
Closed Pattern ~ 21



Scale in Feet 1:38,100 (1 inch = 3,180 feet)





98,427 ft
9,259 ft AGL
60 % N1 Cruise
230 kts

170,834 ft
9,259 ft AGL
60 % N1 Cruise
230 kts

5,000 ft
0 ft AGL
95 % N1 Takeoff
129 kts

0 ft
0 ft AGL
95 % N1 Takeoff
0 kts

327,941 ft
609 ft AGL
68 % N1 Approach
145 kts

8,881 ft
1,599 ft AGL
95 % N1 Takeoff
152 kts


25,000 ft
3,345 ft AGL
95 % N1 Takeoff
237 kts

339,429 ft
59 ft AGL
68 % N1 Approach
123 kts


272,869 ft
9,259 ft AGL
60 % N1 Cruise
135 kts

242,152 ft
9,259 ft AGL
60 % N1 Cruise
230 kts






Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	129
c	19,427	1,599 AGL	95 Takeoff	152
d	31,752	3,345 AGL	95 Takeoff	237
e	59,782	5,259 AGL	60 Cruise	230
f	102,733	5,259 AGL	60 Cruise	230
g	150,580	5,259 AGL	60 Cruise	230
h	176,779	5,259 AGL	68 Approach	135
i	206,745	859 AGL	68 Approach	150
j	215,549	59 AGL	68 Approach	123



Scale in Feet 1:138,000 (1 inch = 11,500 feet)







Flight Profile C5-33C



Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	95 Takeoff	0
b	5,000	0 AGL	95 Takeoff	129
c	7,428	409 AGL	95 Takeoff	137
d	40,384	5,259 AGL	60 Cruise	230
e	85,316	5,259 AGL	60 Cruise	230
f	133,270	5,259 AGL	60 Cruise	230
g	183,915	859 AGL	68 Approach	150
h	193,854	59 AGL	68 Approach	123



Flight Profile C5-33C
Closed Pattern ~ 24




Scale in Feet 1:128,000 (1 inch = 10,700 feet)









14,322 ft
1,389 ft AGL
95 % N1 Takeoff
160 kts

23,787 ft
1,759 ft AGL
60 % N1 Cruise
170 kts

7,408 ft
409 ft AGL
95 % N1 Takeoff
137 kts

CW SLING
SW SLING

3,559 ft
0 ft AGL
95 % N1 Takeoff
129 kts

1,000 ft
0 ft AGL
95 % N1 Takeoff
123 kts

35,160 ft
1,759 ft AGL
60 % N1 Cruise
175 kts

0 ft
50 ft AGL
68 % N1 Approach
123 kts

62,407 ft
59 ft AGL
68 % N1 Approach
123 kts

56,188 ft
359 ft AGL
68 % N1 Approach
123 kts

47,597 ft
759 ft AGL
60 % N1 Cruise
135 kts

Flight Profile C5-33I


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	50 AGL	68 Approach	123
b	1,000	0 AGL	95 Takeoff	123
c	3,559	0 AGL	95 Takeoff	129
d	7,408	409 AGL	95 Takeoff	137
e	14,322	1,389 AGL	95 Takeoff	160
f	23,787	1,759 AGL	60 Cruise	170
g	35,160	1,759 AGL	60 Cruise	175
h	47,597	759 AGL	60 Cruise	135
i	56,188	359 AGL	68 Approach	123
j	62,407	59 AGL	68 Approach	123

Flight Profile C5-33I
Closed Pattern ~ 27





Scale in Feet 1:39,200 (1 inch = 3,270 feet)






Flight Profile C5-05H

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250






Flight Profile C5-05I
Departure ~ 2



Scale in Feet 1:101,000 (1 inch = 8,390 feet)






Flight Profile C5-05J


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

Flight Profile C5-05J
Departure ~ 3



Scale in Feet 1:46,500 (1 inch = 3,880 feet)






Flight Profile C5-15F


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

Flight Profile C5-15F
Departure ~ 4





Scale in Feet 1:87,400 (1 inch = 7,280 feet)






Flight Profile C5-15G

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250






Flight Profile C5-15H


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

Flight Profile C5-15H
Departure ~ 6





Scale in Feet 1:88,600 (1 inch = 7,390 feet)





Flight Profile C5-23H

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250



Flight Profile C5-23I

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

70,000 ft
4,310 ft AGL
95 % N1 Takeoff
250 kts

38,550 ft
3,310 ft AGL
95 % N1 Takeoff
250 kts

20,550 ft
1,000 ft AGL
95 % N1 Takeoff
160 kts


5,000 ft
0 ft AGL
95 % N1 Takeoff
130 kts

0 ft
0 ft AGL
102 % N1 Takeoff
0 kts

15
14DZ
3388Z
CCW_SLING
CW_SLING
33


2HP
310

Flight Profile C5-23I
Departure ~ 8



Scale in Feet 1:87,400 (1 inch = 7,280 feet)






Flight Profile C5-23J
Departure ~ 9





Scale in Feet 1:96,300 (1 inch = 8,020 feet)





Flight Profile C5-33F

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250



Flight Profile C5-33G

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

38,550 ft
3,310 ft AGL
95 % N1 Takeoff
250 kts

70,000 ft
4,310 ft AGL
95 % N1 Takeoff
250 kts

20,550 ft
1,000 ft AGL
95 % N1 Takeoff
160 kts

5,000 ft
0 ft AGL
95 % N1 Takeoff
130 kts

0 ft
0 ft AGL
102 % N1 Takeoff
0 kts


CCW_SLING
CW_SLING
ADZ
BBZ

Flight Profile C5-33G
Departure ~ 11



Scale in Feet 1:99,800 (1 inch = 8,320 feet)






Flight Profile C5-33H

Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	102 Takeoff	0
b	5,000	0 AGL	95 Takeoff	130
c	20,550	1,000 AGL	95 Takeoff	160
d	38,550	3,310 AGL	95 Takeoff	250
e	70,000	4,310 AGL	95 Takeoff	250
f	200,000	12,300 AGL	95 Takeoff	250

Flight Profile C5-33H
Departure ~ 12

Scale in Feet 1:59,300 (1 inch = 4,940 feet)



Flight Profile CH47C1


Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Lfo Lite 70 kts
b	100	0 AGL	Tkf Load 70 kts
c	150	50 AGL	Tkf Load 70 kts
d	24,214	750 AGL	Lfo Lite 135 kts
e	48,214	750 AGL	Lfo Lite 70 kts
f	55,742	500 AGL	Lfo Lite 70 kts
g	60,741	10 AGL	Lfo Lite 70 kts

Flight Profile CH47C1
CH47 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:36,800 (1 inch = 3,060 feet)





Flight Profile CH47C2


Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Lfo Lite 70 kts
b	25	0 AGL	Tkf Load 70 kts
c	50	50 AGL	Tkf Load 70 kts
d	24,214	750 AGL	Lfo Lite 135 kts
e	48,214	750 AGL	Lfo Lite 70 kts
f	55,742	500 AGL	Lfo Lite 70 kts
g	60,741	10 AGL	Lfo Lite 70 kts

Flight Profile CH47C2
CH47 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:36,800 (1 inch = 3,060 feet)







Flight Profile CH47C3

Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Lfo Lite 70 kts
b	1,000	500 AGL	Tkf Load 70 kts
c	6,000	959 AGL	Lfo Lite 135 kts
d	12,000	959 AGL	Lfo Lite 135 kts
e	286,190	959 AGL	Lfo Lite 70 kts
f	298,189	50 AGL	Lfo Lite 70 kts


Flight Profile CH47C3
CH47 HELICOPTERS DROP ZONE OPERATIONS



Scale in Feet 1:222,000 (1 inch = 18,500 feet)




Flight Profile CH47C4			
Point	Distance ft	Height ft	Power KNOTS
a	0	759 AGL	Lfo Lite 70 kts
b	1,000	759 AGL	Tkf Load 70 kts
c	6,322	759 AGL	Lfo Lite 135 kts
d	10,322	759 AGL	Lfo Lite 70 kts
e	14,321	759 AGL	Lfo Lite 70 kts




Flight Profile CH47C4
CH47 HELICOPTERS DROP ZONE OPERATIONS

Scale in Feet 1:8,960 (1 inch = 747 feet)

Flight Profile CH47C5			
Point	Distance ft	Height ft	Power KNOTS
a	0	759 AGL	Lfo Lite 70 kts
b	1,000	759 AGL	Tkf Load 70 kts
c	6,322	759 AGL	Lfo Lite 135 kts
d	10,322	759 AGL	Lfo Lite 70 kts
e	14,321	759 AGL	Lfo Lite 70 kts



Flight Profile CH47C5
CH47 HELICOPTERS DROP ZONE OPERATIONS




Scale in Feet 1:8,960 (1 inch = 747 feet)




Flight Profile CH47C6

Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Lfo Lite 70 kts
b	25	0 AGL	Tkf Load 70 kts
c	50	50 AGL	Tkf Load 70 kts
d	16,378	750 AGL	Lfo Lite 135 kts
e	31,528	750 AGL	Lfo Lite 70 kts
f	35,842	500 AGL	Lfo Lite 70 kts
g	40,841	10 AGL	Lfo Lite 70 kts




Flight Profile CH47C6
CH47 HELICOPTERS FLYING PATTERNS




Scale in Feet 1:28,200 (1 inch = 2,350 feet)






Flight Profile CH47C7

Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Lfo Lite 70 kts
b	150	50 AGL	Tkf Load 70 kts
c	250	50 AGL	Tkf Load 70 kts
d	3,250	759 AGL	Tkf Load 70 kts
e	8,022	759 AGL	Lfo Lite 70 kts
f	9,926	50 AGL	Lfo Lite 70 kts




Flight Profile CH47C7
CH47 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:7,170 (1 inch = 597 feet)






Flight Profile CH47C8


Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Lfo Lite 70 kts
b	150	50 AGL	Tkf Load 70 kts
c	250	50 AGL	Tkf Load 70 kts
d	3,250	759 AGL	Tkf Load 70 kts
e	8,022	759 AGL	Lfo Lite 70 kts
f	9,926	50 AGL	Lfo Lite 70 kts

Flight Profile CH47C8
CH47 HELICOPTERS FLYING PATTERNS





Scale in Feet 1:7,170 (1 inch = 597 feet)







Flight Profile UH60A1

Point	Distance ft	Height ft	Power KNOTS
a	200,000	750 AGL	Flyover 150 kts
b	30,000	750 AGL	Flyover 150 kts
c	5,500	750 AGL	Approach 69 kts
d	0	50 AGL	Approach 69 kts






Flight Profile UH60A2
 Frequency that the aircraft come in to fly patterns was prov



Scale in Feet 1:262,000 (1 inch = 21,900 feet)








Flight Profile UH60A3

Point	Distance ft	Height ft	Power KNOTS
a	200,000	2,250 AGL	Flyover 150 kts
b	43,800	2,250 AGL	Approach 69 kts
c	25,800	1,650 AGL	Approach 69 kts
d	13,800	750 AGL	Approach 69 kts
e	6,800	500 AGL	Approach 69 kts
f	0	50 AGL	Approach 69 kts

Flight Profile UH60A3
Frequency that the aircraft come in to fly patterns was prov

Scale in Feet 1:237,000 (1 inch = 19,700 feet)






Flight Profile BUH60C7



Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Approach 69 kts
b	150	50 AGL	Takeoff 74 kts
c	250	50 AGL	Takeoff 74 kts
d	3,250	759 AGL	Takeoff 74 kts
e	8,022	759 AGL	Approach 69 kts
f	9,926	50 AGL	Approach 69 kts

Flight Profile BUH60C7
BARNES UH-60 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:7,170 (1 inch = 597 feet)







Flight Profile BUH60C8


Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Approach 69 kts
b	150	50 AGL	Takeoff 74 kts
c	250	50 AGL	Takeoff 74 kts
d	3,250	759 AGL	Takeoff 74 kts
e	8,022	759 AGL	Approach 69 kts
f	9,926	50 AGL	Approach 69 kts

Flight Profile BUH60C8
BARNES UH-60 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:7,170 (1 inch = 597 feet)





Flight Profile UH60C1


Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Approach 69 kts
b	100	0 AGL	Takeoff 74 kts
c	150	50 AGL	Takeoff 74 kts
d	24,214	750 AGL	Flyover 150 kts
e	48,214	750 AGL	Approach 69 kts
f	55,742	500 AGL	Approach 69 kts
g	60,741	10 AGL	Approach 69 kts

Flight Profile UH60C1
UH60/HH60 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:36,800 (1 inch = 3,060 feet)





Flight Profile UH60C2


Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Approach 69 kts
b	25	0 AGL	Takeoff 74 kts
c	50	50 AGL	Takeoff 74 kts
d	24,214	750 AGL	Flyover 150 kts
e	48,214	750 AGL	Approach 69 kts
f	55,742	500 AGL	Approach 69 kts
g	60,741	10 AGL	Approach 69 kts

Flight Profile UH60C2
UH60/HH60 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:36,800 (1 inch = 3,060 feet)






Flight Profile UH60C3

Point	Distance ft	Height ft	Power KNOTS
a	0	50 AGL	Approach 69 kts
b	1,000	500 AGL	Takeoff 74 kts
c	6,000	959 AGL	Flyover 150 kts
d	12,000	959 AGL	Flyover 150 kts
e	286,190	959 AGL	Approach 69 kts
f	298,189	50 AGL	Approach 69 kts


Flight Profile UH60C3
UH60/HH60 HELICOPTERS DROP ZONE OPERATIONS



Scale in Feet 1:222,000 (1 inch = 18,500 feet)




Flight Profile UH60C4			
Point	Distance ft	Height ft	Power KNOTS
a	0	759 AGL	Approach 69 kts
b	1,000	759 AGL	Takeoff 74 kts
c	6,322	759 AGL	Flyover 150 kts
d	10,322	759 AGL	Approach 69 kts
e	14,321	759 AGL	Approach 69 kts



Flight Profile UH60C4
UH60/HH60 HELICOPTERS DROP ZONE OPERATIONS


Scale in Feet 1:8,960 (1 inch = 747 feet)

Flight Profile UH60C5			
Point	Distance ft	Height ft	Power KNOTS
a	0	759 AGL	Approach 69 kts
b	1,000	759 AGL	Takeoff 74 kts
c	6,322	759 AGL	Flyover 150 kts
d	10,322	759 AGL	Approach 69 kts
e	14,321	759 AGL	Approach 69 kts




Flight Profile UH60C5
 UH60/HH60 HELICOPTERS DROP ZONE OPERATIONS

Scale in Feet 1:8,960 (1 inch = 747 feet)




Flight Profile UH60C6

Point	Distance ft	Height ft	Power KNOTS
a	0	10 AGL	Approach 69 kts
b	25	0 AGL	Takeoff 74 kts
c	50	50 AGL	Takeoff 74 kts
d	16,378	750 AGL	Flyover 150 kts
e	31,528	750 AGL	Approach 69 kts
f	35,842	500 AGL	Approach 69 kts
g	40,841	10 AGL	Approach 69 kts




Flight Profile UH60C6
UH60/HH60 HELICOPTERS FLYING PATTERNS



Scale in Feet 1:28,200 (1 inch = 2,350 feet)





200,000 ft
750 ft AGL
Flyover 150 kts

30,000 ft
750 ft AGL
Flyover 150 kts


0 ft
0 ft AGL
Takeoff 74 kts


50 ft
0 ft AGL
Takeoff 74 kts

9,600 ft
500 ft AGL
Flyover 150 kts

CW
74
KTS
74
KTS
74
KTS









Flight Profile UH60D3


Point	Distance ft	Height ft	Power KNOTS
a	0	0 AGL	Takeoff 74 kts
b	50	0 AGL	Takeoff 74 kts
c	9,600	500 AGL	Flyover 150 kts
d	30,000	750 AGL	Flyover 150 kts
e	200,000	750 AGL	Flyover 150 kts

Flight Profile UH60D3
UH60/HH60 HELICOPTERS FLYING PATTERNS

Scale in Feet 1:389,000 (1 inch = 32,400 feet)








Flight Profile C130A2				
Point	Distance ft	Height ft	Power C TIT	Speed kts
a	200,000	10,532 AGL	932 Variable	170
b	47,201	2,524 AGL	932 Variable	150
c	15,178	845 AGL	932 Variable	110
d	0	50 AGL	932 Variable	110

Flight Profile C130A2
Transient C-130



Scale in Feet 1:262,000 (1 inch = 21,900 feet)





Flight Profile C130A3

Point	Distance ft	Height ft	Power C TIT	Speed kts
a	200,000	10,532 AGL	932 Variable	170
b	47,201	2,524 AGL	932 Variable	150
c	15,178	845 AGL	932 Variable	110
d	0	50 AGL	932 Variable	110


47,201 ft
2,524 ft AGL
932 C TIT Variable
150 kts

Flight Profile C130A3
Transient C-130





Scale in Feet 1:76,100 (1 inch = 6,340 feet)






Flight Profile DZC130A1

Point	Distance ft	Height ft	Power C TIT	Speed kts
a	200,000	4,959 AGL	932 Variable	170
b	47,201	4,959 AGL	932 Variable	150
c	15,178	959 AGL	932 Variable	110
d	0	959 AGL	932 Variable	110





15,000 ft
2,750 ft AGL
932 C TIT Variable
170 kts

3,000 ft
1,000 ft AGL
977 C TIT Variable
140 kts

0 ft
1,000 ft AGL
977 C TIT Variable
140 kts

274,000 ft
759 ft AGL
932 C TIT Variable
150 kts

298,189 ft
759 ft AGL
932 C TIT Variable
140 kts

278,000 ft
759 ft AGL
932 C TIT Variable
150 kts


200,000 ft
500 ft AGL
932 C TIT Variable
150 kts

190,000 ft
2,750 ft AGL
932 C TIT Variable
170 kts


Flight Profile DZC130C1



Point	Distance ft	Height ft	Power C TIT	Speed kts
a	0	1,000 AGL	977 Variable	140
b	3,000	1,000 AGL	977 Variable	140
c	15,000	2,750 AGL	932 Variable	170
d	190,000	2,750 AGL	932 Variable	170
e	200,000	500 AGL	932 Variable	150
f	274,000	759 AGL	932 Variable	150
g	278,000	759 AGL	932 Variable	150
h	298,189	759 AGL	932 Variable	140


Flight Profile DZC130C1
Transient C-130 - Drop Zone Operations at 1000 MSL



Scale in Feet 1:222,000 (1 inch = 18,500 feet)








Flight Profile C130D1


Point	Distance ft	Height ft	Power C TIT	Speed kts
a	0	0 AGL	970 Variable	0
b	4,800	0 AGL	977 Variable	105
c	13,500	300 AGL	977 Variable	130
d	38,190	2,820 AGL	932 Variable	170
e	108,562	8,588 AGL	932 Variable	170
f	155,000	8,588 AGL	932 Variable	170

Flight Profile C130D1
Transient C-130





Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile C130D2

Point	Distance ft	Height ft	Power C TIT	Speed kts
a	0	0 AGL	970 Variable	0
b	4,800	0 AGL	977 Variable	105
c	13,500	300 AGL	977 Variable	130
d	38,190	2,820 AGL	932 Variable	170
e	108,562	8,588 AGL	932 Variable	170
f	200,000	8,588 AGL	932 Variable	170







Flight Profile C130D3


Point	Distance ft	Height ft	Power C TIT	Speed kts
a	0	0 AGL	970 Variable	0
b	4,800	0 AGL	977 Variable	105
c	13,500	300 AGL	977 Variable	130
d	38,190	2,820 AGL	932 Variable	170
e	108,562	8,588 AGL	932 Variable	170
f	200,000	8,588 AGL	932 Variable	170

Flight Profile C130D3
Transient C-130




Scale in Feet 1:53,600 (1 inch = 4,460 feet)






Flight Profile C17A1
Transient operations



Scale in Feet 1:144,000 (1 inch = 12,000 feet)






Flight Profile C17A2


Point	Distance ft	Height ft	Power EPR	Speed kts
a	200,000	6,954 AGL	1.1 Variable	250
b	100,000	2,954 AGL	1.1 Variable	230
c	60,377	1,554 AGL	1.3 Parallel	160
d	39,000	1,554 AGL	1.3 Parallel	160
e	27,000	1,515 AGL	1.1 Parallel	130
f	0	50 AGL	1.1 Parallel	120

Flight Profile C17A2
Transient operations



Scale in Feet 1:262,000 (1 inch = 21,900 feet)






Flight Profile C17A3

Point	Distance ft	Height ft	Power EPR	Speed kts
a	200,000	6,954 AGL	1.1 Variable	250
b	100,000	2,954 AGL	1.1 Variable	230
c	60,377	1,554 AGL	1.3 Parallel	160
d	39,000	1,554 AGL	1.3 Parallel	160
e	27,000	1,515 AGL	1.1 Parallel	130
f	0	50 AGL	1.1 Parallel	120


100,000 ft
2,954 ft AGL
1.1 EPR Variable
230 kts

Flight Profile C17A3
Transient operations



Scale in Feet 1:150,000 (1 inch = 12,500 feet)






Flight Profile C17D1


Point	Distance ft	Height ft	Power EPR	Speed kts
a	0	0 AGL	1.4 Variable	0
b	5,000	0 AGL	1.42 Variable	140
c	18,000	1,000 AGL	1.25 Variable	165
d	20,000	1,200 AGL	1.25 Variable	250
e	40,000	3,200 AGL	1.25 Variable	250
f	155,000	10,000 AGL	1.25 Variable	250

Flight Profile C17D1
Transient operations



Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile C17D2
Transient operations



Scale in Feet 1:83,000 (1 inch = 6,920 feet)







Flight Profile C17D3


Point	Distance ft	Height ft	Power EPR	Speed kts
a	0	0 AGL	1.4 Variable	0
b	5,000	0 AGL	1.42 Variable	140
c	18,000	1,000 AGL	1.25 Variable	165
d	20,000	1,200 AGL	1.25 Variable	250
e	40,000	3,200 AGL	1.25 Variable	250
f	200,000	10,000 AGL	1.25 Variable	250

Flight Profile C17D3
Transient operations



Scale in Feet 1:56,100 (1 inch = 4,670 feet)






Flight Profile E3A1


Point	Distance ft	Height ft	Power EPR	Speed kts
a	200,000	9,850 AGL	1.12 Variable	250
b	84,000	4,400 AGL	1.5 Variable	220
c	36,000	1,900 AGL	1.6 Variable	150
d	0	50 AGL	1.5 Variable	135

Flight Profile E3A1
Arrival ~ 1



Scale in Feet 1:123,000 (1 inch = 10,300 feet)







Flight Profile E3D1

Point	Distance ft	Height ft	Power EPR	Speed kts
a	0	0 AGL	1.84 Variable	0
b	8,000	0 AGL	1.8 Variable	140
c	12,000	500 AGL	1.75 Variable	170
d	30,100	1,850 AGL	1.75 Variable	170
e	35,000	2,350 AGL	1.5 Variable	150
f	63,400	3,850 AGL	1.7 Variable	250
g	200,000	15,000 AGL	1.7 Variable	260

Flight Profile E3D1
Departure ~ 1

Scale in Feet 1:58,800 (1 inch = 4,900 feet)






Flight Profile E3D2


Point	Distance ft	Height ft	Power EPR	Speed kts
a	0	0 AGL	1.84 Variable	0
b	8,000	0 AGL	1.8 Variable	140
c	12,000	500 AGL	1.75 Variable	170
d	30,100	1,850 AGL	1.75 Variable	170
e	35,000	2,350 AGL	1.5 Variable	150
f	63,400	3,850 AGL	1.7 Variable	250
g	200,000	15,000 AGL	1.7 Variable	260

Flight Profile E3D2
Departure ~ 2




Scale in Feet 1:87,700 (1 inch = 7,310 feet)






Flight Profile F15A1
Transient operations




Scale in Feet 1:127,000 (1 inch = 10,600 feet)






Flight Profile F15D1
Transient operations



Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile F15D2
Transient operations



Scale in Feet 1:83,000 (1 inch = 6,920 feet)






Flight Profile F22 Arrival


Point	Distance ft	Height ft	Power % ETR	Speed kts
a	200,000	18,000 AGL	86 Variable	300
b	140,000	15,000 AGL	83 Variable	300
c	87,000	4,550 AGL	82 Variable	250
d	33,000	1,725 AGL	84 Variable	180
e	0	50 AGL	72.4 Variable	135

Flight Profile F22 Arrival
F22 Transient



Scale in Feet 1:127,000 (1 inch = 10,600 feet)






Flight Profile F22 Departure 1


Point	Distance ft	Height ft	Power % ETR	Speed kts
a	0	0 AGL	90 Variable	0
b	4,000	0 AGL	90 Variable	150
c	15,000	1,000 AGL	92 Variable	300
d	75,600	10,000 AGL	92 Variable	330
e	100,000	15,000 AGL	90 Variable	350
f	200,000	18,000 AGL	90 Variable	350

Flight Profile F22 Departure 1
F22 Transient



Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile F22 Departure 2
F22 Transient




Scale in Feet 1:83,000 (1 inch = 6,920 feet)






Flight Profile KC10A1
Transient operations




Scale in Feet 1:53,200 (1 inch = 4,440 feet)






Flight Profile KC10A2
Transient operations



Scale in Feet 1:262,000 (1 inch = 21,900 feet)






Flight Profile KC10D1


Point	Distance ft	Height ft	Power % N1	Speed kts
a	0	0 AGL	93 Variable	0
b	30	0 AGL	93 Variable	30
c	4,500	0 AGL	93 Variable	130
d	11,000	500 AGL	93 Variable	160
e	18,250	1,200 AGL	93 Variable	200
f	29,100	1,950 AGL	90 Variable	250
g	70,000	7,000 AGL	90 Variable	250
h	155,000	12,000 AGL	90 Variable	300

Flight Profile KC10D1
Transient operations



Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile KC10D2
Transient operations



Scale in Feet 1:83,000 (1 inch = 6,920 feet)






Flight Profile KC135A1


Point	Distance ft	Height ft	Power % NC	Speed kts
a	200,000	10,532 AGL	85.5 Parallel	250
b	30,400	1,643 AGL	85.5 Parallel	160
c	0	50 AGL	85.5 Parallel	160

Flight Profile KC135A1
Transient operations



Scale in Feet 1:53,200 (1 inch = 4,440 feet)






Flight Profile KC135A2


Point	Distance ft	Height ft	Power % NC	Speed kts
a	200,000	10,532 AGL	85.5 Parallel	250
b	30,400	1,643 AGL	85.5 Parallel	160
c	0	50 AGL	85.5 Parallel	160

Flight Profile KC135A2
Transient operations



Scale in Feet 1:262,000 (1 inch = 21,900 feet)






Flight Profile KC135D1

Point	Distance ft	Height ft	Power % NC	Speed kts
a	0	0 AGL	89.6 Variable	0
b	8,000	0 AGL	89.6 Variable	160
c	10,000	200 AGL	89.6 Variable	160
d	18,000	1,000 AGL	89.6 Variable	200
e	26,000	1,000 AGL	89.6 Variable	250
f	80,000	6,400 AGL	89.6 Variable	250
g	150,000	13,000 AGL	86.6 Variable	300

Flight Profile KC135D1
Transient operations

Scale in Feet 1:52,200 (1 inch = 4,350 feet)



Flight Profile KC135D2


Point	Distance ft	Height ft	Power % NC	Speed kts
a	0	0 AGL	89.6 Variable	0
b	8,000	0 AGL	89.6 Variable	160
c	10,000	200 AGL	89.6 Variable	160
d	18,000	1,000 AGL	89.6 Variable	200
e	26,000	1,000 AGL	89.6 Variable	250
f	80,000	6,400 AGL	89.6 Variable	250
g	150,000	13,000 AGL	86.6 Variable	300
h	200,000	13,000 AGL	86.6 Variable	300

Flight Profile KC135D2
Transient operations




Scale in Feet 1:83,000 (1 inch = 6,920 feet)






Flight Profile P3A1
Arrival ~ 1



Scale in Feet 1:134,000 (1 inch = 11,100 feet)






Flight Profile P3A2


Point	Distance ft	Height ft	Power ESHP	Speed kts
a	200,000	10,532 AGL	5325 Variable	250
b	90,000	5,000 AGL	5325 Variable	250
c	30,000	1,575 AGL	5225 Variable	130
d	6,000	300 AGL	5000 Variable	130
e	0	50 AGL	5000 Variable	130

Flight Profile P3A2
Arrival ~ 2



Scale in Feet 1:262,000 (1 inch = 21,900 feet)






3,500 ft
0 ft AGL
4600 ESHP Variable
115 kts

0 ft
0 ft AGL
3800 ESHP Variable
0 kts

16,000 ft
1,000 ft AGL
3000 ESHP Variable
210 kts


Flight Profile P3D1				
Point	Distance ft	Height ft	Power ESHP	Speed kts
a	0	0 AGL	3800 Variable	0
b	3,500	0 AGL	4600 Variable	115
c	16,000	1,000 AGL	3000 Variable	210
d	100,000	7,700 AGL	3000 Variable	210
e	200,000	10,000 AGL	3000 Variable	210

Flight Profile P3D1
Departure ~ 1



Scale in Feet 1:52,200 (1 inch = 4,350 feet)






Flight Profile P3D2
Departure ~ 2




Scale in Feet 1:83,000 (1 inch = 6,920 feet)






Flight Profile T38AA1
Arrival ~ 1





Scale in Feet 1:91,800 (1 inch = 7,650 feet)






Flight Profile T38AA2

Point	Distance ft	Height ft	Power % RPM	Speed kts
a	200,000	8,000 AGL	90 Variable	250
b	60,000	3,100 AGL	88 Variable	240
c	24,600	1,300 AGL	92 Variable	160
d	0	50 AGL	88 Variable	155





2HP
15
14DZ
CW SLING
CCW SLING
33


24,600 ft
1,300 ft AGL
92 % RPM Variable
160 kts

60,000 ft
3,100 ft AGL
88 % RPM Variable
240 kts

0 ft
50 ft AGL
88 % RPM Variable
155 kts


Flight Profile T38AA3

Point	Distance ft	Height ft	Power % RPM	Speed kts
a	200,000	8,000 AGL	90 Variable	250
b	60,000	3,100 AGL	88 Variable	240
c	24,600	1,300 AGL	92 Variable	160
d	0	50 AGL	88 Variable	155



Flight Profile T38AD1

Point	Distance ft	Height ft	Power % RPM	Speed kts
a	0	0 AGL	100 Max A/B	0
b	3,500	0 AGL	100 Afterburner	160
c	10,000	650 AGL	100 Variable	250
d	16,000	1,500 AGL	100 Variable	300
e	28,000	3,000 AGL	100 Variable	300
f	57,300	7,000 AGL	100 Variable	300
g	72,300	9,000 AGL	100 Variable	300
h	100,000	13,000 AGL	100 Variable	300
i	200,000	20,000 AGL	96 Variable	300




Flight Profile T38AD1
Departure ~ 1



Scale in Feet 1:36,500 (1 inch = 3,050 feet)





Flight Profile T38AD2


Point	Distance ft	Height ft	Power % RPM	Speed kts
a	0	0 AGL	100 Max A/B	0
b	3,500	0 AGL	100 Afterburner	160
c	10,000	650 AGL	100 Variable	250
d	16,000	1,500 AGL	100 Variable	300
e	28,000	3,000 AGL	100 Variable	300
f	57,300	7,000 AGL	100 Variable	300
g	72,300	9,000 AGL	100 Variable	300
h	100,000	13,000 AGL	100 Variable	300
i	200,000	20,000 AGL	96 Variable	300

Flight Profile T38AD2
Departure ~ 2



Scale in Feet 1:36,500 (1 inch = 3,040 feet)





Flight Profile T38AD3

Point	Distance ft	Height ft	Power % RPM	Speed kts
a	0	0 AGL	100 Max A/B	0
b	3,500	0 AGL	100 Afterburner	160
c	10,000	650 AGL	100 Variable	250
d	16,000	1,500 AGL	100 Variable	300
e	28,000	3,000 AGL	100 Variable	300
f	57,300	7,000 AGL	100 Variable	300
g	72,300	9,000 AGL	100 Variable	300
h	100,000	13,000 AGL	100 Variable	300
i	200,000	20,000 AGL	96 Variable	300

